

Public Hearings:

5:55 PM Assignment of Permanent Zoning

6:10 PM Rezoning Request

6:20 PM Proposed Code Amendment



**CITY OF PERRYSBURG
CITY COUNCIL
AGENDA**

March 7, 2023

1. Call to Order - 6:30 PM
2. Roll Call
3. Pledge of Allegiance
4. Minutes of Council Meeting of February 21, 2023
5. Special Reports
 - a. Update from CVB
6. Letters, Communications, and Citizens Communications
7. Administrative Reports
 - a. Mayor
 - b. City Administrator
 - c. Finance Director
 - d. Law Director
8. President of Council Report
9. Committee Reports

a. Finance & Economic Development

ORDINANCE 1-2023

AMENDING ORDINANCE 56-2022 TO AMEND APPROPRIATIONS FOR
CURRENT EXPENSES AND OTHER EXPENDITURES FOR THE YEAR
ENDING DECEMBER 31, 2023 AND DECLARING AN EMERGENCY

***Recommendation 3rd Reading, and
A Vote is Requested, and
Pass as an Emergency Measure***

b. Safety

RESOLUTION 31-2023

A RESOLUTION AUTHORIZING A PURCHASE AGREEMENT WITH PENN
CARE NOT TO EXCEED THREE HUNDRED EIGHTY-TWO THOUSAND,

FOUR HUNDRED SIXTY-SEVEN DOLLARS (\$382,467.00) FOR THE PURCHASE OF A BRAUN CHIEF XL, FORD F-550 4X4 DIESEL CHASSIS AMBULANCE FOR THE PERRYSBURG FIRE DIVISION AND DECLARING AN EMERGENCY

***Recommendation to Suspend the Rules,
Waive the Three Readings, and
Pass as an Emergency Measure***

RESOLUTION 32-2023

A RESOLUTION AUTHORIZING A PURCHASE AGREEMENT WITH PENN CARE NOT TO EXCEED THREE HUNDRED EIGHTY-TWO THOUSAND, FOUR HUNDRED SIXTY-SEVEN DOLLARS (\$382,467.00) FOR THE PURCHASE OF A BRAUN CHIEF XL, FORD F-550 4X4 DIESEL CHASSIS AMBULANCE FOR THE PERRYSBURG FIRE DIVISION AND DECLARING AN EMERGENCY

***Recommendation to Suspend the Rules,
Waive the Three Readings, and
Pass as an Emergency Measure***

c. Recreation

RESOLUTION 8-2023

ADOPTING THE ORLEANS PARK MASTER PLAN

***Recommendation 3rd Reading, and
A Vote is Requested***

RESOLUTION 16-2023

A RESOLUTION DECLARING CERTAIN WOODLANDS PARK PLAYGROUND EQUIPMENT NO LONGER NEEDED FOR PUBLIC USE OR UNFIT FOR PUBLIC SERVICE

***Recommendation to Suspend the Rules,
Waive the Three Readings, and
A Vote is requested***

d. Planning & Zoning

e. Personnel

f. Public Utilities

RESOLUTION 15-2023

AUTHORIZING AN AGREEMENT WITH JONES AND HENRY ENGINEERS, LTD. IN AN AMOUNT NOT TO EXCEED SIXTY-THREE THOUSAND DOLLARS AND NO CENTS (\$63,000.00) FOR ENGINEERING AND DESIGN SERVICES FOR THE GRASSY CREEK INTERCEPTOR REHABILITATION PROJECT; AND DECLARING AN EMERGENCY

***Recommendation to Suspend the Rules,
Waive the Three Readings, and
Pass as an Emergency Measure***

ORDINANCE 3-2023

AMENDING CODIFIED ORDINANCE 1050.10 OF THE CITY OF
PERRYSBURG STREETS, UTILITIES AND PUBLIC SERVICE CODE LAST
AMENDED BY ORDINANCE 125-2012 ON JULY 10, 2012

***Recommendation to Suspend the Rules,
Waive the Three Readings, and
A Vote is requested***

g. Service

RESOLUTION 28-2023

A RESOLUTION AWARDDING A BID AND AGREEMENT WITH M&M
FOAMWORKS LLC IN AN AMOUNT NOT TO EXCEED TWO HUNDRED
THOUSAND DOLLARS (\$200,000.00) FOR THE 2023 SIDEWALK
PROGRAM AND DECLARING AN EMERGENCY

***Recommendation to Suspend the Rules,
Waive the Three Readings, and
Pass as an Emergency Measure***

ORDINANCE 8-2023

AMENDING THE CITY OF PERRYSBURG ADMINISTRATIVE CODE,
CHAPTER 252, DEPARTMENT OF FINANCE

1st Reading, no vote required

10. Other Business

11. Adjournment

ORDINANCE 1-2023

AMENDING ORDINANCE 56-2022 TO AMEND APPROPRIATIONS FOR CURRENT EXPENSES AND OTHER EXPENDITURES FOR THE YEAR ENDING DECEMBER 31, 2023 AND DECLARING AN EMERGENCY

WHEREAS, to provide for current expenses and other expenditures for the fiscal year ending December 31, 2023, the City of Perrysburg, Ohio, approved the 2023 city budget pursuant to Ordinance 56-2022; and,

WHEREAS, it has been determined by the Mayor and Director of Finance that certain amendments should be made to the revenues, expenditures, and appropriations described in the approved 2023 budget for the City of Perrysburg, Wood County, Ohio; and,

WHEREAS, in order to reflect appropriate adjustments to the budget and otherwise provide for necessary appropriations, it is reasonable and appropriate to amend Ordinance 56-2022.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. To provide for current expenses and other expenditures for the City of Perrysburg, Ohio, during the fiscal year ending December 31, 2023, sums are set aside and appropriated as stated in Exhibit A attached hereto.

SECTION 2. To the extent the sums set aside and appropriated as stated in Exhibit A change those stated in Ordinance 56-2022, that ordinance is amended.

SECTION 3. The Director of Finance is authorized to draw his warrant upon the City Treasury in the amount appropriated and for the purposes stated in this Ordinance upon receiving the proper certificates and vouchers therefore, approved by the officer authorized by law to approve the same or authorized by an ordinance or resolution of Council to make the expenditure.

SECTION 4. The Mayor and Director of Finance are authorized to enter into contracts in accordance with the laws of the State of Ohio and the Charter, ordinances, and resolutions of the City of Perrysburg, Ohio.

SECTION 5. It is found and determined that all formal actions of Council concerning or relating to the passage of this Ordinance were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 6. This Ordinance is hereby declared to be an emergency measure necessary for the immediate preservation of the public peace, health and safety of the citizens of the City of Perrysburg, Wood County, Ohio, in order to ensure that such appropriations, powers, and duties within the annual budget shall be in effect immediately, and shall be in full force and effect from and immediately after its passage and approval by the Mayor.

President of Council

Mayor

PASSED: _____

ATTEST: _____

APPROVED: _____

CITY OF
PERRYSBURG
2023 BUDGET AMENDMENTS

Fund Description	Department	Budget Category	2023 Budget Amendment
General Fund (1110)	Information Technology (11145)	Salaries	\$ 70,000.00
General Fund (1110)	Engineer (11156)	Salaries	\$ 70,000.00
General Fund (1110)	Police (21232)	Salaries	\$ 144,150.00
General Fund (1110)	Administration (11230)	Salaries	\$ (95,500.00)
General Fund (1110)	Fire (21233)	Salaries	\$ 65,000.00
General Fund (1110)	Planning and Zoning (51234)	Salaries	\$ 17,000.00
General Fund (1110)	Street Division (71541)	Salaries	\$ 56,000.00
General Fund (1110)	Information Technology (11145)	Fringe Benefits	\$ 39,875.00
General Fund (1110)	Engineer (11156)	Fringe Benefits	\$ 39,875.00
General Fund (1110)	Police (21232)	Fringe Benefits	\$ 31,075.00
General Fund (1110)	Administration (11230)	Fringe Benefits	\$ (7,110.00)
General Fund (1110)	Fire (21233)	Fringe Benefits	\$ 4,850.00
General Fund (1110)	Planning and Zoning (51234)	Fringe Benefits	\$ 3,900.00
General Fund (1110)	Street Division (71541)	Fringe Benefits	\$ 35,587.00
General Fund (1110)	Council (11001)	Travel, Registration, Dues, and Memberships	\$ 1,000.00
General Fund (1110)	Mayor (11003)	Travel, Registration, Dues, and Memberships	\$ 1,000.00
General Fund (1110)	Fire (21233)	Travel, Registration, Dues, and Memberships	\$ 7,500.00
General Fund (1110)	Planning and Zoning (51234)	Travel, Registration, Dues, and Memberships	\$ 1,000.00
General Fund (1110)	Human Resources (11005)	Services	\$ 55,775.00
General Fund (1110)	Law (11006)	Services	\$ 125,000.00
General Fund (1110)	Administration (11230)	Services	\$ 15,000.00
General Fund (1110)	City Wide (11755)	Services	\$ 129,905.00
General Fund (1110)	Special Disbursements (11761)	Services	\$ 8,000.00
General Fund (1110)	Police (21232)	Services	\$ 150,000.00
General Fund (1110)	Fire (21233)	Services	\$ 78,420.00
General Fund (1110)	Planning and Zoning (51234)	Services	\$ 29,000.00
General Fund (1110)	Street Division (71541)	Services	\$ 7,500.00
General Fund (1110)	Public Parks and Playgrounds (41646)	Services	\$ 13,500.00
General Fund (1110)	Council (11001)	Supplies and Materials	\$ (1,000.00)
General Fund (1110)	Mayor (11003)	Supplies and Materials	\$ (1,000.00)
General Fund (1110)	City Wide (11755)	Supplies and Materials	\$ 8,000.00
General Fund (1110)	Fire (21233)	Supplies and Materials	\$ 35,200.00
General Fund (1110)	Street Division (71541)	Supplies and Materials	\$ (7,500.00)
General Fund (1110)	Public Parks and Playgrounds (41646)	Supplies and Materials	\$ (2,500.00)
General Fund (1110)	Special Disbursements (11761)	Miscellaneous	\$ 125,000.00
Hotel/Motel Tax (7220)	Hotel/Motel Tax (11015)	Miscellaneous	\$ 75,000.00
Hotel/Motel Tax (7220)	Hotel/Motel Tax (11015)	Other Financing Sources	\$ 75,000.00
Street Construction and Repair (2223)	Traffic Signals (71546)	Services	\$ 210,000.00
Lighting Fund (2225)	Bond and Note Retirement (93238)	Services	\$ 25,000.00
Lighting Fund (2225)	Bond and Note Retirement (93238)	Supplies and Materials	\$ (25,000.00)
Muni Court Computer/L.R. (2238)	Muni Court Computer/L.R. (11820)	Services	\$ 10,000.00
Payroll and Payout Reserve (1112)	City Wide (11755)	Fringe Benefits	\$ 3,700.00
Payroll and Payout Reserve (1112)	City Wide (11755)	Salaries	\$ (3,700.00)
Police & Fire Pension (2228)	Contract Services/Fringe Benefits (21236)	Fringe Benefits	\$ 43,250.00
Capital Improvements (4403)	Information Technology (11145)	Capital Outlay	\$ 45,000.00
Capital Improvements (4403)	City Wide (11755)	Capital Outlay	\$ 1,780,000.00
Capital Improvements (4403)	Police (21232)	Capital Outlay	\$ 52,000.00
Capital Improvements (4403)	Fire (21233)	Capital Outlay	\$ 587,250.00
Capital Improvements (4403)	Street Division (71541)	Capital Outlay	\$ 170,000.00
Employee Health and Welfare (6505)	Employees Health and Welfare (11075)	Miscellaneous	\$ (785,000.00)
Employee Health and Welfare (6505)	Employees Health and Welfare (11075)	Services	\$ 785,000.00
Water Division (5331)	Water (61814)	Services	\$ 22,500.00
Water Division (5331)	Water (61814)	Supplies and Materials	\$ 347,500.00
Water Pollution Control (5332)	Sewer Collections (61826)	Services	\$ 22,500.00
Water Pollution Control (5332)	WWTP (61815)	Services	\$ 207,500.00
Water Pollution Control (5332)	Sewer Collections (61826)	Supplies and Materials	\$ (2,500.00)
Water R & E (5401)	Water (61814)	Capital Outlay	\$ 300,000.00
Sewer R & E (5402)	Sewer Collections (61826)	Capital Outlay	\$ (5,033,000.00)
Sewer R & E (5402)	WWTP (61815)	Capital Outlay	\$ 485,000.00
Sewer R & E (5402)	Storm Water Management (62955)	Capital Outlay	\$ 1,380,000.00
Sewer R & E (5402)	Sewer Collections (61826)	Miscellaneous	\$ 250,000.00
			\$ 2,280,502.00

CITY OF PERRYSBURG

2023 BUDGET AMENDMENTS

Fund Description	Department	Budget Category	Amount	Account Description	Notes
General Fund	Planning and Zoning	Travel, Registration, Dues	\$ 1,000.00	Travel and Meals	P&Z - additional training for Economic Development
General Fund	Planning and Zoning	Services	\$ 4,000.00	Other - Services	P&Z - additional contract services for Economic Development
General Fund	Administration	Services	\$ 15,000.00	Other - Services	Reveille Contract Increase
Capital Improvements	City Wide	Capital Outlay	\$ 40,000.00	Other - Capital Outlay	Hood Park Design
Capital Improvements	City Wide	Capital Outlay	\$ 150,000.00	Other - Capital Outlay	Parking Improvements Walnut / Third / Elm
General Fund	Human Resources	Services	\$ 13,775.00	Communication/Technical Services	NeoGov Learn
General Fund	Human Resources	Services	\$ 7,000.00	Communication/Technical Services	Predictive Index
General Fund	Law	Services	\$ 40,000.00	Legal Fees	Union negotiations
General Fund	Information Technology	Salaries	\$ 70,000.00	Employees Full Time Wages (FTW)	Additional Position - GIS/Software Assistant
General Fund	Information Technology	Fringe Benefits	\$ 9,800.00	OPERS	Additional Position - GIS/Software Assistant
General Fund	Information Technology	Fringe Benefits	\$ 1,100.00	Medicare	Additional Position - GIS/Software Assistant
General Fund	Information Technology	Fringe Benefits	\$ 26,500.00	Insurance Benefits Employee	Additional Position - GIS/Software Assistant
General Fund	Information Technology	Fringe Benefits	\$ 375.00	Vision Reimbursement	Additional Position - GIS/Software Assistant
General Fund	Information Technology	Fringe Benefits	\$ 2,100.00	Deferred Compensation Employer Contr	Additional Position - GIS/Software Assistant
General Fund	Engineer	Salaries	\$ 70,000.00	Employees Full Time Wages (FTW)	Additional Position - Inspector
General Fund	Engineer	Fringe Benefits	\$ 9,800.00	OPERS	Additional Position - Inspector
General Fund	Engineer	Fringe Benefits	\$ 1,100.00	Medicare	Additional Position - Inspector
General Fund	Engineer	Fringe Benefits	\$ 26,500.00	Insurance Benefits Employee	Additional Position - Inspector
General Fund	Engineer	Fringe Benefits	\$ 375.00	Vision Reimbursement	Additional Position - Inspector
General Fund	Engineer	Fringe Benefits	\$ 2,100.00	Deferred Compensation Employer Contr	Additional Position - Inspector
General Fund	City Wide	Services	\$ 18,000.00	Communication/Technical Services	New Phone System Service
General Fund	Police	Salaries	\$ 79,150.00	Employees FTW - Sworn Officers	Additional Position - Deputy Police Chief - starting April 2023
General Fund	Police	Fringe Benefits	\$ 1,150.00	Medicare	Additional Position - Deputy Police Chief - starting April 2023
General Fund	Police	Fringe Benefits	\$ 19,900.00	Insurance Benefits Employee	Additional Position - Deputy Police Chief - starting April 2023
General Fund	Police	Fringe Benefits	\$ 375.00	Vision Reimbursement	Additional Position - Deputy Police Chief - starting April 2023
General Fund	Police	Fringe Benefits	\$ 4,800.00	Deferred Compensation Employer Contr	Additional Position - Deputy Police Chief - starting April 2023
General Fund	Police	Services	\$ 150,000.00	Communication/Technical Services	ALPR Cameras
General Fund	Fire	Services	\$ 7,000.00	Building Repairs and Maintenance	Misc. Repairs
General Fund	Fire	Services	\$ 2,000.00	Building Repairs and Maintenance	Pond Maintenance
General Fund	Fire	Services	\$ 10,000.00	Vehicle and Equipment Maintenance	Misc. Equipment Maintenance

Fund Description	Department	Budget Category	Amount	Account Description	Notes
General Fund	Fire	Services	\$ 2,500.00	Vehicle and Equipment Maintenance	Rogue Plates Equipment Maintenance
General Fund	Fire	Services	\$ 2,000.00	Vehicle and Equipment Maintenance	Fitness Equipment Maintenance
General Fund	Fire	Supplies and Materials	\$ 10,200.00	Equipment and Furniture <\$10k	PPE - 3 Additional Sets
General Fund	Fire	Supplies and Materials	\$ 20,000.00	Medical Supplies	Medical Supplies reduced by 20k
General Fund	Fire	Supplies and Materials	\$ 5,000.00	Other - Supplies and Materials	CPR supplies and educational materials reduced by 5k
General Fund	Planning and Zoning	Services	\$ 25,000.00	Other - Services	Contract service additional funding
General Fund	Street Division	Salaries	\$ 56,000.00	Employees Full Time Wages (FTW)	Additional Position - Light Equipment Operator
General Fund	Street Division	Fringe Benefits	\$ 7,900.00	OPERS	Additional Position - Light Equipment Operator
General Fund	Street Division	Fringe Benefits	\$ 812.00	Medicare	Additional Position - Light Equipment Operator
General Fund	Street Division	Fringe Benefits	\$ 26,500.00	Insurance Benefits Employee	Additional Position - Light Equipment Operator
General Fund	Street Division	Fringe Benefits	\$ 375.00	Vision Reimbursement	Additional Position - Light Equipment Operator
Police & Fire Pension	Contract Services/Fringe Benefits	Fringe Benefits	\$ 16,600.00	Ohio Police and Fire	Additional Position - Deputy Police Chief - starting April 2023
Capital Improvements	Information Technology	Capital Outlay	\$ 45,000.00	Equipment >\$10k	New Phone System Capital
Capital Improvements	Police	Capital Outlay	\$ 12,000.00	Other - Capital Outlay	Firearms
Capital Improvements	Police	Capital Outlay	\$ 40,000.00	Other - Capital Outlay	Additional Radios
Capital Improvements	Fire	Capital Outlay	\$ 22,250.00	Other - Capital Outlay	Fire Safety Trailer Improvements
Capital Improvements	Fire	Capital Outlay	\$ 25,000.00	Other - Capital Outlay	Hose Bed Cover
Capital Improvements	Fire	Capital Outlay	\$ 35,000.00	Other - Capital Outlay	Power Cot (1)
Capital Improvements	Fire	Capital Outlay	\$ 30,000.00	Other - Capital Outlay	Stair Chairs (2)
Capital Improvements	Street Division	Capital Outlay	\$ 25,000.00	Equipment and Furniture >\$10k	HVAC budget increase from 75k to 100k
Capital Improvements	Street Division	Capital Outlay	\$ 85,000.00	Equipment and Furniture >\$10k	Toro Mower Replacement
Capital Improvements	Street Division	Capital Outlay	\$ (50,000.00)	Equipment >\$10k	Snow Blower - encumbered in 2022
Capital Improvements	Street Division	Capital Outlay	\$ 60,000.00	Motor Vehicles	Mechanics Truck
Capital Improvements	Street Division	Capital Outlay	\$ 50,000.00	Other - Capital Outlay	Resurfacing Bicentennial Parking Lot
General Fund	Human Resources	Services	\$ 50,000.00	Other - Services	City Administrator Executive Search
General Fund	Human Resources	Services	\$ (15,000.00)	Other - Services	Reduce Administrator Search Contract to \$35,000
General Fund	Law	Services	\$ 85,000.00	Legal Fees	Additional Legal Services and Surveys for Annexations
General Fund	Administration	Salaries	\$ (95,500.00)	Employees Full Time Wages (FTW)	Safety Director Split 50% Police/50% Fire
General Fund	Administration	Fringe Benefits	\$ (1,380.00)	Medicare	Safety Director Split 50% Police/50% Fire
General Fund	Administration	Fringe Benefits	\$ (5,730.00)	Deferred Compensation Employer Contr	Safety Director Split 50% Police/50% Fire
General Fund	City Wide	Services	\$ 16,905.00	Communication/Technical Services	Civic Clerk - 2023
General Fund	City Wide	Services	\$ 7,000.00	Communication/Technical Services	Keepit Office365
General Fund	City Wide	Services	\$ 8,000.00	Communication/Technical Services	KnowBe4
General Fund	City Wide	Services	\$ 80,000.00	Other - Services	Storm Water Utility Study
General Fund	City Wide	Supplies and Materials	\$ 8,000.00	Equipment and Furniture <\$10k	City Seal Updated

Fund Description	Department	Budget Category	Amount	Account Description	Notes
General Fund	Special Disbursements	Services	\$ 8,000.00	Auditing and Accounting Services	Indirect Cost Study
General Fund	Special Disbursements	Miscellaneous	\$ 125,000.00	Jobs Grant Payment	Additional Jobs Grant Payments
General Fund	Police	Salaries	\$ 65,000.00	Employees FTW - Sworn Officers	Safety Director Split 50% Police/50% Fire
General Fund	Police	Fringe Benefits	\$ 950.00	Medicare	Safety Director Split 50% Police/50% Fire
General Fund	Police	Fringe Benefits	\$ 3,900.00	Deferred Compensation Employer Contr	Safety Director Split 50% Police/50% Fire
General Fund	Fire	Salaries	\$ 65,000.00	Employees FTW - Sworn Officers	Safety Director Split 50% Police/50% Fire
General Fund	Fire	Fringe Benefits	\$ 950.00	Medicare	Safety Director Split 50% Police/50% Fire
General Fund	Fire	Fringe Benefits	\$ 3,900.00	Deferred Compensation Employer Contr	Safety Director Split 50% Police/50% Fire
General Fund	Fire	Travel, Registration, Dues	\$ 7,500.00	Registration	Haz Mat IQ Class
General Fund	Fire	Services	\$ 1,620.00	Communication/Technical Services	VLI Tech - Cloud Hosting EMS Records
General Fund	Fire	Services	\$ 3,300.00	Building Repairs and Maintenance	Storage Building Floor Concrete
General Fund	Fire	Services	\$ 50,000.00	Vehicle and Equipment Maintenance	Ambulance Repair
General Fund	Public Parks and Playgrounds	Services	\$ 11,000.00	Operational Services	Renewed Compost Increase Prices
General Fund	Planning and Zoning	Salaries	\$ 17,000.00	Employees Full Time Wages (FTW)	Zoning Director Position Duties Added
General Fund	Planning and Zoning	Fringe Benefits	\$ 2,630.00	OPERS	Zoning Director Position Duties Added
General Fund	Planning and Zoning	Fringe Benefits	\$ 250.00	Medicare	Zoning Director Position Duties Added
General Fund	Planning and Zoning	Fringe Benefits	\$ 1,020.00	Deferred Compensation Employer Contr	Zoning Director Position Duties Added
Street Construction and Re	Traffic Signals	Services	\$ 210,000.00	Building Repairs and Maintenance	Missed on original budget
Police & Fire Pension	Contract Services/Fringe Benefits	Fringe Benefits	\$ 26,650.00	Ohio Police and Fire	Safety Director Split 50% Police/50% Fire
Muni Court Computer/L.R.	Muni Court Computer/L.R.	Services	\$ 2,400.00	Communication/Technical Services	Westlaw Online Subscription Services
Muni Court Computer/L.R.	Muni Court Computer/L.R.	Services	\$ 3,600.00	Advertising, Printing, and Reproduction	Copier services
Muni Court Computer/L.R.	Muni Court Computer/L.R.	Services	\$ 4,000.00	Rentals and Leases	Postage Lease
Capital Improvements	City Wide	Capital Outlay	\$ 180,000.00	Other - Capital Outlay	Second Street Parking
Capital Improvements	City Wide	Capital Outlay	\$ 110,000.00	Other - Capital Outlay	Walnut Street Parking - Indiana to Railroad
Capital Improvements	City Wide	Capital Outlay	\$ 1,100,000.00	Other - Capital Outlay	Downtown ADA Project - Additional Funds - \$1.5 million total
Capital Improvements	City Wide	Capital Outlay	\$ (500,000.00)	Other - Capital Outlay	Reduce Downtown ADA to \$1.0 million total (400k original + 600k amend)
Capital Improvements	City Wide	Capital Outlay	\$ 700,000.00	Other - Capital Outlay	Orleans Park Path
Capital Improvements	Fire	Capital Outlay	\$ 425,000.00	Motor Vehicles	Additional Ambulance
Capital Improvements	Fire	Capital Outlay	\$ 50,000.00	Other - Capital Outlay	Fire Garage Construction Additional Funding
Water Division	Water	Services	\$ 20,000.00	Training/Consultant	Operator Training - bringing in trainer
Water Division	Water	Supplies and Materials	\$ 350,000.00	Operational Materials	Additional Hydrants, Meters, Pumps
Water Pollution Control	WWTP	Services	\$ 200,000.00	Operational Services	Aeration Tank Cleaning - Moved From Capital Fund
Water Pollution Control	WWTP	Services	\$ 7,500.00	Training/Consultant	Bringing in trainer
Water Pollution Control	Sewer Collections	Services	\$ 20,000.00	Training/Consultant	Operator Training - bringing in trainer
Water R & E	Water	Capital Outlay	\$ 50,000.00	Equipment >\$10k	Excavator

Fund Description	Department	Budget Category	Amount	Account Description	Notes
Water R & E	Water	Capital Outlay	\$ (50,000.00)	Equipment >\$10k	Vac-trailer
Water R & E	Water	Capital Outlay	\$ 50,000.00	Equipment >\$10k	Controls at EBPS and SBPS
Water R & E	Water	Capital Outlay	\$ (75,000.00)	Motor Vehicles	Crane Truck - encumbered in 2022
Water R & E	Water	Capital Outlay	\$ (125,000.00)	Motor Vehicles	Water Service Truck
Water R & E	Water	Capital Outlay	\$ 175,000.00	Motor Vehicles	Dump truck
Water R & E	Water	Capital Outlay	\$ 25,000.00	Other - Capital Outlay	5th & 6th Street WM replacement, Phase I - Design
Water R & E	Water	Capital Outlay	\$ 50,000.00	Other - Capital Outlay	AMI Phase 2 & 3 Additional Funding - Fiberglass Pole
Water R & E	Water	Capital Outlay	\$ (50,000.00)	Other - Capital Outlay	Loop closure - Levis Commons Engineering
Water R & E	Water	Capital Outlay	\$ (1,000,000.00)	Other - Capital Outlay	5th & 6th Street Watermain replacement, Phase II Construction
Water R & E	Water	Capital Outlay	\$ (250,000.00)	Other - Capital Outlay	Future Tank Rehab
Water R & E	Water	Capital Outlay	\$ (250,000.00)	Other - Capital Outlay	Loop closure - Levis Commons Construction
Water R & E	Water	Capital Outlay	\$ 300,000.00	Other - Capital Outlay	Campus Design
Water R & E	Water	Capital Outlay	\$ 75,000.00	Other - Capital Outlay	5th & 6th Street WM replacement, Phase I - Construction Engineering
Water R & E	Water	Capital Outlay	\$ 80,000.00	Other - Capital Outlay	5th & 6th Street Watermain replacement, Phase II - Design
Water R & E	Water	Capital Outlay	\$ 58,000.00	Other - Capital Outlay	WM Levis Commons, Dixie Hwy Crossing Design & CE
Water R & E	Water	Capital Outlay	\$ 290,000.00	Other - Capital Outlay	WM Levis Commons, Dixie Hwy Crossing Project - C
Water R & E	Water	Capital Outlay	\$ 50,000.00	Other - Capital Outlay	New EBPS Meter Chamber - D
Water R & E	Water	Capital Outlay	\$ 47,000.00	Other - Capital Outlay	WM Repalcement Lake Vue, Eckel Junction Road Design & CE
Water R & E	Water	Capital Outlay	\$ 50,000.00	Other - Capital Outlay	Fort Meigs Water Tower Interior Paint - D
Water R & E	Water	Capital Outlay	\$ 825,000.00	Other - Capital Outlay	5th & 6th Street WM replacement, Phase I - Construction
Sewer R & E	WWTP	Capital Outlay	\$ (50,000.00)	Other - Capital Outlay	Front Loader
Sewer R & E	WWTP	Capital Outlay	\$ 150,000.00	Equipment >\$10k	New Meter and Backflow
Sewer R & E	WWTP	Capital Outlay	\$ 335,000.00	Other - Capital Outlay	Digester Cleaning, Improvements, and Engineering
Sewer R & E	Sewer Collections	Capital Outlay	\$ 50,000.00	Equipment >\$10k	Excavator
Sewer R & E	Sewer Collections	Capital Outlay	\$ (50,000.00)	Equipment >\$10k	Vac-trailer
Sewer R & E	Sewer Collections	Capital Outlay	\$ (100,000.00)	Equipment >\$10k	Brookhaven Pumps
Sewer R & E	Sewer Collections	Capital Outlay	\$ 300,000.00	Other - Capital Outlay	Campus Design
Sewer R & E	Sewer Collections	Capital Outlay	\$ (125,000.00)	Equipment >\$10k	Gorman View Pump Station Imps
Sewer R & E	Sewer Collections	Capital Outlay	\$ (75,000.00)	Motor Vehicles	Crane Truck - encumbered in 2022
Sewer R & E	Sewer Collections	Capital Outlay	\$ 175,000.00	Motor Vehicles	Dump truck
Sewer R & E	Sewer Collections	Capital Outlay	\$ (100,000.00)	Other - Capital Outlay	Primary Clarifier Design
Sewer R & E	Sewer Collections	Capital Outlay	\$ (75,000.00)	Other - Capital Outlay	Construction Phase - Digester Imps Engineering
Sewer R & E	Sewer Collections	Capital Outlay	\$ (2,000,000.00)	Other - Capital Outlay	Digester Cleaning and Improvements Construction
Sewer R & E	Sewer Collections	Capital Outlay	\$ (125,000.00)	Other - Capital Outlay	Digester Cleaning and Improvements Engineering
Sewer R & E	Sewer Collections	Capital Outlay	\$ (25,000.00)	Other - Capital Outlay	Brookhaven Lateral Repairs Engineering

Fund Description	Department	Budget Category	Amount	Account Description	Notes
Sewer R & E	Sewer Collections	Capital Outlay	\$ 100,000.00	Other - Capital Outlay	Cherry St. CSO - Stormwater Reroute
Sewer R & E	Sewer Collections	Capital Outlay	\$ (175,000.00)	Other - Capital Outlay	Elm St. CSO - Engineering and Replacement
Sewer R & E	Sewer Collections	Capital Outlay	\$ (150,000.00)	Other - Capital Outlay	Louisiana and Grassy Creek
Sewer R & E	Sewer Collections	Capital Outlay	\$ 325,000.00	Other - Capital Outlay	Elm St./7th Street - Sanitary Sewer Replacement
Sewer R & E	Sewer Collections	Capital Outlay	\$ (125,000.00)	Other - Capital Outlay	Aeration Tank Cleaning
Sewer R & E	Sewer Collections	Capital Outlay	\$ (75,000.00)	Other - Capital Outlay	Construction Phase - Maple St. ER-SSO
Sewer R & E	Sewer Collections	Capital Outlay	\$ (2,500,000.00)	Other - Capital Outlay	Maple Street ER-SSO
Sewer R & E	Sewer Collections	Capital Outlay	\$ (125,000.00)	Other - Capital Outlay	Maple Street ER-SSO Engineering
Sewer R & E	Sewer Collections	Capital Outlay	\$ 17,000.00	Other - Capital Outlay	3rd Street Sewer - B
Sewer R & E	Sewer Collections	Capital Outlay	\$ 325,000.00	Other - Capital Outlay	3rd Street Sewer - C
Sewer R & E	Sewer Collections	Capital Outlay	\$ 100,000.00	Other - Capital Outlay	Grassy Ck Interceptor Lining - D
Sewer R & E	Sewer Collections	Capital Outlay	\$ 650,000.00	Other - Capital Outlay	Grassy Ck Interceptor Lining - C
Sewer R & E	Sewer Collections	Capital Outlay	\$ (800,000.00)	Other - Capital Outlay	Ft. Meigs Ditch Rehab
Sewer R & E	Sewer Collections	Capital Outlay	\$ (175,000.00)	Other - Capital Outlay	Ft. Meigs Ditch Rehab Engineering
Sewer R & E	Storm Water Management	Capital Outlay	\$ 800,000.00	Other - Capital Outlay	Ft. Meigs Ditch Rehab
Sewer R & E	Storm Water Management	Capital Outlay	\$ 175,000.00	Other - Capital Outlay	Ft. Meigs Ditch Rehab Engineering
Sewer R & E	Storm Water Management	Capital Outlay	\$ 130,000.00	Other - Capital Outlay	Ft. Meigs Ditch Design
Sewer R & E	Storm Water Management	Capital Outlay	\$ 150,000.00	Other - Capital Outlay	SR199 Ditch Cleaning, Phase 2
Sewer R & E	Storm Water Management	Capital Outlay	\$ 25,000.00	Other - Capital Outlay	Locust St Ditch Cleaning
Sewer R & E	Storm Water Management	Capital Outlay	\$ 100,000.00	Other - Capital Outlay	Willow Bend Storm Sewer Imps - C
Hotel/Motel Tax	Hotel/Motel Tax	Miscellaneous	\$ 75,000.00	Remittance	Additional Hotel/Motel Revenue Anticipated
Hotel/Motel Tax	Hotel/Motel Tax	Other Financing Sources	\$ 75,000.00	Transfers - Out	Additional Hotel/Motel Revenue Anticipated
General Fund	Council	Supplies and Materials	\$ (1,000.00)	Other - Supplies and Materials	Moving to Travel and Meals for misc. meeting meals
General Fund	Council	Travel, Registration, Dues	\$ 1,000.00	Travel and Meals	Moving to Travel and Meals for misc. meeting meals
General Fund	Mayor	Supplies and Materials	\$ (1,000.00)	Other - Supplies and Materials	Moving to Travel and Meals for misc. meeting meals
General Fund	Mayor	Travel, Registration, Dues	\$ 1,000.00	Travel and Meals	Moving to Travel and Meals for misc. meeting meals
General Fund	Public Parks and Playgrounds	Services	\$ 2,500.00	Operational Services	Rental of Uniforms - should be in services
General Fund	Public Parks and Playgrounds	Supplies and Materials	\$ (2,500.00)	Uniforms, Clothing, and Boots	Rental of Uniforms - should be in services
General Fund	Street Division	Services	\$ 7,500.00	Operational Services	Rental of Uniforms - should be in services
General Fund	Street Division	Supplies and Materials	\$ (7,500.00)	Uniforms, Clothing, and Boots	Rental of Uniforms - should be in services
Payroll and Payout Reserve	City Wide	Salaries	\$ (3,700.00)	Employees Full Time Wages (FTW)	Accounting for Medicare for Potential Payouts
Payroll and Payout Reserve	City Wide	Fringe Benefits	\$ 3,700.00	Medicare	Accounting for Medicare for Potential Payouts
Lighting Fund	Bond and Note Retirement	Services	\$ 25,000.00	Utilities	Moving supplies to services
Lighting Fund	Bond and Note Retirement	Supplies and Materials	\$ (25,000.00)	Other - Supplies and Materials	Moving supplies to services
Water Division	Water	Services	\$ 2,500.00	Operational Services	Rental of Uniforms - should be in services

Fund Description	Department	Budget Category	Amount	Account Description	Notes
Water Division	Water	Supplies and Materials	\$ (2,500.00)	Uniforms, Clothing, and Boots	Rental of Uniforms - should be in services
Water Pollution Control	WWTP	Services	\$ (10,350.00)	Operational Services	Account for OEPA fees in correct account code
Water Pollution Control	WWTP	Services	\$ 10,350.00	Operational Services	Account for OEPA fees in correct account code
Water Pollution Control	Sewer Collections	Services	\$ 2,500.00	Operational Services	Rental of Uniforms - should be in services
Water Pollution Control	Sewer Collections	Supplies and Materials	\$ (2,500.00)	Uniforms, Clothing, and Boots	Rental of Uniforms - should be in services
Water R & E	Water	Capital Outlay	\$ (25,000.00)	Motor Vehicles	Pick Up Truck (1) - WWTP
Sewer R & E	WWTP	Capital Outlay	\$ 50,000.00	Motor Vehicles	Pick Up Truck (1) - WWTP
Sewer R & E	Sewer Collections	Capital Outlay	\$ (25,000.00)	Motor Vehicles	Pick Up Truck (1) - WWTP
Sewer R & E	Sewer Collections	Capital Outlay	\$ (250,000.00)	Other - Capital Outlay	Grant Payments - in wrong budget category
Sewer R & E	Sewer Collections	Miscellaneous	\$ 250,000.00	Sanitary Sewer Grant Payments	Grant Payments - in wrong budget category
Employee Health and Well	Employees Health and Welfare	Services	\$ 785,000.00	Other - Services	Moving administrative fees from claims line to services
Employee Health and Well	Employees Health and Welfare	Miscellaneous	\$ (785,000.00)	Medical Claims	Moving administrative fees from claims line to services
TOTAL			\$ 2,280,502.00		

Green	Changes requested after first Council reading
White	In Original Dept. budget request and taken out for budget balancing measures
Yellow	New budget requests
Blue	Net to zero - moving budget categories

TO: Mayor Mackin
President Smith
Members of City Council

FROM: Patrick Jones, Director of Public Safety

RE: Resolution 31-2023

DATE: March 1, 2023



Subject Matter/Background

Resolution 31-2023 authorizes the purchase of a new Braun Chief LX, Ford F-550 4x4 diesel chassis ambulance at a purchase price not to exceed \$382,467.00. This emergency vehicle is budgeted for purchase in the 2023 budget. Current lead times for this ambulance to be built is up to two years, due to ongoing supply chain issues.

This ambulance will replace a 2019 Kenworth ambulance that will be repurposed as, and is better suited as, a technical rescue vehicle. The Fire Division is requesting to purchase an emergency vehicle that has a Ford cab and chassis and a Braun box on the back. The dealer is Penn Care, therefore, the dealer is the contractor in the legislation. Pricing for this ambulance is under Ohio State Term pricing contract 009362.

This resolution was approved by the Safety Committee 3-0 to forward to City Council.

Financial Review

The funds are available in line item 4403.21233.55600.

Recommendation

If City Council is in agreement, a motion to suspend the three readings, waive the rules, and authorize this Resolution as an Emergency is recommended.

RESOLUTION 31-2023

A RESOLUTION AUTHORIZING A PURCHASE AGREEMENT WITH PENN CARE NOT TO EXCEED THREE HUNDRED EIGHTY- TWO THOUSAND, FOUR HUNDRED SIXTY-SEVEN DOLLARS (\$382,467.00) FOR THE PURCHASE OF A BRAUN CHIEF XL, FORD F-550 4X4 DIESEL CHASSIS AMBULANCE FOR THE PERRYSBURG FIRE DIVISION AND DECLARING AN EMERGENCY

WHEREAS, it is necessary for the safety and security of the City of Perrysburg that the City of Perrysburg Fire Division have the necessary equipment to respond to medical emergencies,

WHEREAS, a replacement emergency vehicle is necessary at this time to enable the City of Perrysburg Fire Division to respond efficiently to medical emergencies; and,

WHEREAS, this emergency vehicle would replace a 2019 Kenworth ambulance that would be repurposed and better suited as a technical rescue equipment vehicle; and,

WHEREAS, at their February 28, 2023 meeting, the Safety Committee voted 3-0 to advance this resolution to City Council.

NOW, THEREFORE, BE IT RESOLVED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. The Mayor and Director of Finance are authorized to enter into an agreement with Penn Care to purchase a Braun Chief XL, Ford F-550 4x4 diesel chassis ambulance at a cost not to exceed Three Hundred Eighty-Two Thousand, Four-Hundred Sixty-Seven Dollars (\$382,467.00) in accordance with the proposal attached hereto as Exhibit A.

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Resolution were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Resolution is hereby declared to be an emergency measure necessary for the immediate preservation of the public peace, health and safety of the citizens of the City of Perrysburg, Wood County, Ohio, in order to allow for the immediate purchase of the emergency vehicle for the safety of the City of Perrysburg,

Res# 31-2023

and shall be in full force and effect from and immediately after its passage and approval by the Mayor.

President of Council

Mayor

PASSED _____

ATTEST: _____

APPROVED: _____



Exhibit A

Emergency Vehicle Purchase Agreement February 2, 23

Purchaser:

City of Perrysburg
26100 Fort Meigs Rd.
Perrysburg, OH 43551

Seller:

Penn Care, Inc.
1317 North Rd.
Niles, OH 44446

The City of Perrysburg intends to purchase (1) Braun Chief XL on the Ford F-550 4x4 Diesel Chassis, as designed per the attached specifications, and when applicable, technical drawings, graphic design and other required documents. Additions, deletions and/or changes must be approved by all parties in writing and may cause delays in deliveries and additional charges to the purchaser.

PRICING

Ambulance Conversion:	\$308,991.00
Chassis Price (Estimate Only):	\$73,476.00
Graphics:	None
Additional Equipment:	None
FIN Rebate (Estimate Only):	TBD
Total Per Due at Delivery:	\$382,467.00

CHASSIS AVAILABILITY, PRICING, AND MANUFACTURES INCENTIVE:

Chassis year, price and manufactures incentives are priced as budgetary estimations ONLY and will not be finalized until the chassis arrives at the ambulance manufacturing facilities.

DELIVERY TIMES

Quoted lead times and delivery expectations quoted by Penn Care, Inc. are approximate and not guaranteed. Quoted lead times will be extended for Change Orders, delays from the chassis OEM and Force Majeure.

TRADE DESCRIPTION:

TRADE-IN TERMS AND APPRAISAL

Where Purchaser wishes to trade-in a used motor vehicle as part of the consideration for the motor vehicle ordered, Seller may appraise the trade-in at the time of the execution of this order by Purchaser. Seller also reserves the right to reappraise the trade-in at the time of delivery. The seller shall not alter a Trade-In appraisal from the time of the initial appraisal until the time of delivery unless:



- 1) Intervening factors indicate an apparent decrease in the value of the trade-in over and above ordinary wear and tear
- 2) A change occurs in the mechanical performance of the vehicle
- 3) Emergency, medical, and/or other equipment/components have been removed that were not previously discussed and agreed to in writing
- 4) The Seller has made any misrepresentation of the vehicle and/or components to Penn Care, Inc.

WARRANTY

No representation has been made by Penn Care, Inc., except as herein stated and no warranties, expressed or implied, may arise except from this writing. All warranties are issued by the chassis manufacturer, the ambulance builder, and/or component parts suppliers and Penn Care, Inc. shall have no liability with respect to warranties issued by the chassis manufacturer, the ambulance builder, and component parts suppliers. Used vehicles are "as is" and have no warranty.

INVOICING AND PAYMENT

Unless otherwise agreed to in writing, Penn Care, Inc. will invoice the Purchaser 30 days prior to the scheduled delivery date. Upon completion of production and quality inspection by the Purchaser the vehicle is declared ready for delivery and payment will be due upon acceptance and/or delivery.

PAYMENT OF SALES AND USE TAXES

The price for the motor vehicle specified in this agreement does not include Sales Taxes and Use Taxes (Federal, State, or Local) unless expressly stated. Purchaser assumes and agrees to pay, unless prohibited by law, and such Sales, Use, or Occupational Taxes imposed on or applicable to the transaction covered by this agreement, regardless of which party may have primary tax liability.

ACCEPTANCE

When requesting a final inspection the Purchaser shall inspect the vehicle(s) within 10-days of notification of completion of production. Vehicles not inspected by buyer will be deemed complete and ready for delivery, and payment will be due upon delivery. Items and issues discovered after the 10-day window shall not hold up payment from buyer to Penn Care Inc., these issues will be handled as warranty claims following the normal procedures.

PAYMENT AND TITLE

All payments shall be made in U.S. dollars either by certified check or wire transfers, credit card payments are not acceptable without prior written authorization (fees will apply). Payment terms are COD, unless otherwise agreed to in writing by Penn Care, Inc. Interest terms begin 16-days from date of delivery and are charged at a rate of prime plus 6%. MSO and title are released to Purchaser upon payment in full, including any related interest, shipping expenses, and other related costs and expenses to Penn Care Inc. or to the appointed floor plan financing company.

As collateral security for the payment of the purchase price of the Vehicles, Buyer hereby grants to Penn Care Inc., a lien on and security interest in and to all of the right, title, and interest of Purchaser in, to, and under the Vehicles, wherever located, and whether now existing or hereafter arising or acquired from time to time, and in all accessions thereto and replacements or modifications thereof, as well as all proceeds, including insurance proceeds, of the foregoing. The security interest granted under this provision constitutes a purchase money security interest under the Ohio Uniform Commercial Code.

CANCELLATION

Penn Care, Inc., may, in its sole discretion, and without liability or penalty, cancel this order at its sole discretion. Once Penn Care's manufactures commence engineering, no cancellation of this order is permitted, and the full purchase price is due and payable to Penn Care, Inc. Notwithstanding other provisions of this Agreement, and in addition thereto, Penn Care, Inc. shall be entitled to its reasonable and anticipated lost profit from such cancellation.

FORCE MAJEURE

Penn Care, Inc. shall not be liable or responsible to Purchaser, nor be deemed to have defaulted or breached these Terms and Conditions, for any failure or delay in fulfilling or performing any of these Terms and Conditions when and to the extent such failure or delay is caused by or results from acts or circumstances beyond the reasonable control of Penn Care, Inc., and/or the manufactures which Penn Care, Inc. represents including, without limitation, acts of God, flood, fire, earthquake, explosion, governmental actions, war, invasion or hostilities, terrorist threats or acts, riot or other civil unrest, national emergency, revolution, insurrection, epidemic, lockouts, strikes or other labor disputes (whether or not relating to either party's workforce), restraints or delays affecting carriers, inability or delay in obtaining supplies of adequate or suitable materials, or telecommunication breakdown, or power outage.

DEFAULT/ATTORNEY'S FEES

Purchaser is in default of the Terms and Conditions if any of the following occurs (except as prohibited by law): (i) Purchaser fails to perform any obligation that Purchaser has undertaken in these Terms and Conditions; or (ii) Penn Care, Inc., in good faith, believes that Purchaser cannot, or will not, pay or perform the obligations it has agreed to in the Terms and Conditions.



If Purchaser defaults, or in the event Penn Care, Inc. brings an action or proceeding to enforce the terms hereof or declare rights hereunder, Purchaser agrees to pay Penn Care, Inc. costs for collecting amounts owing, including, without limitation, court costs, attorney's fees (for attorneys who are not our salaried employees), and fees for repossession, repair, storage, and sale of Vehicles, all without relief from valuation and appraisal laws.

GOVERNING LAW

All of terms and provisions of the agreement and the rights and obligations of the parties hereto shall be interpreted and enforced in accordance with the laws of the State of Ohio.

REMEDIES

If Purchaser is in default of these Terms and Conditions, Penn Care, Inc. shall have all the remedies provided by law in these Terms and Conditions: (i) Penn Care, Inc. may require Purchaser to immediately pay Penn Care, Inc., subject to any refund required by law, the remaining unpaid balance due; (ii) Penn Care, Inc. may require Purchaser to make the Vehicle available to Penn Care, Inc. at a designated place that is reasonably convenient to each party; (iii) Penn Care, Inc. may immediately take possession of the Vehicle by legal process or self-help, but in doing so Penn Care, Inc. may not breach the peace or unlawfully enter onto Purchaser's premises; (iv) Penn Care, Inc. may then sell the Vehicle and apply what it receives as provided by law to Penn Care, Inc. reasonable expenses and then toward Purchaser's obligations; and (v) Except when prohibited by law, Penn Care, Inc. may sue Purchaser for additional amounts if the proceeds of a sale do not pay all of the amounts Purchaser owes to Penn Care, Inc. By choosing any one or more of these remedies, Penn Care, Inc. does not waive its right to use another remedy. By deciding not to use any remedy, Penn Care, Inc. does not give up its right to consider the event a default if it happens again.

PURCHASER

Signature: _____

Name/Title: _____

Date: _____



Quotation Summary

Travis Krieger 2 Braun Proposals 2023-02-02 15-07-20

Reference: QUO0000006907 **Rev:** 2
Purchaser: Penn Care
Contact: Taylor Pease
Address: 1317 North Road
Niles, OH

Opportunity: Perrysburg FD
Account: Perrysburg FD
Contact: Joel Whitmore
Shipping Address:

Telephone:

Currency: USD
Quotation Date: 2023-01-31
Expiration: 2023-03-02

Sales Contact: Travis Krieger
Mobile: 330-696-3066
Phone: 330-696-3066

Factory Contact: Kris Turner
Mobile:

Name	Specifications
Chief XL Type I	-72" Headroom -169"L Full Seam Welded Module
	

Product	Description	Quantity	Unit Net	Total Net
CHFSLI	173" long x 96" wide module with 74" headroom.	1.00	\$382,467.00	\$382,467.00

Price Details	Price
Chassis	73,476.00
Base and options	242,537.00
Custom Options	66,454.00
List Price Per Unit	\$382,467.00

**** Product quotes are valid for 30 calendar days. After 30 calendar days quotes are subject to change. Any applicable discounts will be added and validated at time of invoice. Discounts subject to change.**

Payment Terms:

FORCE MAJEURE "Company shall not be liable or responsible to Purchaser, or be deemed to have defaulted or breached these Standard Terms and Conditions, for any failure or delay in fulfilling or performing any of these Standard Terms and Conditions when and to the extent such failure or delay is caused by or results from acts or circumstances beyond the reasonable control of Company including, without limitation, acts of God, flood, fire, earthquake, explosion, governmental actions, war, invasion or hostilities, terrorist threats or acts, riot or other civil unrest, national emergency, revolution, insurrection, epidemic/pandemic, telecommunication breakdown, power outage, lockouts, strikes or other labor disputes (whether or not relating to either party's workforce), restraints or delays affecting carriers, inability or delay in obtaining chassis from an original equipment manufacturer or other supplies of adequate or suitable components or materials at reasonable prices."



Sales Options by Category

Braun - KKK Change Notice

Item Number	Name	Quantity	Price
00-01-0001	GENERAL CONDITIONS	1.00	Included
00-01-0006	DYNAMIC SIDE IMPACT & ROLLOVER TESTS	1.00	Included
00-01-0017	BIDDER IS KKK-A-1822F AMENDMENT 1 COMPLIANT	1.00	Included
80-10-0000	KKK-A-1822F COMPLIANCE PACKAGE KKK-A-1822F compliance sticker, electrical load analysis sticker, and payload sticker shall be installed in the oxygen compartment. Any deviations from KKK-A-1822F shall be listed in the vehicle delivery packet with a notation on the-compliance sticker.	1.00	Included
00-01-0029	NO CONTRACT REQUIRED NO STS, HGAC, FSA, SOURCEWELL or GPO contract required	1.00	Included
00-01-0072	100% PREPAY Purchaser will prepay 100% of total price.	1.00	Included

Braun - Chassis

Item Number	Name	Quantity	Price
SR00137422	AIR HORNS - BUELL DUAL TRUMPETS 10" and 12" THRU BUMPER W/ LANYRD Air Horn - (Buell) dual trumpets, one (1) 10" and one (1) 12", mounted thru front bumper, one each side, compressor per drawing. The air horns shall be activated by a push button located on the MCC (master control console) and by a lanyard cable installed in the OEM cab headliner area, unless otherwise stated	1.00	2,170.00
SR00137427	CUSTOMER SUPPLIED SECURE 3 KEY KNOX BOX-MCC: Braun is to install a customer supplied secure 3 key Knox Box (08796-2) to the cab console. Per console layout.	1.00	418.00
SR00137434	CODE 3 VITAL VIO DECONTAMINATION SYSTEM PCL-LED-VV PATIENT LIGHT VV, 48LED, 12-24VDC (BARE LEADS) Install (2) Code 3 Vital Vio Antimicrobial Light Disinfection units in cab Headliner.	1.00	1,267.00



SR00137455	PASS THROUGH - CAB TO MODULE, LOCKABLE SLIDING WINDOW Install: A lockable sliding window in the cab over the pass thru opening to the module.	1.00	Included
SR00137472	SIREN SPEAKERS, CAST PRODUCTS - IN FRONT BUMPER Two (2) Cast Products - 100-watt siren speakers, shall be installed in the the front bumper.	1.00	Included
SR00141249	CHIEF XL I AMBULANCE MODULE MY2025 Type I - Ambulance - Chief XL I Ford - 173" module length with 74" headroom. Manufactured in Van Wert, Ohio, USA	1.00	Included
SR00152318	BUMPER/GRILLE GUARD BUCKSTOP Install a Buckstop Outback Bumper/Grille Guard, Black	1.00	4,699.00
CH_F4550L	CHASSIS - FORD F550 193" WB 4X4 DRW (108 C.A.) DIESEL ENGINE FORD F550 CHASSIS CAB, 193" WB 4X4 DRW (108" C.A.)	1.00	Included
15-00-0010	FUEL TANK - FULL UPON FACTORY RELEASE The chassis fuel tank of the completed unit shall be full at time of release from the ambulance manufacturer's facility.	1.00	Included
20-10-0603	ENGINE BLOCK HEATER - OEM PLUG An engine block heater shall be included in the chassis with the 125 VAC power cord.	1.00	Included
20-20-0252	HEAT SHIELDS, PROTECTIVE Install: aluminized steel protective heat shields to the upper laterals above the exhaust system.	1.00	Included
20-20-0277	HIGH IDLE SYSTEM, AUTOMATIC A high-idle module will be added to the chassis. The high idle will be engaged automatically by the M-Tech system when all chassis parameters are met. Chassis parameters include but not limited to vehicle in park, service brake not depressed, accelerator not depressed, parking brake set. High-idle is also activated by the M-Tech heat or A/C.	1.00	Included
20-01-0105	SUSPENSION - LIQUID SPRING TYPE I Install: Liquid Spring	1.00	Included
20-10-0206	BATTERY - TWO SYSTEM - F SERIES CHASSIS	1.00	Included



	The vehicle shall have a 12 V two (2) battery system rated at 1500 cold cranking amps. Both batteries shall be securely installed in the Ford OEM locations, under the vehicle hood.		
20-21-0101	FLOOR CONSOLE F450/F550 STANDARD CONSOLE - ALUMINUM PLEASE NOTE: Console drawings are for reference only and do not include all features depicted on the drawings. All consoles shall be designed, priced, and approved internally to allow for accurate BOM pricing. The prices shown are estimated for general budget pricing only and pricing is subject to design; must contact manufacturer for pricing validation.	1.00	Included
20-10-0112	INBOARD ARM RESTS FOR ALUMINUM CONSOLE Install: inboard arm rests in the cab. (arm rests Havis Shields C-ARM-102 mount to the aluminum floor console)	1.00	Included
30-10-0030	BACKUP ALARM Install: (OSHA approved) back up alarm with a disable control for silent backing, located on the MCC (master control console).	1.00	Included
20-30-0806	RUNNING BOARDS - STAR PUNCHED DIAMOND PLATE Aluminum diamond plate running boards with a star punched non-skid surface shall be provided on the cab. The running boards shall be dip anodized after they are formed to retain finish and increase corrosion resistance.	1.00	Included
40-10-0117	DEF TANK FILL PROTECTOR - STAINLESS STEEL Install: stainless steel DEF tank fill protector per drawing.	1.00	110.00
40-10-0112	FUEL FILL PROTECTOR - STAINLESS STEEL Install: stainless steel fuel fill protector per drawing.	1.00	110.00
30-25-0204	LIGHTS RUNNING BOARD -WHELEN 2 inch round-LED Install: (1) pair of Whelen white TOCACCRR LED lights with black grommets, (1) each side, low on the module front, as running board lights, activated with the cab door switches. per dwg # 1 (Braun part #18105 Light and #18106 Grommet).	1.00	288.00
20-30-0202	MIRRORS, EXT OEM MANUAL TELESCOPING W/REMOTE & HEAT The chassis shall have OEM manual telescoping, folding trailer tow mirrors with power/heated glass, heated convex spotter mirror, integrated clearance lamps/turn signals.	1.00	Included



20-30-0261	OEM AUTO-LOCK DISABLED (cab & module doors do not auto lock or unlock) The OEM auto-lock feature will be disabled.	1.00	Included
20-20-0281	SECURITY SYSTEM - ANTI THEFT- IGNITION OVER RIDE Install Sound Off Ignition security system. (ignition over ride)	1.00	Included
30-10-0753	SIREN, WHELEN 295-HFSA7-REMOTE WITH MICROPHONE (Meets CA Title 13) A Whelen 295-HFSA7 remote dual siren amplifier shall be flush-mounted in the master control console located in the cab. The siren shall be capable of hands-free operation and shall be equipped with a noise canceling microphone. (Meets CA Title 13)	1.00	
20-40-0203	WHEELS, FORGED POLISHED ALUMINUM - 19.5 - F450/550 193" WB Forged, polished aluminum wheels shall be provided, to include bright hub covers and center ornaments and valve stem extensions.	1.00	Included

Braun - Electrical

Item Number	Name	Quantity	Price
SR00154109	LIGHTS, INTERIOR CABINETS, RIDGEBACK 12V LED STRIP LIGHT, BLUE All polycarbonate door(s), interior cabinets shall have Ridgeback 12V blue LED strip lights for interior compartment lighting.	1.00	994.00
SR00137418	OEM AUXILLARY SWITCHES, FLOODLIGHT ACTIVATION External change: Ford OEM aux switches to activate the floodlights. Furthest left switch shall activate the left flood light. The next switch to the right shall activate the middle flood light. The next switch to the right shall activate the right flood light. (SR137444)	1.00	Included
SR00137432	LOCKS POWER - PASSAGE, COMPARTMENTS, KEY FOBS Power door locks on module passage doors, and (6) OSS compartments, use OEM key fobs.	1.00	
SR00137465	OUTLETS, EXTERIOR OSS#3 Outlets Exterior OSS #3: (1)125VAC (1) 12VDC outlets in OSS #3 Upper, Rear Forward Wall.	1.00	218.00
SR00137475	SYSTEM ACTIVE AND CHECK OUT LIGHTS -Standard 15 MINUTES Switch: located at the curb and rear entry doors for activation of the V-MUX electrical system,	1.00	



check out light switch located at the curb and rear doors for activation of the left LED angled lights prior to entering the module, system programmed to shut down automatically after 15 minutes unless the ignition is on.

SR00137479	----- LIGHTS, OSS COMPARTMENTS - RIDGEBACK LED STRIP LIGHTING: Each outside storage compartment Ridgeback LED strip lighting located one each side of the door opening, activated by a magnetic switch, excluding battery compartment. Lengths dependent on OSS dimensions.	1.00	1,190.00
SR00137480	----- FRONT WALL OUTLETS: Install one (1) 125Vac and two (2) 12VDC outlets on the back wall of upper front wall cabinet #1. Install one (1) 125VAC and one (1) 12VDC outlet in the upper corner of front wall cabinet #2. Install one (1) 125VAC and one (1) 12VDC outlet in the upper corner of front wall cabinet #3, per dwg. #7. (7) outlets total for this line only.	1.00	763.00
30-06-0004	----- ELECTRICAL SYSTEM - WELDON V-MUX, MICRO PROCESSOR BASED Install: Weldon V-MUX 100% solid state microprocessor based multiplex system.	1.00	Included
30-10-0110	----- ELECTRICAL CIRCUITS All electrical circuits: shall have wiring and circuit protection suitable to the demand and must meet the national electric code (NEC) wiring requirements, added on wiring (18 GA through 10 GA) color coded and stamped with code numbers for easy identification, SLX high temperature thermoplastic cross link wire used. SGX insulated cable used for all under hood / underbody battery and charging system cable. High temperature (375° f) thermoplastic loom used on all harnesses.	1.00	Included
30-06-0126	----- ELECTRICAL COMPARTMENT (PDQ) - MULTIPLEX ELECTRICAL SYSTEM Electrical compartment / hinged door w/ (2) chrome locking lever latches/ located on the partition wall behind the attendant seat.	1.00	Included
30-06-0325	----- FLASHER - MULTIPLEX ELECTRICAL SYSTEM Provide: Flasher within and programmed by the multiplex electrical system.	1.00	Included
30-06-0350	----- FLASHING HEADLIGHTS - MULTIPLEX ELECTRICAL	1.00	Included



	SYSTEM Headlights (high beams) shall be programmed through the multiplex system to alternate flash (wig-wag). -----		
30-10-0190	GROUND FAULT CIRCUIT INTERRUPTER-GFCI Install: A 125 VAC, 20 AMP circuit breaker with ground fault circuit interrupter (GFCI) electronic ground leakage detection in the load center for the shoreline circuit. -----	1.00	Included
30-06-0285	MODULE DISCONNECT - MULTIPLEX ELECTRICAL SYSTEM Install: In-Power disconnect to keep the system power engaged after the ignition is switched to the "off" position. -----	1.00	Included
30-06-0575	REVERSE -TRANSMISSION- FUNCTIONS - MULTIPLEX ELECTRICAL SYSTEM System programmed to provide activation for: rear outboard warning lights, rear side warning lights, rear scene lights, the rear side scene lights - when the transmission selector lever is placed into "reverse" position. -----	1.00	Included
30-06-0150	SPARE CIRCUIT - MULTIPLEX ELECTRICAL SYSTEM Provide (1) spare 15-amp circuit. -----	1.00	Included
30-06-0175	WIRING HARNESS CONNECTORS - MULTIPLEX ELECTRICAL SYSTEM Connect all wiring harnesses via quick connect circular plug connectors. -----	1.00	Included
30-06-0300	VOLTMETER - MULTIPLEX ELECTRICAL SYSTEM Provide: (1) digital voltmeter on the master control console screen. -----	1.00	Included
30-06-0026	WARNING DISPLAY - MULTIPLEX ELECTRICAL SYSTEM Install: digital warning display integrated into the cab display console, programmed through the multiplex system to provide visual and audible indication. -----	1.00	Included
30-06-0225	EMERGENCY MASTER SWITCH - MULTIPLEX ELECTRICAL SYSTEM Supply: A single emergency master switch for activating all the emergency warning lights on the master control console screen, emergency master switch will activate the module power automatically, include an Emergency Master Menu button to allow access to individual warning light functions. -----	1.00	Included
30-06-0250	CONTROL PANEL SWITCHES - MULTIPLEX ELECTRICAL SYSTEM	1.00	Included



	Switches on the master control console and attendant control panel screens shall have dimmable perimeter backlighting.		
30-06-0275	MODULE POWER SWITCH - MULTIPLEX ELECTRICAL SYSTEM Provide: A module power switch for the electrical system on both the Master Control Console and the Attendant Control Panel screens.	1.00	Included
30-06-0101	ATTENDANT CONTROL PANEL (ACP) - MULTIPLEX ELECTRICAL SYSTEM Attendant Control Panel (ACP) contains a color micro processor screen, controls all equipment installed in the patient compartment.	1.00	Included
30-06-0375	PARK OVERRIDE - MULTIPLEX ELECTRICAL SYSTEM Park override switch on the master control console screen, reactivates all lights disabled when the transmission is placed in the neutral/park position.	1.00	Included
30-06-0400	LOAD MANAGER-SEQUENTIAL SWITCHING SYSTEM - MULTIPLEX ELECTRIC SYSTEM Load manager-sequential switching system controlled by the microprocessor based electrical system: emergency master button shall control the sequential switching of the emergency lights and/or other warning devices, load manager shall automatically shed non-critical electrical loads during low voltage conditions.	1.00	Included
30-06-0450	FRONT CLEAR DISABLE SWITCH - MULTIPLEX ELECTRICAL SYSTEM Activation of the switch on the master control console screen to disable all forward-facing clear warning lights.	1.00	Included
30-06-0076	MASTER CONTROL CONSOLE (MCC) - MULTIPLEX ELECTRICAL SYSTEM Floor mounted Master Control Console (MCC) located in the cab, housing siren, color microprocessor display screen, controlling all the Emergency Warning functions, Patient Compartment lighting and module heat/ac functions.	1.00	Included
30-06-0475	CURBSIDE SCENE LIGHTS ON WITH CURBSIDE DOOR The Curbside scene lights: programmed to activate when the Curbside door is in the open position.	1.00	Included
30-06-0500	REAR SCENE LIGHTS ON WITH REAR DOORS OPEN Rear scene lights programmed to activate when the rear doors are in the open position.	1.00	Included
30-06-0525	DISABLE SWITCH FOR REAR SCENE LIGHTS - MULTIPLEX	1.00	Included



	ELECTRICAL SYSTEM Install: disable switch at the rear door area to disable the rear scene lights.		
30-06-0550	DISABLE SWITCH FOR SIDE SCENE LIGHTS - MULTIPLEX ELECTRICAL SYSTEM A disable switch shall be installed at the curbside door area to disable the curbside scene lights.	1.00	Included
30-06-0010	VISTA IV MCC - PUSH BUTTON Install: Weldon V-MUX Vista IV interface module / display screen in the cab, operated through the use of push buttons.	1.00	Included
30-10-0903	VISTA DISPLAY SCREEN - PUSH BUTTON - CURBSIDE - FIXED ANGLED One (1) Vista screen shall be provided in the patient compartment on the curbside wall on a fixed angled mount with removable plate per the location on dwg. #6.	1.00	1,576.00
30-06-0050	DAYTIME RUNNING LAMPS - MULTIPLEX ELECTRICAL SYSTEM OEM Daytime Running Light headlights activated for daytime operation, when transmission is placed in drive.	1.00	Included
30-10-0073	CAMERA PATIENT AREA SINGLE SYSTEM - VISTA SCREEN Install: camera system to monitor the patient compartment, tied to M-Tech display screen. See Dwg #8	1.00	722.00
30-10-0071	CAMERA REAR VIEW - SINGLE SYSTEM - VISTA SCREEN Install: camera system rear view, tied to M-Tech display screen. Per Dwg #2. Camera alignment will be conducted at final inspection, if applicable.	1.00	Included
30-10-0150	FAN - CIRCULATION INSTALLED IN ELECTRICAL COMPARTMENT Install: Circulation fan in PDQ compartment	1.00	Included
30-10-0585	USB - DUAL OUTLET, ONE (1) INTERIOR LOCATED ON CONSOLE Install: (1) dual USB port outlet, 5 volt / 2.1 amp, in the vehicle, located on the Master Control Console in the cab.	1.00	Included
125ADD	OUTLET, ADDITIONAL-125VAC Cab behind the passenger seat	1.00	109.00



30-10-0258	INVERTER, VANNER - 1100 WATT, LIFESINE LSC 12-1100-DC CHARGER Install: Vanner LifeSine LSC 12-1100-DC watt inverter with battery conditioner / charger per drawing (non-hardwired).	1.00	1,976.00
30-12-0001	RECEPTACLE SHORELINE INLET-SUPER 20 AMP, AUTO EJECT - YELLOW COVER Install: Kussmaul super auto eject shoreline inlet receptacle with yellow cover on module exterior (forward street side) near the driver's door, equipped with an integral dynamic disconnect.	1.00	Included
30-10-0094	SHORELINE INDICATOR LIGHT- ALLIED VCC GREEN MINI NEON - EXTERIOR MOUNTED Install: (1) Allied VCC green mini neon indicator light above the shoreline inlet per drawings. The indicator shall illuminate when shoreline power is present at the inlet.	1.00	Included
30-10-0657	RADIO ANTENNA BASES - TWO (2) Enter antenna information here Two (2) antenna bases with attached coax cables shall be installed on the module roof. The coax cables shall terminate in the PDQ. Access to the antenna bases shall be through adjacent module interior dome lights.	1.00	Included
30-10-0299	LIGHT, ATTENDANT CONTROL PANEL AREA - TECNIQ SILHO-X LED - WARM WHITE A Tecniq Silho-X 2.75" round warm white LED light with SS trim ring, shall be mounted above the left wall forward action area counter. The light shall be operated through a button on the ACP Vista screen labeled "Attendant Light". (Braun #26415)	1.00	Included
30-10-0310	LIGHT, LED ELECTRICAL COMPARTMENT -PDQ A 12 VDC LED light shall be located in the PDQ. The light shall be wired "battery-hot" to activate when the PDQ door is in the open position. The light shall be off when the door is in the closed position.	1.00	Included
30-11-0106	LIGHTS, DOME LED (8) WHELEN SUPER LED Eight (8) Whelen #LED (80C0EHCR) dome lights, shall be installed. See dwg #9	1.00	Included
40-10-0151	SWITCH DOOR UNLOCK, WATERPROOF - HIDDEN IN FRONT GRILLE AREA Install: exterior hidden door unlock switch in grille area.	1.00	Included
30-06-0201	RADIO TIE-IN POINT - (1) 12V/40 AMP - CAB CONSOLE AREA Install (1) set of 12 volt/40 amp radio tie-in studs in cab	1.00	Included



console: (1) battery hot, (1) ignition hot, (1) grounded stud.

30-06-0202	RADIO TIE-IN POINT - (1) 12V/40 AMP - PATIENT COMPARTMENT Install (1) set of 12 volt/40 amp radio tie-in studs in patient compartment: (1) battery hot, (1) ignition hot, (1) grounded stud.	1.00	Included
30-06-0203	RADIO TIE-IN POINT - (1) 12V/250 AMP - PDQ Install (1) set of 12 volt/250 amp radio tie-in studs in the PDQ: (1) battery hot, (1) ignition hot, (1) grounded stud.	1.00	Included

Braun - Exterior Lighting

Item Number	Name	Quantity	Price
SR00137414	LIGHTS -FONT MODULE-(2) WHELEN 600 ROTO-BEAM LED Install two (2) Whelen 600 Roto-beam LED lights on the front of the module, outboard of the warning lights. Per dwg #1	1.00	830.00
SR00137423	LIGHTS, UNDERBODY TECNIQ E10 LED Install: (6) Tecniq E10 white LED lights mounted on brackets underneath the module, turn on automatically when the vehicle is shifted into park, also activated or disabled by a switch on the MCC Vista display screen (Braun #27245).	1.00	946.00
SR00137425	LIGHTS - (4) WHELEN 700 SCENE LIGHTS - CONDENSER Install four (4) Whelen 700 LED scene lights with chrome flanges to the condenser. There shall be two (2) on the front of the condenser and one (1) on each side.	1.00	525.00
SR00137444	LIGHTS, FRONT MODULE FLOOD (1) - WHELEN PIONEER PLUS (PCH2) COMBO- FLOOD & SPOT A Whelen Pioneer Plus LED (PCH1) dual panel combination floodlight with (PBH103) recessed housing shall be installed in the center position. These light shall operate from The OEM switches in the Cab. Furthest Left Switch to activate the Left flood light, the next shall operate the Front and the third switch from the left is to operate the right flood light.	1.00	1,418.00
SR00137451	LIGHTS FRONT MODULE - 4 WHELEN 900 SUPER RED LED Four (4) Whelen 900 series super LED RED warning lights with chrome bezels shall be installed on the module front. The lights shall operate from a switch on the master control console, labeled "Flashers". FRONT	1.00	Included



WARNING LIGHT LOCATION 2 - RED The warning light located on the upper front of the module in location 1 shall be red. FRONT WARNING LIGHT LOCATION 3 - RED The warning light located on the upper front of the module in location 2 shall be red. FRONT WARNING LIGHT LOCATION 5 - RED The warning light located on the upper front of the module in location 3 shall be red. FRONT WARNING LIGHT LOCATION 6 - RED The warning light located on the upper front of the module in location 4 shall be red.

SR00137459	----- LIGHT INTERIOR OF REAR FACING OSS & PASSAGE DOORS, TWO (2) RED MINI LED PER DOOR Two (2) Whelen red Mini LED lights shall be installed on the interior of all rear facing exterior compartment and patient entry doors. The lights shall be located as follows: one (1) on each upper and lower outer corner. The lights shall random flash upon door opening. (does not include the battery door) (16 lights)	1.00	1,066.00
SR00137463	----- LIGHTS, RUB RAIL - WHELEN LED STRIP - 4 EACH SIDE Install: Whelen strip lights on rub rail, (4) LED's each side - (2) red LED's and (2) white LED's alternating in color (red-white-red-white) along the module side, total of eight (8) lights, alternate flash with box warning lights.	1.00	1,322.00
SR00137471	----- LIGHTS, SIDE MODULE FLOOD (2) - WHELEN PIONEER PLUS LED DUAL (PFH2) Two (2) Whelen Pioneer Plus LED (PFH2) dual lamp floodlights with (PBH203) chrome trim ring shall be installed, one (1) each module side in the center position. These lights shall operate from The OEM switches in the Cab. Furthest Left Switch to activate the Left flood light, the next shall operate the Front and the third switch from the left is to operate the right flood light.	1.00	3,165.00
SR00137481	----- LIGHTS GRILLE - WHELEN 500 SUPER LED Four (4) Whelen 500 series super LED warning lights, with waterproof connectors shall be installed the grille area of the chassis. The lights shall operate from a switch on the master control console labeled "Flashers".	1.00	225.00
30-06-0410	----- WARNING LIGHTS FLASH PATTERN SIGNAL ALERT 75 - MULTIPLEX ELECTRICAL SYSTEM The default flash pattern for the vehicle warning lights: Signal Alert 75.	1.00	Included



ClearLENS	CLEAR LENSES ON ALL WARNING LIGHTS	1.00	Included
STRPTRN	STRAIGHT PATTERN WARNING LIGHTS The front warning lights will be aligned in a straight pattern across the module.	1.00	Included
30-25-0122	LIGHTS, ICC / LED CLEARANCE - ON MODULE FRONT - TECNIQ Install: (5) amber Tecniq LED (S33-AA00-1) clearance / ICC lights on the front of the module near the roof line per dwg #1.	1.00	Included
30-25-0123	LIGHTS, ICC / LED CLEARANCE - ON MODULE REAR - TECNIQ Install: (5) red TECNIQ LED (S33-RR00-1) clearance / ICC lights on the rear of the module near the roof line per dwg #2.	1.00	Included
ROL090002	LIGHTS REAR MODULE, UPPER OUTER - 2 WHELEN 900 LED Two (2) Whelen 900 series super LED warning light with chrome bezels shall be installed on the upper rear of the module, in the outer location. The lights shall operate from a switch on the master control console, labeled "Flashers".	1.00	Included
ROLCLR1R	REAR OUTER MODULE LIGHT LOCATION 1 - RED The warning light located on upper rear of the module, in outer location 1 shall be red.	1.00	Included
ROLCLR2R	REAR OUTER MODULE LIGHT LOCATION 2 - RED The warning light located on upper rear of the module, in outer location 2 shall be red.	1.00	Included
RCL060001	LIGHTS REAR MODULE, UPPER CENTER - 1 WHELEN 600 LED One (1) Whelen 600 series super LED warning light with a chrome bezel shall be installed on the upper rear of the module, center location. The light shall operate from a switch on the master control console, labeled "Flashers".	1.00	Included
RCLCLR1A	REAR CENTER MODULE LIGHT LOCATION 1-AMBER The warning light located on upper rear of the module in the center location shall be amber.	1.00	Included
RS060002	LIGHTS REAR SCENE - 2 WHELEN 600 LED Two (2) Whelen 600 Series super LED scene/load lights with chrome bezels shall be installed on the upper rear of the module. The lights shall operate from a switch	1.00	Included



	on the master control console, labeled "Rear Scene Lights".		
30-26-2002	TRAFFIC ADVISOR REAR OF MODULE WHELEN TAL-85 Install: Whelen #TAL-85 LED directional light bar on the rear of the module per dwg #2, to have a multi-function controller mounted in the OEM chassis cab in console with cut out on top plate to accommodate multifunction controller switch.	1.00	1,518.00
WL090002	LIGHTS REAR WINDOW - 2 WHELEN 900 SUPER LED Two (2) Whelen 900 series super LED warning lights with chrome flanges shall be installed on the rear of the module at window level, one (1) on each side. These lights shall operate from a switch on the master control console, labeled "Flashers".	1.00	Included
WLCLR1R	WINDOW LEVEL LIGHT LOCATION 1 - RED The warning light located on rear of the module at window level, location 1 shall be red.	1.00	Included
WLCLR2R	WINDOW LEVEL LIGHT LOCATION 2 - RED The warning light located on rear of the module at window level, location 2 shall be red.	1.00	Included
30-26-3008	LIGHTS, REAR TAIL - WHELEN 600 LED STOP, TURN, & MINIMUM INTENSITY BACK-UP Install: (1) pair each of Whelen 600 series LED stop/tail lights, turn lights, and LED MINIMUM intensity back-up lights with chrome bezels on rear of the module.	1.00	Included
30-26-7002	LIGHT, LICENSE PLATE LED - WHELEN OACOEDCR Install:(1) Whelen OACOEDCR LED license plate light with 45 deg angled chrome-plated bezel on the rear of module, lower left side.	1.00	Included
FIL07T0002	LIGHTS FRONT INTERSECTION - 2 WHELEN 700 LED W/15 DEGREE TILT HOUSING Two (2) Whelen 700 series super LED warning lights, with water-proof connectors, shall be mounted in 15 degree tilt housings on the front chassis fenders, one (1) on each side. The lights shall operate from a switch on the master control console labeled "Flashers". NOTE: When vehicle is placed in park, the override switch must be on for intersection light(s) to remain on.	1.00	Included
FILCLR1R	FRONT INTERSECTION LIGHT LOCATION 1 - RED The warning light located on front of the chassis fender in location 1 shall be red.	1.00	Included
FILCLR2R	FRONT INTERSECTION LIGHT LOCATION 2 - RED The warning light located on front of the chassis fender	1.00	Included



	in location 2 shall be red. -----		
RIL070002	LIGHTS INTERSECTION REAR - 2 WHELEN 700 LED Two (2) Whelen 700 series super LED warning lights with, chrome flanges and water-proof connectors, shall be installed above the rear wheel wells, one (1) on each side. These lights shall operate from a switch on the master control console screen labeled "Flashers". NOTE: When vehicle is placed in park, the override switch must be on for intersection light(s) to remain on. -----	1.00	Included
RILCLR1R	REAR INTERSECTION LIGHT LOCATION 1 - RED The warning light located on above the rear wheel well at location 1 shall be red. -----	1.00	Included
RILCLR2R	REAR INTERSECTION LIGHT LOCATION 2 - RED The warning light located on above the rear wheel well at location 2 shall be red. -----	1.00	Included
30-27-1102	LIGHTS, ICC / LED CLEARANCE - ON MODULE SIDE - TECNIQ Install: (2) red Tecniq LED (S33-RR00-1) clearance/ICC lights, (1) red on each side at rear of the vehicle, flash with turn signal, per Dwg #3 and #4. -----	1.00	Included
SWL090004	LIGHTS SIDE WARNING - 4 WHELEN 900 SUPER LED Four (4) Whelen 900 series super LED warning lights with chrome flanges shall be installed, two (2) on each side of module exterior per dwg. -----	1.00	Included
SWLCLR1R	SIDE WARNING LIGHT LOCATION 1 - RED The warning light located on side of the module, in outer location 1 shall be red. -----	1.00	Included
SWLCLR2R	SIDE WARNING LIGHT LOCATION 2 - RED The warning light located on side of the module, in outer location 2 shall be red. -----	1.00	Included
SWLCLR3R	SIDE WARNING LIGHT LOCATION 3 - RED The warning light located on side of the module, in outer location 3 shall be red. -----	1.00	Included
SWLCLR4R	SIDE WARNING LIGHT LOCATION 4 - RED The warning light located on side of the module, in outer location 4 shall be red. -----	1.00	Included
SS090004	LIGHTS SIDE SCENE - 4 WHELEN 900 24 DIODE LED Four (4) Whelen 900 series 24 Diode LED scene lights with chrome flanges shall be installed, two (2) each module side. These lights shall operate from switches on the master control console labeled "Left Scene Light" and "Right Scene Light".	1.00	Included



Braun - Module Body Construction

Item Number	Name	Quantity	Price
SR00137431	CUSTOM MODULE LENGTH & HEIGHT Module Headroom to be 74" and Length to be 173"	1.00	7,200.00
39-00-0005	AWS ALUMINUM CERTIFIED WELDERS	1.00	Included
39-10-0003	CONNECTIONS, MODULE Bolt: to the chassis frame rail with (12) 5/8" -11 grade 8 bolts through OEM rubber insulating spacers installed on outriggers at twelve (12) separate locations (six each frame rail), providing noise insulation and easy removal for chassis replacement, mounting bolts to be properly torqued and secured with locktite, system used for fastening the module to the frame to be that approved by the chassis manufacturer.	1.00	Included
40-00-0080	INSULATION - POLYURETHANE SPRAY FOAM The walls, ceiling, passage doors, outside storage doors, the entire underside of the module floor (except for mounting pads), the underside of the outside storage compartments, the wheel wells, and the underside of the curbside step area shall be completely foam - in - place insulated with nominal 3/4" thick sprayed on Class I, urethane foam for thermal and acoustical insulation. The insulation shall comply with FMVSS #302 flame spread requirements. The underside of the body shall be properly prepared to ensure adhesion before the spray insulation is applied.	1.00	Included
39-00-0001	MODULE BODY CONSTRUCTION - SEAMLESS Module: fabricated entirely of parts cut and formed from .125" (minimum) thickness 5052-H32 flat aluminum sheet stock, using CNC machines capable of .010" repeatability. This is the only alloy that may be used for body parts that are welded together. Roll-cage type interior super-structure, aluminum partition and module welded together into a single unit, roof designed with a minimum 1.5" crown to facilitate water run-off. Floor, roof, sides, all exterior doors fabricated from .125" (minimum) thick flat aluminum sheet stock, exterior joints between the roof and side components continuous full seam welded the entire length of the module. All exterior body panel joints continuous full seam welded. No VHB bonding tape or other adhesives used in the construction of the ambulance module.	1.00	Included



39-00-0002	SOLE SOURCE MODULE BODY CONSTRUCTION	1.00	Included
------------	--------------------------------------	------	----------

Braun - Module Features / Exterior

Item Number	Name	Quantity	Price
SR00137430	RUB RAILS, ANODIZED ALUMINUM, "C" CHANNEL Install: bright dip anodized aluminum "C" channel rub rails on lower sides of body below outside compartment sill areas, rub rails to be offset 3/16" from body.	1.00	1,532.00
SR00137437	OSS #1 - EZ-O2 LIFT OXYGEN SYSTEM OSS #1 streetside forward, with an EZ-O2 lift system, for housing an O2 cylinder. Install a fixed shelf 62" from the floor with a gasket to seal against the door to seal off the upper section of the compartment. Air horn compressor, suction pump, and inverter to be located above the shelf, louvers in the upper section, sound deadening material. Door post changes on forward side of OSS #1.	1.00	4,489.00
SR00137457	OSS #4 - BACKBOARD AND (2) ADJUSTABLE SHELVES WITH OUTSIDE ACCESS AND FIXED DIVIDER OSS #4 curbside rear, with one (1) fixed vertical divider for backboard/scoop stretcher storage on one side and and two (2) adjustable shelves. Door open as far as possible and no track on the lower 32", referene 8196.	1.00	Included
SR00137462	OSS #2 - (2) ADJUSTABLE SHELVES OSS #2 streetside center, with two (2) adjustable shelves.	1.00	Included
SR00137478	OSS #4A - OPEN STORAGE Outside storage compartment #4A, lower Curbside, located between compartment #4, and wheel.	1.00	1,434.00
SR00152319	OSS #3 DOUBLE DOORS OSS #3: OSS #3: Double doors-Outside Access Only. Full height cabinet with shallow upper portion. (1) Adj. Shelf. (shelf depth adjusted to allow for the full length tapping plate) in full depth lower section. Upper and lower section both to have a full size exterior tapping plate for post production tool mounting. Upper section to have minimum of 12" depth from tapping plate to doors. 2 Zico SCBA brackets (installed at final inspection) to be affixed to the upper section tapping plate. Doors to open as wide as possible.	1.00	2,255.00



40-00-0009	----- ALUMINUM PARTS - MODULE EXTERIOR All unpainted exterior aluminum parts to be bright dip anodized after fabrication to retain the finish and increase corrosion resistance.	1.00	Included
40-00-0010	----- CORROSION MINIMIZATION - MODULE All module contact with dissimilar metals shall be minimized with the use of nylon screw-hole inserts to provide hinge to door isolation with the module body, polypropylene strip hinge Isolation, polyethylene backed rubber tape, ceramic coated stainless steel hinge bolts, and ECK brand corrosion inhibitor spray.	1.00	Included
40-00-0020	----- DOOR CONSTRUCTION - GASKET PLACEMENT All exterior hinged module doors shall be constructed in an inverted pan-formed design. The pan shall be constructed from .125" thick 5052-H32 flat sheet aluminum. The exterior door skin shall be constructed of .190" thick aluminum and welded to the pan. Door gaskets shall be attached to the interior side of the door skin on the top, bottom and outer edge of the door. The gasket on the hinge side of the door will be attached to the door frame.	1.00	Included
40-00-0060	----- EXTERIOR COMPARTMENTS - SWEEP-OUT Exterior module compartments: a sweep-out design to aid in facilitation of the purchaser's routine care and cleaning of the vehicle. All exterior compartment floors, with the exception of the front ALS compartment to be constructed to be flush with the bottom door frame.	1.00	Included
40-00-0030	----- EXTERIOR COMPARTMENTS DESIGN All exterior compartments shall be vented and include: sound absorbing slip resistant polyurethane material sprayed on the inside of all compartments and compartment shelving, slide out trays and closeouts, baffled seep holes provided to prevent water from splashing or seeping into the exterior compartments, full-length, two-way adjustable, stainless steel hinges on all exterior compartment doors with 3/16" stainless steel hinge pins, compartment doors installed, flush with the module body, when double doors are provided, each door to have exterior handle, but only the forward door lockable, rearward door is secured when forward door is locked), all exterior compartments and passage doors keyed alike, lockable Eberhard "free-floating" type chrome plated handles with rotary locks. Gasket installed under each handle to protect the paint; drip rails installed above all exterior compartment doors.	1.00	Included



40-00-0055	----- EXTERIOR COMPARTMENTS, VENTING - OXYGEN STORAGE (9) square inches (minimum) of venting provided in the exterior oxygen storage compartment, to dissipate any leaking oxygen gas. -----	1.00	Included
40-00-0070	----- HANDLES, EBERHARD - CHROME FREE FLOATING TYPE Install: Eberhard #EMC-1-2110 chrome "free-floating" handles on each exterior module door, large enough to accommodate a gloved hand. -----	1.00	Included
40-10-0072	----- LOWERED MODULE SIDES Module sides to be as low as possible and still comply with KKK-1822-F ramp break over angle. -----	1.00	Included
40-10-0321	----- STEPWELL, CURBSIDE DOORWAY - MID STEP AREA Install: aluminum diamond plate step well and mid-level step in curbside doorway threshold area. -----	1.00	Included
40-00-0091	----- THRESHOLD, STAINLESS STEEL - ALL OSS STORAGE COMPARTMENTS Each exterior storage compartment with a hinged door: stainless steel lower threshold at the door opening to protect the paint. -----	1.00	Included
40-10-0340	----- STONE GUARDS, MOD FRNT -ANODIZED DIAMOND PLATE Install: anodized aluminum diamond plate stone guards on module front, (1) each side. -----	1.00	Included
40-10-0066	----- DOOR SLIDING - MODULE CURBSIDE PASSAGE Install EZ Glide curb door. -----	1.00	Included
40-10-0088	----- DOORS - REAR PASSAGE Patient compartment rear door opening: doors flush without a protruding flange or lip, right rear passage door lockable, chrome exterior handle, left rear door non-locking, chrome exterior handle, all handles installed with a gasket, hinge full length stainless steel with a 3/16" stainless steel hinge pin, two-way adjustable, each rear door two-point slam action automotive type rotary latching system to the body, right rear door lock to the body at the top and bottom, not to left rear door, doors .213" steel door latch activator rods with clevis adjusters, doors lockable from inside and outside, shut on molded, air-core, automotive type door seals to prevent water from leaking into vehicle interior. -----	1.00	Included
40-10-0130	----- EMERGENCY RELEASE LEVER, REAR PATIENT PASSAGE -----	1.00	Included



	DOORS Install emergency release lever, attached to each rear passage door latch to be free-floating from the interior door linkages. -----		
40-10-0505	WINDOWS, PASSAGE DOOR - (CURB SLIDING, REAR FIXED) Curbside passage door (sliding) window with removable screen, rear passage doors w/ non-openable window, windows 69% dark tint, secured with black oxide coated fasteners, open doors not to block warning lights. -----	1.00	Included
40-10-0103	FENDERETTES - POLISHED ALUMINUM Install: Polished aluminum fenderettes around the rear wheel well openings. -----	1.00	Included
40-10-0119	HOLD-OPEN - REAR DOORS - GRABBERS Install: door grabbers (1 pair) with hard rubber inserts on rear doors. -----	1.00	Included
40-10-0360	KICKPLATE/THRESHOLD, REAR DOORWAY - ANODIZED DIAMOND PLATE Install: anodized aluminum diamond plate kick plate at the rear exterior doorway, providing a kick / scuff plate at rear of the vehicle above rear step, per dwg # 2. -----	1.00	Included
40-10-0204	MUD FLAPS, REAR - BLACK RUBBER FIBERGLASS REINFORCED - THREE COLOR Install black rubber, fiberglass reinforced mud flaps with a minimum 1/4" thickness bolted to underside of module behind rear wheels, to provide adequate coverage of rear dual wheels of the chassis, mud flaps to be (3) color with the Manufacturers Logo. -----	1.00	Included
40-10-0266	REAR STEP/BUMPER -FLIP-UP CENTER SECTION - STAR PUNCHED AND ANODIZED Affix: rear bumper to chassis frame, constructed with a hinged center section, (2) steel braces to secure step to chassis frame, outer 17" on each end of bumper constructed from heavy gauge stamped polished stainless steel bumper parts, to provide smooth rounded corners, step constructed of star punched .125" thick aluminum diamond plate, (2) rear LED step illumination lights provided. All diamond plate surfaces to be anodized; strip of black PVC installed on face of step. -----	1.00	Included
40-10-0381	TOW HOOKS, MODULE REAR Secure: fasten (2) tow hooks in rear step area to rear step braces. -----	1.00	Included



40-00-0019	DOOR SKINS, OUTSIDE STORAGE COMPARTMENTS - DIAMOND PLATE INTERIOR SKINS Interior door skins for all outside storage compartments constructed of .063" thick aluminum diamond plate. -----	1.00	Included
OS102EZ	OSS #1 - OXYGEN STORAGE EZ O2 LIFT An E-Z O2 lift shall be mounted to the door as an assisted lift for the H and M cylinders. -----	1.00	Included
OS2XL1STD	OSS #2 - STREETSIDE CENTER OSS #2 streetside center, hinged double doors with spring-loaded gas cylinders, handles installed on the exterior of each door, forward door with locking handle. -----	1.00	Included
OS2SHELF2	OSS #2 - SHELVES TWO (2) ADJUSTABLE WITH TRACK Outside storage compartment #2 shall contain two (2) adjustable shelves with track. -----	1.00	Included
OS5XL1STD	OSS #5 - CURBSIDE FORWARD OSS #5 curbside forward, hinged door with spring- loaded gas cylinder, locking handle installed on the exterior of the door. -----	1.00	Included
OS5XL1OP1	OSS #5 - INSIDE/OUTSIDE ACCESS TO THE ALS CABINET - #5B OPEN STORAGE AREA OSS #5 curbside forward, inside/outside access to the ALS cabinet, and #5B lower storage area. -----	1.00	Included

Braun - Module Interior / Patient Compartment

Item Number	Name	Quantity	Price
SR00137413	ACTION AREA The action area is to include suction control, (1) 125VAC (1) 12VDC (1) dual USB outlet, (2) ohio Med oxygen outlets and bypass valve. Vista screen mounted on angled flip-down panel with chrome lever latches. -----	1.00	2,160.00
SR00137424	CABINET -FRONT WALL CABINETS WITH CARGO NETS, (3) ADJ. SHELVES: Front wall, interior cabinet #2 and #3 shall each be single compartment and have a RED cargo net on each, Buckles shall be installed on the bottom of the net and compartment shall each have an adjustable shelf and also have an adjustable shelf acting as a barrier between the cabinets per dwg. #7. -----	1.00	1,425.00
SR00137433	CABINET - SLIDING POLYCARBONATE DOORS WITH (1) FIXED SHELF, SHALLOW DEPTH STORAGE RECESSED INTO OSS #3 Left wall rear interior cabinet (#3): fixed frame, sliding polycarbonate doors w/ full length	1.00	1,026.00



	handles, the outer most sliding door to have handles on both ends, (1) fixed shelf, shallow depth storage, with top/bottom dividers (6 top/6 bottom). Sliding polycarbonate doors and flip up restocking frame.		
SR00137435	----- CABINET - HINGED ALUMINUM DOOR WITH CENTER SQUEEZE LATCH AND GAS SHOCK HOLD-OPEN Front wall over pass thru interior cabinet (#5): cabinet w/ (1) flip up hinged aluminum door with gas filled hold-open shocks, center squeeze latch. Temperature adjustable warming plate with thermostat within cabinet.	1.00	1,158.00
SR00137436	----- ASPIRATOR / SUCTION - SSCOR - WITH ELECTRIC PUMP - RECESSED A SSCOR suction system shall be recessed into the street side lower interior wall near the attendant's seat per dwg. #5 dimensions. The 12 VDC SSCOR electric vacuum pump to be installed in OSS #1 compartment. (must use SSCOR pump and tubing)	1.00	Included
SR00137439	----- STAINLESS STEEL WALL PROTECTION - INTERIOR STREETSIDE: A brushed stainless steel panel shall be provided on the street side wall 6" from the Floor. Per dwg. #5.	1.00	Included
SR00137443	----- STREET SIDE INTERIOR DRAWER #5 Cabinet with solid acrylic countertop pull-out drawer toward the bench with 3 front-to-back adjustable dividers within drawer locking stainless steel flush pull latch.	1.00	1,104.00
SR00137445	----- OXYGEN OUTLET (1) CEILING - OHIO MED - AT FOOT OF COT AREA: One (1) Ohio Medical flush mounted, quick release oxygen outlet shall be installed in the ceiling above the foot of cot area	1.00	Included
SR00137446	----- OVERHEAD CABINETS WITH HINGED POLYCARBONATE DOORS, GAS SHOCK HOLD-OPENS, AND CENTER SQUEEZE LATCHES. Curbside interior cabinets #1 & #2 above the seating area with hinged polycarbonate doors with six (6) adjustable dividers in each cabinet. each flip door shall have a center squeeze latch per dwg. #6.	1.00	1,197.00
SR00137448	----- SHARPS-STREETSIDE add hinged door and hinged acrylic flap with an ABS funnel on the bottom side of the acrylic flap to the top of the counter top, over the	1.00	955.00



sharps cutout. Sharps container will be a customer supplied 4.7qt container.

SR00137456	----- ASSIST HANDLES, (2) 'V-BARS' KNURL STYLE, (4) KNURL ASSIST A total of eight (8) assist handles shall be provided: two (2) 1-1/4" diameter Knurl style 'V' handles, one (1) on each passage door; and six (6) 12" Knurl assist handles: two (2) handles at the rear doorway-one on each side, one (1) at the curbside doorway, one (1) on the curbside door per dwg. #6, one (1) at the end of the squad bench in the stepwell area per dwg. #8, one (1) on the exterior by the forward curbside door per dwg. #4.	1.00	1,221.00
SR00137458	----- CABINET - (2) PULL-OUT DRAWERS TOWARDS THE CPR SEAT WITH LOCKING STAINLESS STEEL FLUSH PULL LATCHES Left wall interior cabinet (#5) below action area: two (2) vertically stacked drawers facing the CPR seat . Each drawer shall have a locking, stainless steel, flush pull latch 3 front to back adjustable dividers in each drawer	1.00	2,004.00
SR00137466	----- FRESH AIR INTAKE Install a fresh air intake on the curbside forward above the curbside doorway.	1.00	297.00
SR00137468	----- CABINET - RESTOCKNG FRAME WITH SLIDING POLYCARBONATE DOORS AND (1) FIXED SHELF Left wall, upper rear interior cabinet (#1): sliding polycarbonate doors w/ a flip-up restocking frame, gas filled hold-open shocks, full length handles w/ outer most sliding door to have handles on both ends, (1) fixed shelf, 2 ea top/bottom dividers	1.00	1,218.00
SR00137470	----- CURBSIDE CABINET AT HEAD OF BENCH Cabinet stack at head of squad bench. with (1) pull out drawer #4 toward bench. Install 3 front to back dividers in drawer #4. With locking stainless steel flush pull latch. Notch below drawer for access to a sharps/waste pull out drawer into the isle with a drop from the top hinged acrylic lid and a locking stainless steel flush pull latch. Install a (1)125VAC (1) 12VDC (1) dual USB above countertop, per dwg. #6. Front side of cabinet stack towards the step area is to be a Recessed (3) glove box holder per drawing #8	1.00	2,546.00
SR00137473	----- CABINET - RESTOCKNG FRAME WITH SLIDING	1.00	1,323.00



	POLYCARBONATE DOORS AND (1) FIXED SHELF Left wall, upper interior cabinet (#2): sliding polycarbonate doors, flip-up restocking frame w/ gas filled hold-open shocks, full length handles, outer most sliding door to have handles on both ends, (1) fixed shelf with top/bottom dividers (6 top/6 bottom).		
SR00137474	----- CABINET - HINGED POLYCARBONATE DOOR WITH CENTER SQUEEZE LATCH AND GAS SHOCK HOLD-OPEN Left wall upper interior cabinet (#6): cabinet w/ (1) flip up hinged polycarbonate door with gas filled hold-open shocks, center squeeze latch. -----	1.00	Included
SR00137485	STORAGE AREA, ABS OVER CURBSIDE DOOR Install an ABS storage area with plexiglass door and quarter turn latch, in the head pad over the curbside entry door.	1.00	Included
50-51-1001	----- CABINET CONSTRUCTION - INTERIOR - ALUMINUM All interior cabinets shall be constructed of .090" thick welded aluminum. -----	1.00	Included
50-51-1014	CATCH, MAGNETIC - ADHESIVE BACK FOR INTERIOR DOOR(S) OVER 36 INCHES All interior doors that are over 36" inches tall with a latch on the top of the door shall have an adhesive back magnetic catch installed on the bottom of the door. -----	1.00	Included
50-60-0220	EMBLEMS / SIGNS - REAR PATIENT COMPARTMENT (2) "No Smoking / Oxygen Equipped / Fasten Seat Belts" signs: (1) sign installed in the cab, (1) above the oxygen outlets in the patient compartment street side cabinet. -----	1.00	Included
50-60-0300	FLOOR CONSTRUCTION- PATIENT COMPARTMENT, NON-WOOD COMPOSITE Sub-floor in the patient compartment: constructed of .125" thick aluminum over .125" and .190" thick reinforcing hat sections and mounting laterals, aluminum sub-floor covered with a 3/4" non-wood composite material, all corner molding, edging and trim anodized aluminum or stainless steel and sealed to prevent fluids from seeping under the cabinets. -----	1.00	Included
50-60-0301	FLOORING - COVE Patient compartment floor radius: coved with pre-formed floor coving material, installed behind the vinyl floor covering, along both the street side and curbside walls.	1.00	Included



50-60-0391	----- HEADLINER - REAR PATIENT COMPARTMENT Headliner in the patient compartment shall be one-piece, seamless, .090 thick aluminum finished with sprayed-on multi-use polychromatic coating.	1.00	Included
50-51-1013	----- HOLD OPENS FOR INTERIOR DOORS All interior cabinets with doors less than 6" tall shall have friction hinges as hold opens for door(s). Doors 6" and taller shall be designed using gas shocks as hold opens for the door(s).	1.00	Included
50-60-0660	----- PADDED EDGING PROTECTION Install: padded corner edging where necessary on exposed corners and edges in the patient compartment for patient and attendant protection.	1.00	Included
50-00-0202	----- ROUNDED INTERIOR CORNERS Interior vertical edges: rounded/padded corners in the following locations: forward and aft edges of the CPR seat, the wall at the aft end of the squad bench, the partition opening cabinet edges and the upper front wall cabinet.	1.00	Included
50-51-1011	----- RECESSED ADJUSTABLE SHELF TRACK - CABINETS Install recessed adjustable shelf track in cabinets.	1.00	Included
50-51-5001	----- UPHOLSTERY - PATRIOT PLUS CHARCOAL #8605 All cushions, head pads and seating surfaces shall be covered with Patriot Plus Charcoal #8605	1.00	Included
50-60-0661	----- INTERIOR MODULE PADS Vinyl upholstered, foam cushioned head/back pads shall be installed as follows: the lower edge of the upper front wall cabinet (above the partition doorway or window), above the rear doors, above the side door, and on the street side wall behind and on each side of the CPR seat. The pads shall be covered with a flame-retardant color coordinated vinyl upholstery material.	1.00	Included
50-51-6003	----- LONPLATE II, NON-SLIP EMBOSSED SM. GRID - GUNMETAL #424 The floor in the patient compartment shall be covered with Lonseal brand "Lonplate II" non-slip; small grid (embossed) Gunmetal #424.	1.00	Included
50-51-2002	----- CABINET DOORS - CLEAR POLYCARBONATE All cabinet doors shall be clear polycarbonate material / installed in aluminum track lined with PPL inserts / An edge mounted aluminum handle shall be installed on	1.00	Included



	each sliding cabinet door.		
50-51-3001	CABINETS/ WALLS - POLYCHROMATIC COATING - MARBLE STONE Headliner, walls, cabinet faces, and cabinet interiors MultiSpec color to be Marble Stone	1.00	Included
IS-CNT-ACR	COUNTER TOP, SOLID ACRYLIC Install: solid acrylic countertop with 1/2" lip on the primary action area.	1.00	1,823.00
50-51-4055	COUNTERTOP - SOLID ACRYLIC - BLACK ONYX MIRAGE A solid acrylic counter top, Black Onyx Mirage.	1.00	Included
50-01-0301	INVENTORY CONTROL SYSTEM Install mini footman loops on the sliding door cabinet frames, and drill holes in the cabinet door handles for the inventory control system	1.00	120.00
50-01-0411	LATCHES, CABINET, CN10 COMPLIANT AS APPLICABLE The ACP (attendant control panel) door and the PDQ (power distribution quarters) door shall be secured with chrome locking lever latches, all remaining interior hinged cabinet doors with center squeeze latches (if applicable). All interior drawers with flush pull latches (if applicable).	1.00	Included
50-10-0226	LEFT WALL - ATTENDANT CONTROL PANEL - HINGED PANEL A hinged access panel and secured with two (2) latches to the immediate right of the attendant's seat, color microprocessor screen installed on the panel.	1.00	Included
IC-CNT-ACR	COUNTER TOP, CURBSIDE - SOLID ACRYLIC Install: solid acrylic countertop with 1/2" lip on the cabinet at the head of the curbside seating area.	1.00	1,111.00
50-50-0541	HOLD OPENS - SQUAD BENCH LID - GAS CYLINDERS Gas cylinder hold-open(s) shall be provided and installed to hold lid in the open and closed position.	1.00	Included
SQ-BN-BASE	SQUAD BENCH BASE W/STORAGE A storage area shall be provided in the squad bench base. The squad bench base shall be constructed of .090" thick aluminum for maximum storage capacity and minimum weight. The interior of the squad bench shall be sprayed with sound absorbing polyurethane material.	1.00	Included
IF3PDQ	CABINET - PDQ The Power Distribution Quarters (PDQ) shall hold electrical components, (i.e., power distribution nodes,	1.00	Included



	circuit breakers, etc.), hinged door with (2) chrome locking lever latches, located on the partition wall behind the attendant seat.		
50-60-0001	AIR PURIFICATION SYSTEM, ULTRAVIOLET Install a Ultraviolet Air Purification System within the heater/AC.	1.00	518.00
IF1XL1C4	CABINET - FRONT WALL, UPPER #1 - HINGED ALUMINUM DOOR W/INSERT The front wall interior cabinet #1, flip up hinged aluminum door with polycarbonate insert and gas shock hold-open(s), center squeeze latch, (1) adjustable shelf.	1.00	Included
IF1XL1OP4	CABINET WITH HINGED ALUMINUM DOOR WITH POLYCARBONATE INSERT AND CENTER SQUEEZE LATCH WITH (1) ADJUSTABLE SHELF Install cabinet with hinged aluminum door with polycarbonate insert and gas shock hold-open(s) in the upper front wall.	1.00	Included
IF3XL1OP1	CABINET - VENTED RADIO CABINET PDQ ABOVE Power Distribution Quarters (PDQ) compartment and a vented radio compartment below the PDQ, lower front wall, left.	1.00	Included
IF3XL1RAD	CABINET - FRONT WALL, LOWER BELOW PDQ (SINGLE VENTED DOOR) A radio cabinet with a vented, hinged aluminum door, secured by a chrome locking lever latch, located on the front lower left wall, door to open towards rear of the module.	1.00	Included
IF4XL1OP4	CABINET - HINGED POLYCARBONATE DOORS WITH CENTER SQUEEZE LATCHES, PASS-THROUGH WINDOW OPEN TO THE CAB Window opening, pass-through from cab to module. A cabinet with hinged polycarbonate doors located below window opening. The cabinet to have oen (1) adjustable shelf.	1.00	1,336.00
IF-CNT-ACR	COUNTER TOP, SOLID ACRYLIC Install: solid acrylic countertop with a 1/2" lip in the pass-through opening.	1.00	1,111.00
50-20-0507	PASS THROUGH - CAB TO MODULE, WINDOW OPENING A window opening: provided in the rear of the cab to accommodate pass-through communications to the patient compartment, bellows provided to connect the cab to the module.	1.00	Included



50-50-0118	----- SEATING - ATTENDANT - USSC VALOR R - BACK INTEGRAL CHILD, SWIVEL SEAT CN8 COMPLIANT A USSC Valor rear facing, R-back attendant seat with an integrated child seat installed at the head of the patient cot: a (2) position swivel seat mounted on a pedestal base with a heavy-duty seat frame / ABTS (All Belts To Seat) application with (4) point / (4) retractors single click internal mount belt system. The seat shall be padded and covered with sewn matching vinyl upholstery. -----	1.00	3,020.00
50-50-0121	----- SEATING - ATTENDANT - CENTERED WITH COT Attendant seat to be centered with cot per dwg #9 -----	1.00	369.00
50-50-0333	----- CPR SEAT STORAGE AREA, BELOW SEAT - W/HINGED SEAT BOTTOM The bottom seat cushion shall be hinged with a storage area located below. The interior of the storage area shall be sprayed with sound absorbing polyurethane material. An automatic latching fastener shall be installed to secure the CPR seat lid in the closed position. -----	1.00	878.00
CPROP4	----- SEATING - CPR - EVS WITH BACKPACK HARNESS A CPR seat shall be installed on the street side of the patient compartment aft of the primary action area counter. The CPR seat shall be KKK-A-1822F Change Notice 8 compliant with the Backpack style shoulder / seat belt system and conform to all applicable FMVSS and SAE J3026 requirements. -----	1.00	1,350.00
SQSTOP7	----- SEATING - CN8 COMPLIANT TWO (2) EVS BACKPACK A Squad bench seat: (2) EVS individual seating positions will be installed on the curb side of the patient compartment. Seats shall have the EVS Backpack Belting system and be covered with color coordinated, cut and sewn vinyl. -----	1.00	2,407.00
50-41-0408	----- HEAT/AIR CONDITIONING, PROAIR IW-3856 CD CENTER DUCTED - 700 CFM (56,000 BTU HEAT / 38,000 BTU COOL) BRUSHLESS BLOWER -----	1.00	2,370.00
COND_HSL_01	----- HVAC - SINGLE COIL CONDENSER - 24,000 BTU A single coil condenser, 24,000 BTU Low Profile, shall be installed on the front of the module. The condenser shall be top center mounted with mounting brackets. Condenser and brackets are to be painted to match the module. -----	1.00	2,021.00
COND_BRK_01	----- CONDENSER BRACKET TO BE FLAT DESIGN AND COLOR -----	1.00	Included



	MATCH TO THE CONDENSER The condenser bracket shall be a flat designed, painted to match the condenser, mounted to the bulkhead of the module.		
50-60-0730	DOOR PANELS - MODULE PASSAGE DOORS - FULL LENGTH ALUMINUM - W/ACCESS PANELS Interior rear and curbside passage door panels to be full length aluminum, Multi-Spec sprayed to match interior color and contain removable latch access panel per dwg. # 6 & # 8. (Total 3).	1.00	Included
50-60-0256	EXHAUST VENTILATOR, 3-SPEED - MULTIPLEX ELECTRIC SYSTEM Install: three-speed, 250 CFM (minimum) exhaust fan in the street side cabinet in the patient compartment, fan pulse width modulated from a switch on the attendant control panel vista screen, exhaust system to have a louvered grille inside and a chrome vent outside, system vent through the side of the vehicle, not through the roof.	1.00	Included
50-60-0325	NO - GLOVE, DISPENSER - CURBSIDE ABOVE DOOR Delete the glove box (3) dispenser above the curbside door.	1.00	Included
50-60-0332	GLOVE DISPENSER - (1) BOX - EACH REAR DOOR - TOTAL TWO (2) A single box glove dispenser unit, with a clear acrylic hinged access panel with cut-out, shall be recessed on the rear passage doors, one each door per dwg #8.	1.00	600.00
50-60-0351	GRAB RAILS, 1-1/4" DIAMETER, (96") OVER COT & (64") SQ BENCH Install 64" stainless steel grab rail over the squad bench area.	1.00	Included
50-60-0431	IV HANGERS - CEILING RECESSED - CAST PRODUCTS #IV2008-1 (2) Two (2) Cast Products #IV2008-1 recessed; dual ceiling I.V. hangers shall be provided per Dwg #9 locations.	2.00	Included
50-60-1640	OXYGEN OUTLET (1) RIGHT WALL - OHIO MED - HEAD END OF SEATING AREA One (1) Ohio Medical flush mounted; quick release wall outlet shall be installed in the right wall above the head end of the curbside seating area. Per dwg #6	1.00	Included
50-60-0629	FLOW METER, OXYGEN - THORPE STYLE One (1) Thorpe style oxygen flow meter (15LPM) shipped loose with the completed vehicle.	1.00	Included



50-60-0286	OXYGEN - ZICO QR-D-2 PORTABLE OXYGEN STORAGE BRACKETS TWO (2) RECESSED INTO HEAD OF SQUAD BENCH Two (2) Zico #QR-D-2 storage brackets for "D" oxygen cylinders, shall be recessed and installed into the forward end of the squad bench and accessible from the curbside stepwell.	1.00	1,521.00
------------	---	------	----------

Braun - Optional Patient Compartment Items

Item Number	Name	Quantity	Price
SR00137438	OTE 19507A CLIMATE CONTROLLED CABINET-TEMPERATURE CONTROL MODULE Install: 12-volt OTE key locking climate controlled cabinet at the action area counter, with an exterior vent.	1.00	3,619.00
SR00137450	STAINLESS STEEL WALL PROTECTION - INTERIOR CURBSIDE: A brushed stainless steel panel shall be provided on the street side wall 6" from the Floor.	1.00	Included
SR00137452	AISLE LIGHTING Install Ridgeback strip lights in a aluminum channel under the stainless steel wall protectors on the street side and the curb side.	1.00	1,340.00
SR00137461	CODE 3 VITAL VIO DECONTAMINATION SYSTEM PCL-LED-VV PATIENT LIGHT VV, 48LED, 12-24VDC (BARE LEADS) Install (3) Code 3 Vital Vio Antimicrobial Light Disinfection units in module headliner.	1.00	2,184.00
DECON-EVER-01	EVERGREEN LUMALIER UV ADU-136-PB DECONTAMINATION SYSTEM Install an Evergreen Lumalier Decontamination UV-C system per drawings.	1.00	3,583.00
50-62-0446	COT FASTENER - STRYKER FLOOR PLATE AND 12v PRE-WIRE FOR CUSTOMER FUTURE INSTALL OF A POWER OR PERFORMANCE COT LOAD SYSTEM Install Stryker Floor plate kit and 12v pre-wire for Customer supplied / Customer installed Stryker Performance or Power Load Cot	1.00	Included
30-10-0502	LIGHTS, INTERIOR - WHELEN MINI LED BRAKE/TURN REAR HEADPAD Install: Whelen Mini-LED turn signal and brake light on rear headpad above the rear doors (amber / red / amber).	1.00	240.00

Braun - Paint / Graphics



<i>Item Number</i>	<i>Name</i>	<i>Quantity</i>	<i>Price</i>
60-01-0001	PAINT PROCEDURE All non-anodized aluminum module body surfaces: completely chemically steam cleaned, filled with premium body filler as needed, sanded smooth and primed with an epoxy primer and then primed again with a high solid primer, cured primer surfacer shall be DA sanded with 320 grit and cleaned. A high solid primer shall then be applied, where needed, as a sealer. -----	1.00	Included
60-01-0005	STANDARDS AND SPECIFICATIONS FOR VEHICLE PAINT APPEARANCE Adhere to Standards and Specifications for Vehicle Paint Appearance. -----	1.00	Included
60-10-0108	CAB - OEM PAINT FORD OEM RACE RED -----	1.00	Included
60-01-0004	BUFFING, PAINT - MODULE The paint on the module sides shall be buffed to a high shine using a recommended paint buff system. -----	1.00	Included
60-09-0101	PAINT MOD ALL ONE SOLID COLOR, PLUS CLEAR COAT FORD OEM RACE RED The entire module shall be sprayed one-color and then clear coated. -----	1.00	Included
60-30-0200	REFLECTIVE - DOOR REFLECTIVITY Install reflective material (25" x 2.5" red/silver chevron style), on the lower interior stainless steel panel of each rear door and hinged side door. NOTE: If a sliding side door is provided, install a 1.50" x 40.00" white reflective stripe on the rear facing edge. -----	1.00	Included
60-25-0101	REFLECTIVE - BLACK MATERIAL IN RUB RAILS Install black reflective material in rub rails. -----	1.00	Included

Braun - Vehicle Manuals

<i>Item Number</i>	<i>Name</i>	<i>Quantity</i>	<i>Price</i>
80-20-0001	VEHICLE MANUALS (1) PACKAGE SET One (1) Delivery Manual Package shall be supplied with the vehicle, and shall include the following items: Ambulance manufacturer parts, service, and operation manuals, OEM chassis owner's guide, complete 12 VDC and 125 VAC wiring schematics for all included standard and optional systems, Multiplex Electrical system programming - electronic media -----	1.00	Included
90-10-0007	STATEMENT OF LIMITED WARRANTY NEW AMBULANCES	1.00	Included



DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE

OVERALL HEIGHT = 114"

OVERALL WIDTH WITH RUB

RAILS & FENDERETTES = 98"

WHELEN 700 CLEAR LED LIGHT WITH A PIONEER
PCH1 COMBINATION SPOT/FLOODLIGHT IN A PBH103
RECESSED HOUSING POINTING STRAIGHT OUT

(5) TECNIQ S330 AMBER
MINI-LED MARKER LIGHTS

(2) WHELEN 600 RED
ROTA-BEAM LED LIGHTS

NOTE: MODULE TO HAVE
74" HEADROOM AND BE
173" IN LENGTH.

LOCKING, SLIDING
WINDOW IN CAB

OEM POWER
ADJUSTABLE
MIRRORS

FLASHING HEADLIGHTS W/
DAYTIME RUNNING LIGHTS

BUCKSTOP OUTBACK
BUMPER/GRILLE GUARD

2" LED RUNNING
BOARD LIGHTS

BUELL AIR HORNS

(4) WHELEN 900 RED
LED LIGHTS WITH
CLEAR LENSES

HOSELINE TMC2007 CONDENSER
WITH (4) WHELEN 700
LED SCENE LIGHTS

(2) CODE 3 VITAL
VIO UV LIGHTS IN
THE CAB HEADLINER
(LOCATION MAY VARY)

(4) WHELEN 500 SERIES
SUPER LED GRILLE
LIGHTS WITH CLEAR LENSES:
LEFT - RED/RIGHT - WHITE

HIDDEN UNLOCK SWITCH
IN GRILLE AREA

CAST PRODUCTS RECESSED
100-WATT SIREN SPEAKERS.
CONNECTED TO PRIMARY
SIREN CONTROL.

-CHASSIS TO BE 4x4-

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.

PERRYSBURG F.D.



FRONT EXTERIOR VIEW
CHIEF XL-I/F550 CHASSIS


DATE:
1-16-23
DWG. TKD
REV. A

DRAWING NO.
CPQ# 6907
PFD-1

APPROVAL SIGNATURE:

DATE:

DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE
 OVERALL HEIGHT = 114"
 OVERALL WIDTH WITH RUB
 RAILS & FENDERETTES = 98"



THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



REAR EXTERIOR VIEW
 CHIEF XL-1/F550 CHASSIS

DATE: 8-25-22	DRAWING NO. CPQ# 6907
DWG. BT	REV. NR PFD-2

DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE
 OVERALL HEIGHT = 114"
 OVERALL LENGTH = 311"
 MODULE LENGTH = 173"



COMPARTMENT
O.S.S #1

CLEAR OPENING: 77.00h x 18.25w
 INSIDE DIM'S.: 86.75h x 24.50w x 20.75d
 'EZ-02 LIFT' SYSTEM ON THE DOOR
 (1) FIXED SHELF ABOVE EZ O2 LIFT THAT SEALS TO INSIDE OF DOOR.
 INVERTER, AIR HORN COMPRESSOR AND MISC LOCATED ABOVE SHELF
 AREA ABOVE SHELF TO BE VENTED THROUGH DOOR
 AREA ABOVE TO HAVE SOUND DEADENING MATERIAL

O.S.S #2

CLEAR OPENING: 44.25h x 43.00w
 INSIDE DIM'S.: 47.75h x 49.00w x 20.75d
 (2) ADJUSTABLE SHELF

O.S.S #3

CLEAR OPENING: 63.375h x 33.00w
 INSIDE DIM'S.: 65.25h x 38.50w x 20.75d
 UPPER AREA SHALLOW DEPTH; LOWER 36" FULL DEPTH
 (2) SCBA BRACKETS ON SHALLOW DEPTH WALL MOUNTED ON 6" WIDE TAPPING PLATE
 (1) ADJUSTABLE SHELF-FULL DEPTH LOWER DOORS TO OPEN AS WIDE AS POSSIBLE USING GAS SHOCK

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.

PERRYSBURG F.D.



STREETSIDE EXTERIOR VIEW
 CHIEF XL-I/F550 CHASSIS

DATE:
1-16-23
DWG. TKD
REV. A


DRAWING NO.
CPQ# 6907
PFD-3

DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE

OVERALL HEIGHT = 114"

OVERALL LENGTH = 311"

MODULE LENGTH = 173"



COMPARTMENT

O.S.S #4

CLEAR OPENING: 73.00h x 13.25w
 INSIDE DIM'S: 82.75h x 17.00w x 20.75d
 FIXED DIVIDER 10" FROM FORWARD WALL
 (2) BACKBOARDS REAR OF DIVIDER
 (2) ADJ. SHELVES FORWARD OF DIVIDER

O.S.S #4A

CLEAR OPENING: 26.00h x 16.50w
 INSIDE DIMS: 29.00h x 23.00w x 20.75d
 MISC. STORAGE COMPARTMENT

O.S.S #5

CLEAR OPENING: 69.50h x 17.50w
 INSIDE DIM'S. 5A: SEE PARTITION INTERIOR VIEW
 INSIDE/OUTSIDE STORAGE WITH (3) ADJUSTABLE SHELVES

INSIDE DIM'S. 5B: 19.00h x 20.75w x 18.00d

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



CURBSIDE EXTERIOR VIEW
 CHIEF XL-I/F550 CHASSIS

DATE: 1-17-23
 DWG. TGD
 REV. A

DRAWING NO. CPQ# 6907
 PFD-4



COMPARTMENT

#1 DOOR OPENING: 16.25h x 20.75w
 INSIDE DIMS: 17.00h x 22.50w x 17.25d
 FIXED SHELF WITH TOP/BOTTOM DIVIDERS
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#2 DOOR OPENING: 16.25h x 30.25w
 INSIDE DIMS: 17.00h x 32.00w x 17.25d
 FIXED SHELF WITH TOP/BOTTOM DIVIDERS
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#2A DOOR OPENING: 16.25h x 30.25w
 INSIDE DIMS: 17.00h x 32.00w x 17.25d
 FIXED SHELF WITH TOP/BOTTOM DIVIDERS
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#3 DOOR OPENING: 26.68h x 32.87w
 INSIDE DIMS: 28.43h x 34.62w x 7.50d
 FIXED SHELF (6) ADJ. DIVIDERS TOP/BOTTOM
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#5 - (2) PULL-OUT DRAWERS
 INSIDE DIMS: 3.50h x 14.00w x 11.50d
 FRONT-TO-BACK DIVIDERS IN EACH DRAWER
 LOCKING STAINLESS STEEL FLUSH PULL LATCHES
 TOTAL DRAWER WEIGHT RATING = 10 lbs. EACH

#6 DOOR OPENING: 4.75h x 30.25w
 INSIDE DIMS: 4.75h x 30.25w x 17.25d
 POLY DOOR WITH FRICTION HINGES
 CENTER SQUEEZE LATCH
 TOTAL CABINET WEIGHT RATING = 10 lbs.

#7 PULL-OUT SHARPS/WASTE DRAWER
 5-QUART TRASH / 1.5 QUART SHARPS
 DISPOSAL THROUGH COUNTERTOP
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 TOTAL DRAWER WEIGHT RATING = 10 lbs.

CABINETS #1, #2, AND #2A TO HAVE LIFT-UP
 RESTOCKING FRAMES
 CABINETS WITH INVENTORY CONTROL SYSTEM
 SOLID ACRYLIC COUNTERTOPS
 CABINETS TO BE ALUMINUM

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



STREETSIDE INTERIOR VIEW
 CHIEF XL-I

DATE:
 1-17-23
 DWG. REV.
 TKD A

DRAWING NO.
 CPQ# 6907
 PFD-5



COMPARTMENT

#1/#2 DOOR OPENING: 8.25h x 37.75w
 INSIDE DIMS: 6.75h x 37.75w x 10.25d
 ADJUSTABLE DIVIDERS IN EACH CABINET
 HINGED POLY DOORS WITH HOLD-OPENS
 CENTER SQUEEZE LATCHES
 43" MINIMUM HEADROOM BELOW THE CABINET
 TOTAL CABINET WEIGHT RATING = 10 lbs. EACH

#3 INSIDE DIM'S: 14.25h x 45.00w x 21.00d

#4 CABINET WITH SOLID ACRYLIC COUNTERTOP
 PULL-OUT DRAWER TOWARDS THE BENCH
 FRONT-TO-BACK DIVIDERS WITHIN
 INSIDE DIMS: 4.00h x 10.00w x 13.00d
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 TOTAL DRAWER WEIGHT RATING = 10 lbs.
 NOTCH BELOW DRAWER FOR SHARPS/WASTE DISPOSAL

#5 CABINET WITH SOLID ACRYLIC COUNTERTOP
 PULL-OUT DRAWER TOWARDS THE BENCH
 FRONT-TO-BACK DIVIDERS WITHIN
 INSIDE DIMS: 4.00h x 10.00w x 10.00d
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 DRAWER DOES NOT COMPLY WITH CN10

#6 PULL-OUT SHARPS/WASTE DRAWER TOWARDS THE AISLE
 8-qt. WASTE / 3.3-qt. SHARPS
 SHARPS/WASTE DROP FROM TOP WITH HINGED ACRYLIC
 LID. DRAWER OPENS TO ACCESS CONTAINERS.
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 TOTAL DRAWER WEIGHT RATING = 10 lbs.

SOLID ACRYLIC COUNTERTOPS
 CABINETS WITH INVENTORY CONTROL SYSTEM
 CABINETS TO BE ALUMINUM

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



CURBSIDE INTERIOR VIEW
 CHIEF XL-1

DATE: 1-17-23
 DWG. TKD
 REV. A

DRAWING NO. CPQ# 6907
 PFD-6



PERRYSBURG F.D.




PARTITION INTERIOR VIEW
CHIEF XL-I

DATE:
1-17-23
DWG.
TKD

REV.
A

DRAWING NO.
CPQ# 6907
PFD-7



THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



REAR INTERIOR VIEW
CHIEF XL-I

DATE:
1-17-23
DWG.
TKD

DRAWING NO.
CPQ# 6907
REV.
A
PFD-8



= (2) RECESSED CEILING IV HANGER LOCATIONS



= (1) CEILING OXYGEN OUTLET

* (2) ANTENNA BASES LOCATED OUTBOARD OF DOME LIGHTS WITH COAX SERVICE LOOP

STRYKER FLOOR PLATE AND 12V PRE-WIRE

MODULE WIDTH = 96"
MODULE LENGTH = 173"
MODULE HEAD ROOM = 74"

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.

PERRYSBURG F.D.



FLOOR INTERIOR VIEW
CHIEF XL-I

DATE:
1-17-23
DWG.
TKD

REV.
A

DRAWING NO.
CPQ# 6907
PFD-9

TO: Mayor Mackin
President Smith
Members of City Council

FROM: Patrick Jones, Director of Public Safety

RE: Resolution 32-2023

DATE: March 1, 2023



Subject Matter/Background

Resolution 32-2023 authorizes the purchase of a new Braun Chief LX, Ford F-550 4x4 diesel chassis ambulance at a purchase price not to exceed \$382,467.00. This emergency vehicle is budgeted for purchase in the 2023 amended budget. Current lead times for this ambulance to be built is up to two years, due to ongoing supply chain issues.

This ambulance will replace a 2014 International ambulance that will be used as a reserve ambulance. The Fire Division is requesting to purchase an emergency vehicle that has a Ford cab and chassis and a Braun box on the back. The dealer is Penn Care, therefore, the dealer is the contractor in the legislation. Pricing for this ambulance is under Ohio State Term pricing contract 009362.

This resolution was approved by the Safety Committee 3-0 to forward to City Council.

Financial Review

The funds are available in line item 4403.21233.55600, with the passage of the amended budget.

Recommendation

If City Council is in agreement, a motion to suspend the three readings, waive the rules, and authorize this Resolution as an Emergency is recommended.

RESOLUTION 32-2023

A RESOLUTION AUTHORIZING A PURCHASE AGREEMENT WITH PENN CARE NOT TO EXCEED THREE HUNDRED EIGHTY- TWO THOUSAND, FOUR HUNDRED SIXTY-SEVEN DOLLARS (\$382,467.00) FOR THE PURCHASE OF A BRAUN CHIEF XL, FORD F-550 4X4 DIESEL CHASSIS AMBULANCE FOR THE PERRYSBURG FIRE DIVISION AND DECLARING AN EMERGENCY

WHEREAS, it is necessary for the safety and security of the City of Perrysburg that the City of Perrysburg Fire Division have the necessary equipment to respond to medical emergencies,

WHEREAS, a replacement emergency vehicle is necessary at this time to enable the City of Perrysburg Fire Division to respond efficiently to medical emergencies; and,

WHEREAS, this emergency vehicle would replace a 2014 International ambulance that would be dedicated as a reserve ambulance; and,

WHEREAS, at their February 28, 2023 meeting, the Safety Committee voted 3-0 to advance this resolution to City Council.

NOW, THEREFORE, BE IT RESOLVED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. The Mayor and Director of Finance are authorized to enter into an agreement with Penn Care to purchase a Braun Chief XL, Ford F-550 4x4 diesel chassis ambulance at a cost not to exceed Three Hundred Eighty-Two Thousand, Four-Hundred Sixty-Seven Dollars (\$382,467.00) in accordance with the proposal attached hereto as Exhibit A.

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Resolution were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Resolution is hereby declared to be an emergency measure necessary for the immediate preservation of the public peace, health and safety of the citizens of the City of Perrysburg, Wood County, Ohio, in order to allow for the immediate purchase of the emergency vehicle for the safety of the City of Perrysburg,

and shall be in full force and effect from and immediately after its passage and approval by the Mayor.

President of Council

Mayor

PASSED _____

ATTEST: _____

APPROVED: _____



Exhibit A

Emergency Vehicle Purchase Agreement February 2, 23

Purchaser:

City of Perrysburg
26100 Fort Meigs Rd.
Perrysburg, OH 43551

Seller:

Penn Care, Inc.
1317 North Rd.
Niles, OH 44446

The City of Perrysburg intends to purchase (1) Braun Chief XL on the Ford F-550 4x4 Diesel Chassis, as designed per the attached specifications, and when applicable, technical drawings, graphic design and other required documents. Additions, deletions and/or changes must be approved by all parties in writing and may cause delays in deliveries and additional charges to the purchaser.

PRICING

Ambulance Conversion:	\$308,991.00
Chassis Price (Estimate Only):	\$73,476.00
Graphics:	None
Additional Equipment:	None
FIN Rebate (Estimate Only):	TBD
Total Per Due at Delivery:	\$382,467.00

CHASSIS AVAILABILITY, PRICING, AND MANUFACTURES INCENTIVE:

Chassis year, price and manufactures incentives are priced as budgetary estimations ONLY and will not be finalized until the chassis arrives at the ambulance manufacturing facilities.

DELIVERY TIMES

Quoted lead times and delivery expectations quoted by Penn Care, Inc. are approximate and not guaranteed. Quoted lead times will be extended for Change Orders, delays from the chassis OEM and Force Majeure.

TRADE DESCRIPTION:

TRADE-IN TERMS AND APPRAISAL

Where Purchaser wishes to trade-in a used motor vehicle as part of the consideration for the motor vehicle ordered, Seller may appraise the trade-in at the time of the execution of this order by Purchaser. Seller also reserves the right to reappraise the trade-in at the time of delivery. The seller shall not alter a Trade-In appraisal from the time of the initial appraisal until the time of delivery unless:



- 1) Intervening factors indicate an apparent decrease in the value of the value of the trade-in over and above ordinary wear and tear
- 2) A change occurs in the mechanical performance of the vehicle
- 3) Emergency, medical, and/or other equipment/components have been removed that were not previously discussed and agreed to in writing
- 4) The Seller has made any misrepresentation of the vehicle and/or components to Penn Care, Inc.

WARRANTY

No representation has been made by Penn Care, Inc., except as herein stated and no warranties, expressed or implied, may arise except from this writing. All warranties are issued by the chassis manufacturer, the ambulance builder, and/or component parts suppliers and Penn Care, Inc. shall have no liability with respect to warranties issued by the chassis manufacturer, the ambulance builder, and component parts suppliers. Used vehicles are "as is" and have no warranty.

INVOICING AND PAYMENT

Unless otherwise agreed to in writing, Penn Care, Inc. will invoice the Purchaser 30 days prior to the scheduled delivery date. Upon completion of production and quality inspection by the Purchaser the vehicle is declared ready for delivery and payment will be due upon acceptance and/or delivery.

PAYMENT OF SALES AND USE TAXES

The price for the motor vehicle specified in this agreement does not include Sales Taxes and Use Taxes (Federal, State, or Local) unless expressly stated. Purchaser assumes and agrees to pay, unless prohibited by law, and such Sales, Use, or Occupational Taxes imposed on or applicable to the transaction covered by this agreement, regardless of which party may have primary tax liability.

ACCEPTANCE

When requesting a final inspection the Purchaser shall inspect the vehicle(s) within 10-days of notification of completion of production. Vehicles not inspected by buyer will be deemed complete and ready for delivery, and payment will be due upon delivery. Items and issues discovered after the 10-day window shall not hold up payment from buyer to Penn Care Inc., these issues will be handled as warranty claims following the normal procedures.

PAYMENT AND TITLE

All payments shall be made in U.S. dollars either by certified check or wire transfers, credit card payments are not acceptable without prior written authorization (fees will apply). Payment terms are COD, unless otherwise agreed to in writing by Penn Care, Inc. Interest terms begin 16-days from date of delivery and are charged at a rate of prime plus 6%. MSO and title are released to Purchaser upon payment in full, including any related interest, shipping expenses, and other related costs and expenses to Penn Care Inc. or to the appointed floor plan financing company.

As collateral security for the payment of the purchase price of the Vehicles, Buyer hereby grants to Penn Care Inc., a lien on and security interest in and to all of the right, title, and interest of Purchaser in, to, and under the Vehicles, wherever located, and whether now existing or hereafter arising or acquired from time to time, and in all accessions thereto and replacements or modifications thereof, as well as all proceeds, including insurance proceeds, of the foregoing. The security interest granted under this provision constitutes a purchase money security interest under the Ohio Uniform Commercial Code.

CANCELLATION

Penn Care, Inc., may, in its sole discretion, and without liability or penalty, cancel this order at its sole discretion. Once Penn Care's manufactures commence engineering, no cancellation of this order is permitted, and the full purchase price is due and payable to Penn Care, Inc. Notwithstanding other provisions of this Agreement, and in addition thereto, Penn Care, Inc. shall be entitled to its reasonable and anticipated lost profit from such cancellation.

FORCE MAJEURE

Penn Care, Inc. shall not be liable or responsible to Purchaser, nor be deemed to have defaulted or breached these Terms and Conditions, for any failure or delay in fulfilling or performing any of these Terms and Conditions when and to the extent such failure or delay is caused by or results from acts or circumstances beyond the reasonable control of Penn Care, Inc., and/or the manufactures which Penn Care, Inc. represents including, without limitation, acts of God, flood, fire, earthquake, explosion, governmental actions, war, invasion or hostilities, terrorist threats or acts, riot or other civil unrest, national emergency, revolution, insurrection, epidemic, lockouts, strikes or other labor disputes (whether or not relating to either party's workforce), restraints or delays affecting carriers, inability or delay in obtaining supplies of adequate or suitable materials, or telecommunication breakdown, or power outage.

DEFAULT/ATTORNEY'S FEES

Purchaser is in default of the Terms and Conditions if any of the following occurs (except as prohibited by law): (i) Purchaser fails to perform any obligation that Purchaser has undertaken in these Terms and Conditions; or (ii) Penn Care, Inc., in good faith, believes that Purchaser cannot, or will not, pay or perform the obligations it has agreed to in the Terms and Conditions.



If Purchaser defaults, or in the event Penn Care, Inc. brings an action or proceeding to enforce the terms hereof or declare rights hereunder, Purchaser agrees to pay Penn Care, Inc. costs for collecting amounts owing, including, without limitation, court costs, attorney's fees (for attorneys who are not our salaried employees), and fees for repossession, repair, storage, and sale of Vehicles, all without relief from valuation and appraisal laws.

GOVERNING LAW

All of terms and provisions of the agreement and the rights and obligations of the parties hereto shall be interpreted and enforced in accordance with the laws of the State of Ohio.

REMEDIES

If Purchaser is in default of these Terms and Conditions, Penn Care, Inc. shall have all the remedies provided by law in these Terms and Conditions: (i) Penn Care, Inc. may require Purchaser to immediately pay Penn Care, Inc., subject to any refund required by law, the remaining unpaid balance due; (ii) Penn Care, Inc. may require Purchaser to make the Vehicle available to Penn Care, Inc. at a designated place that is reasonably convenient to each party; (iii) Penn Care, Inc. may immediately take possession of the Vehicle by legal process or self-help, but in doing so Penn Care, Inc. may not breach the peace or unlawfully enter onto Purchaser's premises; (iv) Penn Care, Inc. may then sell the Vehicle and apply what it receives as provided by law to Penn Care, Inc. reasonable expenses and then toward Purchaser's obligations; and (v) Except when prohibited by law, Penn Care, Inc. may sue Purchaser for additional amounts if the proceeds of a sale do not pay all of the amounts Purchaser owes to Penn Care, Inc. By choosing any one or more of these remedies, Penn Care, Inc. does not waive its right to use another remedy. By deciding not to use any remedy, Penn Care, Inc. does not give up its right to consider the event a default if it happens again.

PURCHASER

Signature: _____

Name/Title: _____

Date: _____



Quotation Summary

Travis Krieger 2 Braun Proposals 2023-02-02 15-07-20

Reference: QUO0000006907 **Rev:** 2
Purchaser: Penn Care
Contact: Taylor Pease
Address: 1317 North Road
Niles, OH

Opportunity: Perrysburg FD
Account: Perrysburg FD
Contact: Joel Whitmore
Shipping Address:

Telephone:

Currency: USD
Quotation Date: 2023-01-31
Expiration: 2023-03-02

Sales Contact: Travis Krieger
Mobile: 330-696-3066
Phone: 330-696-3066

Factory Contact: Kris Turner
Mobile:

Name	Specifications
Chief XL Type I	-72" Headroom -169"L Full Seam Welded Module



Product	Description	Quantity	Unit Net	Total Net
CHFSLI	173" long x 96" wide module with 74" headroom.	1.00	\$382,467.00	\$382,467.00

Price Details	Price
Chassis	73,476.00
Base and options	242,537.00
Custom Options	66,454.00
List Price Per Unit	\$382,467.00

**** Product quotes are valid for 30 calendar days. After 30 calendar days quotes are subject to change. Any applicable discounts will be added and validated at time of invoice. Discounts subject to change.**

Payment Terms:

FORCE MAJEURE "Company shall not be liable or responsible to Purchaser, or be deemed to have defaulted or breached these Standard Terms and Conditions, for any failure or delay in fulfilling or performing any of these Standard Terms and Conditions when and to the extent such failure or delay is caused by or results from acts or circumstances beyond the reasonable control of Company including, without limitation, acts of God, flood, fire, earthquake, explosion, governmental actions, war, invasion or hostilities, terrorist threats or acts, riot or other civil unrest, national emergency, revolution, insurrection, epidemic/pandemic, telecommunication breakdown, power outage, lockouts, strikes or other labor disputes (whether or not relating to either party's workforce), restraints or delays affecting carriers, inability or delay in obtaining chassis from an original equipment manufacturer or other supplies of adequate or suitable components or materials at reasonable prices."



Sales Options by Category

Braun - KKK Change Notice

Item Number	Name	Quantity	Price
00-01-0001	GENERAL CONDITIONS	1.00	Included
00-01-0006	DYNAMIC SIDE IMPACT & ROLLOVER TESTS	1.00	Included
00-01-0017	BIDDER IS KKK-A-1822F AMENDMENT 1 COMPLIANT	1.00	Included
80-10-0000	KKK-A-1822F COMPLIANCE PACKAGE KKK-A-1822F compliance sticker, electrical load analysis sticker, and payload sticker shall be installed in the oxygen compartment. Any deviations from KKK-A-1822F shall be listed in the vehicle delivery packet with a notation on the-compliance sticker.	1.00	Included
00-01-0029	NO CONTRACT REQUIRED NO STS, HGAC, FSA, SOURCEWELL or GPO contract required	1.00	Included
00-01-0072	100% PREPAY Purchaser will prepay 100% of total price.	1.00	Included

Braun - Chassis

Item Number	Name	Quantity	Price
SR00137422	AIR HORNS - BUELL DUAL TRUMPETS 10" and 12" THRU BUMPER W/ LANYRD Air Horn - (Buell) dual trumpets, one (1) 10" and one (1) 12", mounted thru front bumper, one each side, compressor per drawing. The air horns shall be activated by a push button located on the MCC (master control console) and by a lanyard cable installed in the OEM cab headliner area, unless otherwise stated	1.00	2,170.00
SR00137427	CUSTOMER SUPPLIED SECURE 3 KEY KNOX BOX-MCC: Braun is to install a customer supplied secure 3 key Knox Box (08796-2) to the cab console. Per console layout.	1.00	418.00
SR00137434	CODE 3 VITAL VIO DECONTAMINATION SYSTEM PCL-LED-VV PATIENT LIGHT VV, 48LED, 12-24VDC (BARE LEADS) Install (2) Code 3 Vital Vio Antimicrobial Light Disinfection units in cab Headliner.	1.00	1,267.00



SR00137455	PASS THROUGH - CAB TO MODULE, LOCKABLE SLIDING WINDOW Install: A lockable sliding window in the cab over the pass thru opening to the module.	1.00	Included
SR00137472	SIREN SPEAKERS, CAST PRODUCTS - IN FRONT BUMPER Two (2) Cast Products - 100-watt siren speakers, shall be installed in the the front bumper.	1.00	Included
SR00141249	CHIEF XL I AMBULANCE MODULE MY2025 Type I - Ambulance - Chief XL I Ford - 173" module length with 74" headroom. Manufactured in Van Wert, Ohio, USA	1.00	Included
SR00152318	BUMPER/GRILLE GUARD BUCKSTOP Install a Buckstop Outback Bumper/Grille Guard, Black	1.00	4,699.00
CH_F4550L	CHASSIS - FORD F550 193" WB 4X4 DRW (108 C.A.) DIESEL ENGINE FORD F550 CHASSIS CAB, 193" WB 4X4 DRW (108" C.A.)	1.00	Included
15-00-0010	FUEL TANK - FULL UPON FACTORY RELEASE The chassis fuel tank of the completed unit shall be full at time of release from the ambulance manufacturer's facility.	1.00	Included
20-10-0603	ENGINE BLOCK HEATER - OEM PLUG An engine block heater shall be included in the chassis with the 125 VAC power cord.	1.00	Included
20-20-0252	HEAT SHIELDS, PROTECTIVE Install: aluminized steel protective heat shields to the upper laterals above the exhaust system.	1.00	Included
20-20-0277	HIGH IDLE SYSTEM, AUTOMATIC A high-idle module will be added to the chassis. The high idle will be engaged automatically by the M-Tech system when all chassis parameters are met. Chassis parameters include but not limited to vehicle in park, service brake not depressed, accelerator not depressed, parking brake set. High-idle is also activated by the M-Tech heat or A/C.	1.00	Included
20-01-0105	SUSPENSION - LIQUID SPRING TYPE I Install: Liquid Spring	1.00	Included
20-10-0206	BATTERY - TWO SYSTEM - F SERIES CHASSIS	1.00	Included



	The vehicle shall have a 12 V two (2) battery system rated at 1500 cold cranking amps. Both batteries shall be securely installed in the Ford OEM locations, under the vehicle hood.		
20-21-0101	FLOOR CONSOLE F450/F550 STANDARD CONSOLE - ALUMINUM PLEASE NOTE: Console drawings are for reference only and do not include all features depicted on the drawings. All consoles shall be designed, priced, and approved internally to allow for accurate BOM pricing. The prices shown are estimated for general budget pricing only and pricing is subject to design; must contact manufacturer for pricing validation.	1.00	Included
20-10-0112	INBOARD ARM RESTS FOR ALUMINUM CONSOLE Install: inboard arm rests in the cab. (arm rests Havis Shields C-ARM-102 mount to the aluminum floor console)	1.00	Included
30-10-0030	BACKUP ALARM Install: (OSHA approved) back up alarm with a disable control for silent backing, located on the MCC (master control console).	1.00	Included
20-30-0806	RUNNING BOARDS - STAR PUNCHED DIAMOND PLATE Aluminum diamond plate running boards with a star punched non-skid surface shall be provided on the cab. The running boards shall be dip anodized after they are formed to retain finish and increase corrosion resistance.	1.00	Included
40-10-0117	DEF TANK FILL PROTECTOR - STAINLESS STEEL Install: stainless steel DEF tank fill protector per drawing.	1.00	110.00
40-10-0112	FUEL FILL PROTECTOR - STAINLESS STEEL Install: stainless steel fuel fill protector per drawing.	1.00	110.00
30-25-0204	LIGHTS RUNNING BOARD -WHELEN 2 inch round-LED Install: (1) pair of Whelen white TOCACCRR LED lights with black grommets, (1) each side, low on the module front, as running board lights, activated with the cab door switches. per dwg # 1 (Braun part #18105 Light and #18106 Grommet).	1.00	288.00
20-30-0202	MIRRORS, EXT OEM MANUAL TELESCOPNG WREMOTE & HEAT The chassis shall have OEM manual telescoping, folding trailer tow mirrors with power/heated glass, heated convex spotter mirror, integrated clearance lamps/turn signals.	1.00	Included



20-30-0261	OEM AUTO-LOCK DISABLED (cab & module doors do not auto lock or unlock) The OEM auto-lock feature will be disabled.	1.00	Included
20-20-0281	SECURITY SYSTEM - ANTI THEFT- IGNITION OVER RIDE Install Sound Off Ignition security system. (ignition over ride)	1.00	Included
30-10-0753	SIREN, WHELEN 295-HFSA7-REMOTE WITH MICROPHONE (Meets CA Title 13) A Whelen 295-HFSA7 remote dual siren amplifier shall be flush-mounted in the master control console located in the cab. The siren shall be capable of hands-free operation and shall be equipped with a noise canceling microphone. (Meets CA Title 13)	1.00	
20-40-0203	WHEELS, FORGED POLISHED ALUMINUM - 19.5 - F450/550 193" WB Forged, polished aluminum wheels shall be provided, to include bright hub covers and center ornaments and valve stem extensions.	1.00	Included

Braun - Electrical

Item Number	Name	Quantity	Price
SR00154109	LIGHTS, INTERIOR CABINETS, RIDGEBACK 12V LED STRIP LIGHT, BLUE All polycarbonate door(s), interior cabinets shall have Ridgeback 12V blue LED strip lights for interior compartment lighting.	1.00	994.00
SR00137418	OEM AUXILLARY SWITCHES, FLOODLIGHT ACTIVATION External change: Ford OEM aux switches to activate the floodlights. Furthest left switch shall activate the left flood light. The next switch to the right shall activate the middle flood light. The next switch to the right shall activate the right flood light. (SR137444)	1.00	Included
SR00137432	LOCKS POWER - PASSAGE, COMPARTMENTS, KEY FOBS Power door locks on module passage doors, and (6) OSS compartments, use OEM key fobs.	1.00	
SR00137465	OUTLETS, EXTERIOR OSS#3 Outlets Exterior OSS #3: (1)125VAC (1) 12VDC outlets in OSS #3 Upper, Rear Forward Wall.	1.00	218.00
SR00137475	SYSTEM ACTIVE AND CHECK OUT LIGHTS -Standard 15 MINUTES Switch: located at the curb and rear entry doors for activation of the V-MUX electrical system,	1.00	



check out light switch located at the curb and rear doors for activation of the left LED angled lights prior to entering the module, system programmed to shut down automatically after 15 minutes unless the ignition is on.

SR00137479	----- LIGHTS, OSS COMPARTMENTS - RIDGEBACK LED STRIP LIGHTING: Each outside storage compartment Ridgeback LED strip lighting located one each side of the door opening, activated by a magnetic switch, excluding battery compartment. Lengths dependent on OSS dimensions.	1.00	1,190.00
SR00137480	----- FRONT WALL OUTLETS: Install one (1) 125Vac and two (2) 12VDC outlets on the back wall of upper front wall cabinet #1. Install one (1) 125VAC and one (1) 12VDC outlet in the upper corner of front wall cabinet #2. Install one (1) 125VAC and one (1) 12VDC outlet in the upper corner of front wall cabinet #3, per dwg. #7. (7) outlets total for this line only.	1.00	763.00
30-06-0004	----- ELECTRICAL SYSTEM - WELDON V-MUX, MICRO PROCESSOR BASED Install: Weldon V-MUX 100% solid state microprocessor based multiplex system.	1.00	Included
30-10-0110	----- ELECTRICAL CIRCUITS All electrical circuits: shall have wiring and circuit protection suitable to the demand and must meet the national electric code (NEC) wiring requirements, added on wiring (18 GA through 10 GA) color coded and stamped with code numbers for easy identification, SLX high temperature thermoplastic cross link wire used. SGX insulated cable used for all under hood / underbody battery and charging system cable. High temperature (375° f) thermoplastic loom used on all harnesses.	1.00	Included
30-06-0126	----- ELECTRICAL COMPARTMENT (PDQ) - MULTIPLEX ELECTRICAL SYSTEM Electrical compartment / hinged door w/ (2) chrome locking lever latches/ located on the partition wall behind the attendant seat.	1.00	Included
30-06-0325	----- FLASHER - MULTIPLEX ELECTRICAL SYSTEM Provide: Flasher within and programmed by the multiplex electrical system.	1.00	Included
30-06-0350	----- FLASHING HEADLIGHTS - MULTIPLEX ELECTRICAL	1.00	Included



	SYSTEM Headlights (high beams) shall be programmed through the multiplex system to alternate flash (wig-wag). -----		
30-10-0190	GROUND FAULT CIRCUIT INTERRUPTER-GFCI Install: A 125 VAC, 20 AMP circuit breaker with ground fault circuit interrupter (GFCI) electronic ground leakage detection in the load center for the shoreline circuit. -----	1.00	Included
30-06-0285	MODULE DISCONNECT - MULTIPLEX ELECTRICAL SYSTEM Install: In-Power disconnect to keep the system power engaged after the ignition is switched to the "off" position. -----	1.00	Included
30-06-0575	REVERSE -TRANSMISSION- FUNCTIONS - MULTIPLEX ELECTRICAL SYSTEM System programmed to provide activation for: rear outboard warning lights, rear side warning lights, rear scene lights, the rear side scene lights - when the transmission selector lever is placed into "reverse" position. -----	1.00	Included
30-06-0150	SPARE CIRCUIT - MULTIPLEX ELECTRICAL SYSTEM Provide (1) spare 15-amp circuit. -----	1.00	Included
30-06-0175	WIRING HARNESS CONNECTORS - MULTIPLEX ELECTRICAL SYSTEM Connect all wiring harnesses via quick connect circular plug connectors. -----	1.00	Included
30-06-0300	VOLTMETER - MULTIPLEX ELECTRICAL SYSTEM Provide: (1) digital voltmeter on the master control console screen. -----	1.00	Included
30-06-0026	WARNING DISPLAY - MULTIPLEX ELECTRICAL SYSTEM Install: digital warning display integrated into the cab display console, programmed through the multiplex system to provide visual and audible indication. -----	1.00	Included
30-06-0225	EMERGENCY MASTER SWITCH - MULTIPLEX ELECTRICAL SYSTEM Supply: A single emergency master switch for activating all the emergency warning lights on the master control console screen, emergency master switch will activate the module power automatically, include an Emergency Master Menu button to allow access to individual warning light functions. -----	1.00	Included
30-06-0250	CONTROL PANEL SWITCHES - MULTIPLEX ELECTRICAL SYSTEM	1.00	Included



	Switches on the master control console and attendant control panel screens shall have dimmable perimeter backlighting.		
30-06-0275	MODULE POWER SWITCH - MULTIPLEX ELECTRICAL SYSTEM Provide: A module power switch for the electrical system on both the Master Control Console and the Attendant Control Panel screens.	1.00	Included
30-06-0101	ATTENDANT CONTROL PANEL (ACP) - MULTIPLEX ELECTRICAL SYSTEM Attendant Control Panel (ACP) contains a color micro processor screen, controls all equipment installed in the patient compartment.	1.00	Included
30-06-0375	PARK OVERRIDE - MULTIPLEX ELECTRICAL SYSTEM Park override switch on the master control console screen, reactivates all lights disabled when the transmission is placed in the neutral/park position.	1.00	Included
30-06-0400	LOAD MANAGER-SEQUENTIAL SWITCHING SYSTEM - MULTIPLEX ELECTRIC SYSTEM Load manager-sequential switching system controlled by the microprocessor based electrical system: emergency master button shall control the sequential switching of the emergency lights and/or other warning devices, load manager shall automatically shed non-critical electrical loads during low voltage conditions.	1.00	Included
30-06-0450	FRONT CLEAR DISABLE SWITCH - MULTIPLEX ELECTRICAL SYSTEM Activation of the switch on the master control console screen to disable all forward-facing clear warning lights.	1.00	Included
30-06-0076	MASTER CONTROL CONSOLE (MCC) - MULTIPLEX ELECTRICAL SYSTEM Floor mounted Master Control Console (MCC) located in the cab, housing siren, color microprocessor display screen, controlling all the Emergency Warning functions, Patient Compartment lighting and module heat/ac functions.	1.00	Included
30-06-0475	CURBSIDE SCENE LIGHTS ON WITH CURBSIDE DOOR The Curbside scene lights: programmed to activate when the Curbside door is in the open position.	1.00	Included
30-06-0500	REAR SCENE LIGHTS ON WITH REAR DOORS OPEN Rear scene lights programmed to activate when the rear doors are in the open position.	1.00	Included
30-06-0525	DISABLE SWITCH FOR REAR SCENE LIGHTS - MULTIPLEX	1.00	Included



	ELECTRICAL SYSTEM Install: disable switch at the rear door area to disable the rear scene lights.		
30-06-0550	DISABLE SWITCH FOR SIDE SCENE LIGHTS - MULTIPLEX ELECTRICAL SYSTEM A disable switch shall be installed at the curbside door area to disable the curbside scene lights.	1.00	Included
30-06-0010	VISTA IV MCC - PUSH BUTTON Install: Weldon V-MUX Vista IV interface module / display screen in the cab, operated through the use of push buttons.	1.00	Included
30-10-0903	VISTA DISPLAY SCREEN - PUSH BUTTON - CURBSIDE - FIXED ANGLED One (1) Vista screen shall be provided in the patient compartment on the curbside wall on a fixed angled mount with removable plate per the location on dwg. #6.	1.00	1,576.00
30-06-0050	DAYTIME RUNNING LAMPS - MULTIPLEX ELECTRICAL SYSTEM OEM Daytime Running Light headlights activated for daytime operation, when transmission is placed in drive.	1.00	Included
30-10-0073	CAMERA PATIENT AREA SINGLE SYSTEM - VISTA SCREEN Install: camera system to monitor the patient compartment, tied to M-Tech display screen. See Dwg #8	1.00	722.00
30-10-0071	CAMERA REAR VIEW - SINGLE SYSTEM - VISTA SCREEN Install: camera system rear view, tied to M-Tech display screen. Per Dwg #2. Camera alignment will be conducted at final inspection, if applicable.	1.00	Included
30-10-0150	FAN - CIRCULATION INSTALLED IN ELECTRICAL COMPARTMENT Install: Circulation fan in PDQ compartment	1.00	Included
30-10-0585	USB - DUAL OUTLET, ONE (1) INTERIOR LOCATED ON CONSOLE Install: (1) dual USB port outlet, 5 volt / 2.1 amp, in the vehicle, located on the Master Control Console in the cab.	1.00	Included
125ADD	OUTLET, ADDITIONAL-125VAC Cab behind the passenger seat	1.00	109.00



30-10-0258	INVERTER, VANNER - 1100 WATT, LIFESINE LSC 12-1100-DC CHARGER Install: Vanner LifeSine LSC 12-1100-DC watt inverter with battery conditioner / charger per drawing (non-hardwired).	1.00	1,976.00
30-12-0001	RECEPTACLE SHORELINE INLET-SUPER 20 AMP, AUTO EJECT - YELLOW COVER Install: Kussmaul super auto eject shoreline inlet receptacle with yellow cover on module exterior (forward street side) near the driver's door, equipped with an integral dynamic disconnect.	1.00	Included
30-10-0094	SHORELINE INDICATOR LIGHT- ALLIED VCC GREEN MINI NEON - EXTERIOR MOUNTED Install: (1) Allied VCC green mini neon indicator light above the shoreline inlet per drawings. The indicator shall illuminate when shoreline power is present at the inlet.	1.00	Included
30-10-0657	RADIO ANTENNA BASES - TWO (2) Enter antenna information here Two (2) antenna bases with attached coax cables shall be installed on the module roof. The coax cables shall terminate in the PDQ. Access to the antenna bases shall be through adjacent module interior dome lights.	1.00	Included
30-10-0299	LIGHT, ATTENDANT CONTROL PANEL AREA - TECNIQ SILHO-X LED - WARM WHITE A Tecniq Silho-X 2.75" round warm white LED light with SS trim ring, shall be mounted above the left wall forward action area counter. The light shall be operated through a button on the ACP Vista screen labeled "Attendant Light". (Braun #26415)	1.00	Included
30-10-0310	LIGHT, LED ELECTRICAL COMPARTMENT -PDQ A 12 VDC LED light shall be located in the PDQ. The light shall be wired "battery-hot" to activate when the PDQ door is in the open position. The light shall be off when the door is in the closed position.	1.00	Included
30-11-0106	LIGHTS, DOME LED (8) WHELEN SUPER LED Eight (8) Whelen #LED (80C0EHCR) dome lights, shall be installed. See dwg #9	1.00	Included
40-10-0151	SWITCH DOOR UNLOCK, WATERPROOF - HIDDEN IN FRONT GRILLE AREA Install: exterior hidden door unlock switch in grille area.	1.00	Included
30-06-0201	RADIO TIE-IN POINT - (1) 12V/40 AMP - CAB CONSOLE AREA Install (1) set of 12 volt/40 amp radio tie-in studs in cab	1.00	Included



console: (1) battery hot, (1) ignition hot, (1) grounded stud.

30-06-0202	RADIO TIE-IN POINT - (1) 12V/40 AMP - PATIENT COMPARTMENT Install (1) set of 12 volt/40 amp radio tie-in studs in patient compartment: (1) battery hot, (1) ignition hot, (1) grounded stud.	1.00	Included
30-06-0203	RADIO TIE-IN POINT - (1) 12V/250 AMP - PDQ Install (1) set of 12 volt/250 amp radio tie-in studs in the PDQ: (1) battery hot, (1) ignition hot, (1) grounded stud.	1.00	Included

Braun - Exterior Lighting

Item Number	Name	Quantity	Price
SR00137414	LIGHTS -FONT MODULE-(2) WHELEN 600 ROTO-BEAM LED Install two (2) Whelen 600 Roto-beam LED lights on the front of the module, outboard of the warning lights. Per dwg #1	1.00	830.00
SR00137423	LIGHTS, UNDERBODY TECNIQ E10 LED Install: (6) Tecniq E10 white LED lights mounted on brackets underneath the module, turn on automatically when the vehicle is shifted into park, also activated or disabled by a switch on the MCC Vista display screen (Braun #27245).	1.00	946.00
SR00137425	LIGHTS - (4) WHELEN 700 SCENE LIGHTS - CONDENSER Install four (4) Whelen 700 LED scene lights with chrome flanges to the condenser. There shall be two (2) on the front of the condenser and one (1) on each side.	1.00	525.00
SR00137444	LIGHTS, FRONT MODULE FLOOD (1) - WHELEN PIONEER PLUS (PCH2) COMBO- FLOOD & SPOT A Whelen Pioneer Plus LED (PCH1) dual panel combination floodlight with (PBH103) recessed housing shall be installed in the center position. These light shall operate from The OEM switches in the Cab. Furthest Left Switch to activate the Left flood light, the next shall operate the Front and the third switch from the left is to operate the right flood light.	1.00	1,418.00
SR00137451	LIGHTS FRONT MODULE - 4 WHELEN 900 SUPER RED LED Four (4) Whelen 900 series super LED RED warning lights with chrome bezels shall be installed on the module front. The lights shall operate from a switch on the master control console, labeled "Flashers". FRONT	1.00	Included



WARNING LIGHT LOCATION 2 - RED The warning light located on the upper front of the module in location 1 shall be red. FRONT WARNING LIGHT LOCATION 3 - RED The warning light located on the upper front of the module in location 2 shall be red. FRONT WARNING LIGHT LOCATION 5 - RED The warning light located on the upper front of the module in location 3 shall be red. FRONT WARNING LIGHT LOCATION 6 - RED The warning light located on the upper front of the module in location 4 shall be red.

SR00137459	----- LIGHT INTERIOR OF REAR FACING OSS & PASSAGE DOORS, TWO (2) RED MINI LED PER DOOR Two (2) Whelen red Mini LED lights shall be installed on the interior of all rear facing exterior compartment and patient entry doors. The lights shall be located as follows: one (1) on each upper and lower outer corner. The lights shall random flash upon door opening. (does not include the battery door) (16 lights)	1.00	1,066.00
SR00137463	----- LIGHTS, RUB RAIL - WHELEN LED STRIP - 4 EACH SIDE Install: Whelen strip lights on rub rail, (4) LED's each side - (2) red LED's and (2) white LED's alternating in color (red-white-red-white) along the module side, total of eight (8) lights, alternate flash with box warning lights.	1.00	1,322.00
SR00137471	----- LIGHTS, SIDE MODULE FLOOD (2) - WHELEN PIONEER PLUS LED DUAL (PFH2) Two (2) Whelen Pioneer Plus LED (PFH2) dual lamp floodlights with (PBH203) chrome trim ring shall be installed, one (1) each module side in the center position. These lights shall operate from The OEM switches in the Cab. Furthest Left Switch to activate the Left flood light, the next shall operate the Front and the third switch from the left is to operate the right flood light.	1.00	3,165.00
SR00137481	----- LIGHTS GRILLE - WHELEN 500 SUPER LED Four (4) Whelen 500 series super LED warning lights, with waterproof connectors shall be installed the grille area of the chassis. The lights shall operate from a switch on the master control console labeled "Flashers".	1.00	225.00
30-06-0410	----- WARNING LIGHTS FLASH PATTERN SIGNAL ALERT 75 - MULTIPLEX ELECTRICAL SYSTEM The default flash pattern for the vehicle warning lights: Signal Alert 75.	1.00	Included



ClearLENS	CLEAR LENSES ON ALL WARNING LIGHTS	1.00	Included
STRPTRN	STRAIGHT PATTERN WARNING LIGHTS The front warning lights will be aligned in a straight pattern across the module.	1.00	Included
30-25-0122	LIGHTS, ICC / LED CLEARANCE - ON MODULE FRONT - TECNIQ Install: (5) amber Tecniq LED (S33-AA00-1) clearance / ICC lights on the front of the module near the roof line per dwg #1.	1.00	Included
30-25-0123	LIGHTS, ICC / LED CLEARANCE - ON MODULE REAR - TECNIQ Install: (5) red TECNIQ LED (S33-RR00-1) clearance / ICC lights on the rear of the module near the roof line per dwg #2.	1.00	Included
ROL090002	LIGHTS REAR MODULE, UPPER OUTER - 2 WHELEN 900 LED Two (2) Whelen 900 series super LED warning light with chrome bezels shall be installed on the upper rear of the module, in the outer location. The lights shall operate from a switch on the master control console, labeled "Flashers".	1.00	Included
ROLCLR1R	REAR OUTER MODULE LIGHT LOCATION 1 - RED The warning light located on upper rear of the module, in outer location 1 shall be red.	1.00	Included
ROLCLR2R	REAR OUTER MODULE LIGHT LOCATION 2 - RED The warning light located on upper rear of the module, in outer location 2 shall be red.	1.00	Included
RCL060001	LIGHTS REAR MODULE, UPPER CENTER - 1 WHELEN 600 LED One (1) Whelen 600 series super LED warning light with a chrome bezel shall be installed on the upper rear of the module, center location. The light shall operate from a switch on the master control console, labeled "Flashers".	1.00	Included
RCLCLR1A	REAR CENTER MODULE LIGHT LOCATION 1-AMBER The warning light located on upper rear of the module in the center location shall be amber.	1.00	Included
RS060002	LIGHTS REAR SCENE - 2 WHELEN 600 LED Two (2) Whelen 600 Series super LED scene/load lights with chrome bezels shall be installed on the upper rear of the module. The lights shall operate from a switch	1.00	Included



	on the master control console, labeled "Rear Scene Lights".		
30-26-2002	----- TRAFFIC ADVISOR REAR OF MODULE WHELEN TAL-85 Install: Whelen #TAL-85 LED directional light bar on the rear of the module per dwg #2, to have a multi-function controller mounted in the OEM chassis cab in console with cut out on top plate to accommodate multifunction controller switch. -----	1.00	1,518.00
WL090002	----- LIGHTS REAR WINDOW - 2 WHELEN 900 SUPER LED Two (2) Whelen 900 series super LED warning lights with chrome flanges shall be installed on the rear of the module at window level, one (1) on each side. These lights shall operate from a switch on the master control console, labeled "Flashers". -----	1.00	Included
WLCLR1R	----- WINDOW LEVEL LIGHT LOCATION 1 - RED The warning light located on rear of the module at window level, location 1 shall be red. -----	1.00	Included
WLCLR2R	----- WINDOW LEVEL LIGHT LOCATION 2 - RED The warning light located on rear of the module at window level, location 2 shall be red. -----	1.00	Included
30-26-3008	----- LIGHTS, REAR TAIL - WHELEN 600 LED STOP, TURN, & MINIMUM INTENSITY BACK-UP Install: (1) pair each of Whelen 600 series LED stop/tail lights, turn lights, and LED MINIMUM intensity back-up lights with chrome bezels on rear of the module. -----	1.00	Included
30-26-7002	----- LIGHT, LICENSE PLATE LED - WHELEN OACOEDCR Install:(1) Whelen OACOEDCR LED license plate light with 45 deg angled chrome-plated bezel on the rear of module, lower left side. -----	1.00	Included
FIL07T0002	----- LIGHTS FRONT INTERSECTION - 2 WHELEN 700 LED W/15 DEGREE TILT HOUSING Two (2) Whelen 700 series super LED warning lights, with water-proof connectors, shall be mounted in 15 degree tilt housings on the front chassis fenders, one (1) on each side. The lights shall operate from a switch on the master control console labeled "Flashers". NOTE: When vehicle is placed in park, the override switch must be on for intersection light(s) to remain on. -----	1.00	Included
FILCLR1R	----- FRONT INTERSECTION LIGHT LOCATION 1 - RED The warning light located on front of the chassis fender in location 1 shall be red. -----	1.00	Included
FILCLR2R	----- FRONT INTERSECTION LIGHT LOCATION 2 - RED The warning light located on front of the chassis fender	1.00	Included



	in location 2 shall be red. -----		
RIL070002	LIGHTS INTERSECTION REAR - 2 WHELEN 700 LED Two (2) Whelen 700 series super LED warning lights with, chrome flanges and water-proof connectors, shall be installed above the rear wheel wells, one (1) on each side. These lights shall operate from a switch on the master control console screen labeled "Flashers". NOTE: When vehicle is placed in park, the override switch must be on for intersection light(s) to remain on. -----	1.00	Included
RILCLR1R	REAR INTERSECTION LIGHT LOCATION 1 - RED The warning light located on above the rear wheel well at location 1 shall be red. -----	1.00	Included
RILCLR2R	REAR INTERSECTION LIGHT LOCATION 2 - RED The warning light located on above the rear wheel well at location 2 shall be red. -----	1.00	Included
30-27-1102	LIGHTS, ICC / LED CLEARANCE - ON MODULE SIDE - TECNIQ Install: (2) red Tecniq LED (S33-RR00-1) clearance/ICC lights, (1) red on each side at rear of the vehicle, flash with turn signal, per Dwg #3 and #4. -----	1.00	Included
SWL090004	LIGHTS SIDE WARNING - 4 WHELEN 900 SUPER LED Four (4) Whelen 900 series super LED warning lights with chrome flanges shall be installed, two (2) on each side of module exterior per dwg. -----	1.00	Included
SWLCLR1R	SIDE WARNING LIGHT LOCATION 1 - RED The warning light located on side of the module, in outer location 1 shall be red. -----	1.00	Included
SWLCLR2R	SIDE WARNING LIGHT LOCATION 2 - RED The warning light located on side of the module, in outer location 2 shall be red. -----	1.00	Included
SWLCLR3R	SIDE WARNING LIGHT LOCATION 3 - RED The warning light located on side of the module, in outer location 3 shall be red. -----	1.00	Included
SWLCLR4R	SIDE WARNING LIGHT LOCATION 4 - RED The warning light located on side of the module, in outer location 4 shall be red. -----	1.00	Included
SS090004	LIGHTS SIDE SCENE - 4 WHELEN 900 24 DIODE LED Four (4) Whelen 900 series 24 Diode LED scene lights with chrome flanges shall be installed, two (2) each module side. These lights shall operate from switches on the master control console labeled "Left Scene Light" and "Right Scene Light".	1.00	Included



Braun - Module Body Construction

Item Number	Name	Quantity	Price
SR00137431	CUSTOM MODULE LENGTH & HEIGHT Module Headroom to be 74" and Length to be 173"	1.00	7,200.00
39-00-0005	AWS ALUMINUM CERTIFIED WELDERS	1.00	Included
39-10-0003	CONNECTIONS, MODULE Bolt: to the chassis frame rail with (12) 5/8" -11 grade 8 bolts through OEM rubber insulating spacers installed on outriggers at twelve (12) separate locations (six each frame rail), providing noise insulation and easy removal for chassis replacement, mounting bolts to be properly torqued and secured with locktite, system used for fastening the module to the frame to be that approved by the chassis manufacturer.	1.00	Included
40-00-0080	INSULATION - POLYURETHANE SPRAY FOAM The walls, ceiling, passage doors, outside storage doors, the entire underside of the module floor (except for mounting pads), the underside of the outside storage compartments, the wheel wells, and the underside of the curbside step area shall be completely foam - in - place insulated with nominal 3/4" thick sprayed on Class I, urethane foam for thermal and acoustical insulation. The insulation shall comply with FMVSS #302 flame spread requirements. The underside of the body shall be properly prepared to ensure adhesion before the spray insulation is applied.	1.00	Included
39-00-0001	MODULE BODY CONSTRUCTION - SEAMLESS Module: fabricated entirely of parts cut and formed from .125" (minimum) thickness 5052-H32 flat aluminum sheet stock, using CNC machines capable of .010" repeatability. This is the only alloy that may be used for body parts that are welded together. Roll-cage type interior super-structure, aluminum partition and module welded together into a single unit, roof designed with a minimum 1.5" crown to facilitate water run-off. Floor, roof, sides, all exterior doors fabricated from .125" (minimum) thick flat aluminum sheet stock, exterior joints between the roof and side components continuous full seam welded the entire length of the module. All exterior body panel joints continuous full seam welded. No VHB bonding tape or other adhesives used in the construction of the ambulance module.	1.00	Included



39-00-0002	SOLE SOURCE MODULE BODY CONSTRUCTION	1.00	Included
------------	--------------------------------------	------	----------

Braun - Module Features / Exterior

Item Number	Name	Quantity	Price
SR00137430	RUB RAILS, ANODIZED ALUMINUM, "C" CHANNEL Install: bright dip anodized aluminum "C" channel rub rails on lower sides of body below outside compartment sill areas, rub rails to be offset 3/16" from body.	1.00	1,532.00
SR00137437	OSS #1 - EZ-O2 LIFT OXYGEN SYSTEM OSS #1 streetside forward, with an EZ-O2 lift system, for housing an O2 cylinder. Install a fixed shelf 62" from the floor with a gasket to seal against the door to seal off the upper section of the compartment. Air horn compressor, suction pump, and inverter to be located above the shelf, louvers in the upper section, sound deadening material. Door post changes on forward side of OSS #1.	1.00	4,489.00
SR00137457	OSS #4 - BACKBOARD AND (2) ADJUSTABLE SHELVES WITH OUTSIDE ACCESS AND FIXED DIVIDER OSS #4 curbside rear, with one (1) fixed vertical divider for backboard/scoop stretcher storage on one side and and two (2) adjustable shelves. Door open as far as possible and no track on the lower 32", referene 8196.	1.00	Included
SR00137462	OSS #2 - (2) ADJUSTABLE SHELVES OSS #2 streetside center, with two (2) adjustable shelves.	1.00	Included
SR00137478	OSS #4A - OPEN STORAGE Outside storage compartment #4A, lower Curbside, located between compartment #4, and wheel.	1.00	1,434.00
SR00152319	OSS #3 DOUBLE DOORS OSS #3: OSS #3: Double doors-Outside Access Only. Full height cabinet with shallow upper portion. (1) Adj. Shelf. (shelf depth adjusted to allow for the full length tapping plate) in full depth lower section. Upper and lower section both to have a full size exterior tapping plate for post production tool mounting. Upper section to have minimum of 12" depth from tapping plate to doors. 2 Zico SCBA brackets (installed at final inspection) to be affixed to the upper section tapping plate. Doors to open as wide as possible.	1.00	2,255.00



40-00-0009	----- ALUMINUM PARTS - MODULE EXTERIOR All unpainted exterior aluminum parts to be bright dip anodized after fabrication to retain the finish and increase corrosion resistance.	1.00	Included
40-00-0010	----- CORROSION MINIMIZATION - MODULE All module contact with dissimilar metals shall be minimized with the use of nylon screw-hole inserts to provide hinge to door isolation with the module body, polypropylene strip hinge Isolation, polyethylene backed rubber tape, ceramic coated stainless steel hinge bolts, and ECK brand corrosion inhibitor spray.	1.00	Included
40-00-0020	----- DOOR CONSTRUCTION - GASKET PLACEMENT All exterior hinged module doors shall be constructed in an inverted pan-formed design. The pan shall be constructed from .125" thick 5052-H32 flat sheet aluminum. The exterior door skin shall be constructed of .190" thick aluminum and welded to the pan. Door gaskets shall be attached to the interior side of the door skin on the top, bottom and outer edge of the door. The gasket on the hinge side of the door will be attached to the door frame.	1.00	Included
40-00-0060	----- EXTERIOR COMPARTMENTS - SWEEP-OUT Exterior module compartments: a sweep-out design to aid in facilitation of the purchaser's routine care and cleaning of the vehicle. All exterior compartment floors, with the exception of the front ALS compartment to be constructed to be flush with the bottom door frame.	1.00	Included
40-00-0030	----- EXTERIOR COMPARTMENTS DESIGN All exterior compartments shall be vented and include: sound absorbing slip resistant polyurethane material sprayed on the inside of all compartments and compartment shelving, slide out trays and closeouts, baffled seep holes provided to prevent water from splashing or seeping into the exterior compartments, full-length, two-way adjustable, stainless steel hinges on all exterior compartment doors with 3/16" stainless steel hinge pins, compartment doors installed, flush with the module body, when double doors are provided, each door to have exterior handle, but only the forward door lockable, rearward door is secured when forward door is locked), all exterior compartments and passage doors keyed alike, lockable Eberhard "free-floating" type chrome plated handles with rotary locks. Gasket installed under each handle to protect the paint; drip rails installed above all exterior compartment doors.	1.00	Included



40-00-0055	----- EXTERIOR COMPARTMENTS, VENTING - OXYGEN STORAGE (9) square inches (minimum) of venting provided in the exterior oxygen storage compartment, to dissipate any leaking oxygen gas. -----	1.00	Included
40-00-0070	----- HANDLES, EBERHARD - CHROME FREE FLOATING TYPE Install: Eberhard #EMC-1-2110 chrome "free-floating" handles on each exterior module door, large enough to accommodate a gloved hand. -----	1.00	Included
40-10-0072	----- LOWERED MODULE SIDES Module sides to be as low as possible and still comply with KKK-1822-F ramp break over angle. -----	1.00	Included
40-10-0321	----- STEPWELL, CURBSIDE DOORWAY - MID STEP AREA Install: aluminum diamond plate step well and mid-level step in curbside doorway threshold area. -----	1.00	Included
40-00-0091	----- THRESHOLD, STAINLESS STEEL - ALL OSS STORAGE COMPARTMENTS Each exterior storage compartment with a hinged door: stainless steel lower threshold at the door opening to protect the paint. -----	1.00	Included
40-10-0340	----- STONE GUARDS, MOD FRNT -ANODIZED DIAMOND PLATE Install: anodized aluminum diamond plate stone guards on module front, (1) each side. -----	1.00	Included
40-10-0066	----- DOOR SLIDING - MODULE CURBSIDE PASSAGE Install EZ Glide curb door. -----	1.00	Included
40-10-0088	----- DOORS - REAR PASSAGE Patient compartment rear door opening: doors flush without a protruding flange or lip, right rear passage door lockable, chrome exterior handle, left rear door non-locking, chrome exterior handle, all handles installed with a gasket, hinge full length stainless steel with a 3/16" stainless steel hinge pin, two-way adjustable, each rear door two-point slam action automotive type rotary latching system to the body, right rear door lock to the body at the top and bottom, not to left rear door, doors .213" steel door latch activator rods with clevis adjusters, doors lockable from inside and outside, shut on molded, air-core, automotive type door seals to prevent water from leaking into vehicle interior. -----	1.00	Included
40-10-0130	----- EMERGENCY RELEASE LEVER, REAR PATIENT PASSAGE -----	1.00	Included



	DOORS Install emergency release lever, attached to each rear passage door latch to be free-floating from the interior door linkages. -----		
40-10-0505	WINDOWS, PASSAGE DOOR - (CURB SLIDING, REAR FIXED) Curbside passage door (sliding) window with removable screen, rear passage doors w/ non-openable window, windows 69% dark tint, secured with black oxide coated fasteners, open doors not to block warning lights. -----	1.00	Included
40-10-0103	FENDERETTES - POLISHED ALUMINUM Install: Polished aluminum fenderettes around the rear wheel well openings. -----	1.00	Included
40-10-0119	HOLD-OPEN - REAR DOORS - GRABBERS Install: door grabbers (1 pair) with hard rubber inserts on rear doors. -----	1.00	Included
40-10-0360	KICKPLATE/THRESHOLD, REAR DOORWAY - ANODIZED DIAMOND PLATE Install: anodized aluminum diamond plate kick plate at the rear exterior doorway, providing a kick / scuff plate at rear of the vehicle above rear step, per dwg # 2. -----	1.00	Included
40-10-0204	MUD FLAPS, REAR - BLACK RUBBER FIBERGLASS REINFORCED - THREE COLOR Install black rubber, fiberglass reinforced mud flaps with a minimum 1/4" thickness bolted to underside of module behind rear wheels, to provide adequate coverage of rear dual wheels of the chassis, mud flaps to be (3) color with the Manufacturers Logo. -----	1.00	Included
40-10-0266	REAR STEP/BUMPER -FLIP-UP CENTER SECTION - STAR PUNCHED AND ANODIZED Affix: rear bumper to chassis frame, constructed with a hinged center section, (2) steel braces to secure step to chassis frame, outer 17" on each end of bumper constructed from heavy gauge stamped polished stainless steel bumper parts, to provide smooth rounded corners, step constructed of star punched .125" thick aluminum diamond plate, (2) rear LED step illumination lights provided. All diamond plate surfaces to be anodized; strip of black PVC installed on face of step. -----	1.00	Included
40-10-0381	TOW HOOKS, MODULE REAR Secure: fasten (2) tow hooks in rear step area to rear step braces. -----	1.00	Included



40-00-0019	DOOR SKINS, OUTSIDE STORAGE COMPARTMENTS - DIAMOND PLATE INTERIOR SKINS Interior door skins for all outside storage compartments constructed of .063" thick aluminum diamond plate. -----	1.00	Included
OS102EZ	OSS #1 - OXYGEN STORAGE EZ O2 LIFT An E-Z O2 lift shall be mounted to the door as an assisted lift for the H and M cylinders. -----	1.00	Included
OS2XL1STD	OSS #2 - STREETSIDE CENTER OSS #2 streetside center, hinged double doors with spring-loaded gas cylinders, handles installed on the exterior of each door, forward door with locking handle. -----	1.00	Included
OS2SHELF2	OSS #2 - SHELVES TWO (2) ADJUSTABLE WITH TRACK Outside storage compartment #2 shall contain two (2) adjustable shelves with track. -----	1.00	Included
OS5XL1STD	OSS #5 - CURBSIDE FORWARD OSS #5 curbside forward, hinged door with spring- loaded gas cylinder, locking handle installed on the exterior of the door. -----	1.00	Included
OS5XL1OP1	OSS #5 - INSIDE/OUTSIDE ACCESS TO THE ALS CABINET - #5B OPEN STORAGE AREA OSS #5 curbside forward, inside/outside access to the ALS cabinet, and #5B lower storage area. -----	1.00	Included

Braun - Module Interior / Patient Compartment

Item Number	Name	Quantity	Price
SR00137413	ACTION AREA The action area is to include suction control, (1) 125VAC (1) 12VDC (1) dual USB outlet, (2) ohio Med oxygen outlets and bypass valve. Vista screen mounted on angled flip-down panel with chrome lever latches. -----	1.00	2,160.00
SR00137424	CABINET -FRONT WALL CABINETS WITH CARGO NETS, (3) ADJ. SHELVES: Front wall, interior cabinet #2 and #3 shall each be single compartment and have a RED cargo net on each, Buckles shall be installed on the bottom of the net and compartment shall each have an adjustable shelf and also have an adjustable shelf acting as a barrier between the cabinets per dwg. #7. -----	1.00	1,425.00
SR00137433	CABINET - SLIDING POLYCARBONATE DOORS WITH (1) FIXED SHELF, SHALLOW DEPTH STORAGE RECESSED INTO OSS #3 Left wall rear interior cabinet (#3): fixed frame, sliding polycarbonate doors w/ full length	1.00	1,026.00



	handles, the outer most sliding door to have handles on both ends, (1) fixed shelf, shallow depth storage, with top/bottom dividers (6 top/6 bottom). Sliding polycarbonate doors and flip up restocking frame.		
SR00137435	----- CABINET - HINGED ALUMINUM DOOR WITH CENTER SQUEEZE LATCH AND GAS SHOCK HOLD-OPEN Front wall over pass thru interior cabinet (#5): cabinet w/ (1) flip up hinged aluminum door with gas filled hold-open shocks, center squeeze latch. Temperature adjustable warming plate with thermostat within cabinet.	1.00	1,158.00
SR00137436	----- ASPIRATOR / SUCTION - SSCOR - WITH ELECTRIC PUMP - RECESSED A SSCOR suction system shall be recessed into the street side lower interior wall near the attendant's seat per dwg. #5 dimensions. The 12 VDC SSCOR electric vacuum pump to be installed in OSS #1 compartment. (must use SSCOR pump and tubing)	1.00	Included
SR00137439	----- STAINLESS STEEL WALL PROTECTION - INTERIOR STREETSIDE: A brushed stainless steel panel shall be provided on the street side wall 6" from the Floor. Per dwg. #5.	1.00	Included
SR00137443	----- STREET SIDE INTERIOR DRAWER #5 Cabinet with solid acrylic countertop pull-out drawer toward the bench with 3 front-to-back adjustable dividers within drawer locking stainless steel flush pull latch.	1.00	1,104.00
SR00137445	----- OXYGEN OUTLET (1) CEILING - OHIO MED - AT FOOT OF COT AREA: One (1) Ohio Medical flush mounted, quick release oxygen outlet shall be installed in the ceiling above the foot of cot area	1.00	Included
SR00137446	----- OVERHEAD CABINETS WITH HINGED POLYCARBONATE DOORS, GAS SHOCK HOLD-OPENS, AND CENTER SQUEEZE LATCHES. Curbside interior cabinets #1 & #2 above the seating area with hinged polycarbonate doors with six (6) adjustable dividers in each cabinet. each flip door shall have a center squeeze latch per dwg. #6.	1.00	1,197.00
SR00137448	----- SHARPS-STREETSIDE add hinged door and hinged acrylic flap with an ABS funnel on the bottom side of the acrylic flap to the top of the counter top, over the	1.00	955.00



sharps cutout. Sharps container will be a customer supplied 4.7qt container.

SR00137456	----- ASSIST HANDLES, (2) 'V-BARS' KNURL STYLE, (4) KNURL ASSIST A total of eight (8) assist handles shall be provided: two (2) 1-1/4" diameter Knurl style 'V' handles, one (1) on each passage door; and six (6) 12" Knurl assist handles: two (2) handles at the rear doorway-one on each side, one (1) at the curbside doorway, one (1) on the curbside door per dwg. #6, one (1) at the end of the squad bench in the stepwell area per dwg. #8, one (1) on the exterior by the forward curbside door per dwg. #4.	1.00	1,221.00
SR00137458	----- CABINET - (2) PULL-OUT DRAWERS TOWARDS THE CPR SEAT WITH LOCKING STAINLESS STEEL FLUSH PULL LATCHES Left wall interior cabinet (#5) below action area: two (2) vertically stacked drawers facing the CPR seat . Each drawer shall have a locking, stainless steel, flush pull latch 3 front to back adjustable dividers in each drawer	1.00	2,004.00
SR00137466	----- FRESH AIR INTAKE Install a fresh air intake on the curbside forward above the curbside doorway.	1.00	297.00
SR00137468	----- CABINET - RESTOCKNG FRAME WITH SLIDING POLYCARBONATE DOORS AND (1) FIXED SHELF Left wall, upper rear interior cabinet (#1): sliding polycarbonate doors w/ a flip-up restocking frame, gas filled hold-open shocks, full length handles w/ outer most sliding door to have handles on both ends, (1) fixed shelf, 2 ea top/bottom dividers	1.00	1,218.00
SR00137470	----- CURBSIDE CABINET AT HEAD OF BENCH Cabinet stack at head of squad bench. with (1) pull out drawer #4 toward bench. Install 3 front to back dividers in drawer #4. With locking stainless steel flush pull latch. Notch below drawer for access to a sharps/waste pull out drawer into the isle with a drop from the top hinged acrylic lid and a locking stainless steel flush pull latch. Install a (1)125VAC (1) 12VDC (1) dual USB above countertop, per dwg. #6. Front side of cabinet stack towards the step area is to be a Recessed (3) glove box holder per drawing #8	1.00	2,546.00
SR00137473	----- CABINET - RESTOCKNG FRAME WITH SLIDING	1.00	1,323.00



	POLYCARBONATE DOORS AND (1) FIXED SHELF Left wall, upper interior cabinet (#2): sliding polycarbonate doors, flip-up restocking frame w/ gas filled hold-open shocks, full length handles, outer most sliding door to have handles on both ends, (1) fixed shelf with top/bottom dividers (6 top/6 bottom).		
SR00137474	----- CABINET - HINGED POLYCARBONATE DOOR WITH CENTER SQUEEZE LATCH AND GAS SHOCK HOLD-OPEN Left wall upper interior cabinet (#6): cabinet w/ (1) flip up hinged polycarbonate door with gas filled hold-open shocks, center squeeze latch. -----	1.00	Included
SR00137485	STORAGE AREA, ABS OVER CURBSIDE DOOR Install an ABS storage area with plexiglass door and quarter turn latch, in the head pad over the curbside entry door.	1.00	Included
50-51-1001	----- CABINET CONSTRUCTION - INTERIOR - ALUMINUM All interior cabinets shall be constructed of .090" thick welded aluminum. -----	1.00	Included
50-51-1014	CATCH, MAGNETIC - ADHESIVE BACK FOR INTERIOR DOOR(S) OVER 36 INCHES All interior doors that are over 36" inches tall with a latch on the top of the door shall have an adhesive back magnetic catch installed on the bottom of the door. -----	1.00	Included
50-60-0220	EMBLEMS / SIGNS - REAR PATIENT COMPARTMENT (2) "No Smoking / Oxygen Equipped / Fasten Seat Belts" signs: (1) sign installed in the cab, (1) above the oxygen outlets in the patient compartment street side cabinet. -----	1.00	Included
50-60-0300	FLOOR CONSTRUCTION- PATIENT COMPARTMENT, NON-WOOD COMPOSITE Sub-floor in the patient compartment: constructed of .125" thick aluminum over .125" and .190" thick reinforcing hat sections and mounting laterals, aluminum sub-floor covered with a 3/4" non-wood composite material, all corner molding, edging and trim anodized aluminum or stainless steel and sealed to prevent fluids from seeping under the cabinets. -----	1.00	Included
50-60-0301	FLOORING - COVE Patient compartment floor radius: coved with pre-formed floor coving material, installed behind the vinyl floor covering, along both the street side and curbside walls.	1.00	Included



50-60-0391	----- HEADLINER - REAR PATIENT COMPARTMENT Headliner in the patient compartment shall be one-piece, seamless, .090 thick aluminum finished with sprayed-on multi-use polychromatic coating.	1.00	Included
50-51-1013	----- HOLD OPENS FOR INTERIOR DOORS All interior cabinets with doors less than 6" tall shall have friction hinges as hold opens for door(s). Doors 6" and taller shall be designed using gas shocks as hold opens for the door(s).	1.00	Included
50-60-0660	----- PADDED EDGING PROTECTION Install: padded corner edging where necessary on exposed corners and edges in the patient compartment for patient and attendant protection.	1.00	Included
50-00-0202	----- ROUNDED INTERIOR CORNERS Interior vertical edges: rounded/padded corners in the following locations: forward and aft edges of the CPR seat, the wall at the aft end of the squad bench, the partition opening cabinet edges and the upper front wall cabinet.	1.00	Included
50-51-1011	----- RECESSED ADJUSTABLE SHELF TRACK - CABINETS Install recessed adjustable shelf track in cabinets.	1.00	Included
50-51-5001	----- UPHOLSTERY - PATRIOT PLUS CHARCOAL #8605 All cushions, head pads and seating surfaces shall be covered with Patriot Plus Charcoal #8605	1.00	Included
50-60-0661	----- INTERIOR MODULE PADS Vinyl upholstered, foam cushioned head/back pads shall be installed as follows: the lower edge of the upper front wall cabinet (above the partition doorway or window), above the rear doors, above the side door, and on the street side wall behind and on each side of the CPR seat. The pads shall be covered with a flame-retardant color coordinated vinyl upholstery material.	1.00	Included
50-51-6003	----- LONPLATE II, NON-SLIP EMBOSSED SM. GRID - GUNMETAL #424 The floor in the patient compartment shall be covered with Lonseal brand "Lonplate II" non-slip; small grid (embossed) Gunmetal #424.	1.00	Included
50-51-2002	----- CABINET DOORS - CLEAR POLYCARBONATE All cabinet doors shall be clear polycarbonate material / installed in aluminum track lined with PPL inserts / An edge mounted aluminum handle shall be installed on	1.00	Included



	each sliding cabinet door.		
50-51-3001	CABINETS/ WALLS - POLYCHROMATIC COATING - MARBLE STONE Headliner, walls, cabinet faces, and cabinet interiors MultiSpec color to be Marble Stone	1.00	Included
IS-CNT-ACR	COUNTER TOP, SOLID ACRYLIC Install: solid acrylic countertop with 1/2" lip on the primary action area.	1.00	1,823.00
50-51-4055	COUNTERTOP - SOLID ACRYLIC - BLACK ONYX MIRAGE A solid acrylic counter top, Black Onyx Mirage.	1.00	Included
50-01-0301	INVENTORY CONTROL SYSTEM Install mini footman loops on the sliding door cabinet frames, and drill holes in the cabinet door handles for the inventory control system	1.00	120.00
50-01-0411	LATCHES, CABINET, CN10 COMPLIANT AS APPLICABLE The ACP (attendant control panel) door and the PDQ (power distribution quarters) door shall be secured with chrome locking lever latches, all remaining interior hinged cabinet doors with center squeeze latches (if applicable). All interior drawers with flush pull latches (if applicable).	1.00	Included
50-10-0226	LEFT WALL - ATTENDANT CONTROL PANEL - HINGED PANEL A hinged access panel and secured with two (2) latches to the immediate right of the attendant's seat, color microprocessor screen installed on the panel.	1.00	Included
IC-CNT-ACR	COUNTER TOP, CURBSIDE - SOLID ACRYLIC Install: solid acrylic countertop with 1/2" lip on the cabinet at the head of the curbside seating area.	1.00	1,111.00
50-50-0541	HOLD OPENS - SQUAD BENCH LID - GAS CYLINDERS Gas cylinder hold-open(s) shall be provided and installed to hold lid in the open and closed position.	1.00	Included
SQ-BN-BASE	SQUAD BENCH BASE W/STORAGE A storage area shall be provided in the squad bench base. The squad bench base shall be constructed of .090" thick aluminum for maximum storage capacity and minimum weight. The interior of the squad bench shall be sprayed with sound absorbing polyurethane material.	1.00	Included
IF3PDQ	CABINET - PDQ The Power Distribution Quarters (PDQ) shall hold electrical components, (i.e., power distribution nodes,	1.00	Included



	circuit breakers, etc.), hinged door with (2) chrome locking lever latches, located on the partition wall behind the attendant seat.		
50-60-0001	AIR PURIFICATION SYSTEM, ULTRAVIOLET Install a Ultraviolet Air Purification System within the heater/AC.	1.00	518.00
IF1XL1C4	CABINET - FRONT WALL, UPPER #1 - HINGED ALUMINUM DOOR W/INSERT The front wall interior cabinet #1, flip up hinged aluminum door with polycarbonate insert and gas shock hold-open(s), center squeeze latch, (1) adjustable shelf.	1.00	Included
IF1XL1OP4	CABINET WITH HINGED ALUMINUM DOOR WITH POLYCARBONATE INSERT AND CENTER SQUEEZE LATCH WITH (1) ADJUSTABLE SHELF Install cabinet with hinged aluminum door with polycarbonate insert and gas shock hold-open(s) in the upper front wall.	1.00	Included
IF3XL1OP1	CABINET - VENTED RADIO CABINET PDQ ABOVE Power Distribution Quarters (PDQ) compartment and a vented radio compartment below the PDQ, lower front wall, left.	1.00	Included
IF3XL1RAD	CABINET - FRONT WALL, LOWER BELOW PDQ (SINGLE VENTED DOOR) A radio cabinet with a vented, hinged aluminum door, secured by a chrome locking lever latch, located on the front lower left wall, door to open towards rear of the module.	1.00	Included
IF4XL1OP4	CABINET - HINGED POLYCARBONATE DOORS WITH CENTER SQUEEZE LATCHES, PASS-THROUGH WINDOW OPEN TO THE CAB Window opening, pass-through from cab to module. A cabinet with hinged polycarbonate doors located below window opening. The cabinet to have oen (1) adjustable shelf.	1.00	1,336.00
IF-CNT-ACR	COUNTER TOP, SOLID ACRYLIC Install: solid acrylic countertop with a 1/2" lip in the pass-through opening.	1.00	1,111.00
50-20-0507	PASS THROUGH - CAB TO MODULE, WINDOW OPENING A window opening: provided in the rear of the cab to accommodate pass-through communications to the patient compartment, bellows provided to connect the cab to the module.	1.00	Included



50-50-0118	----- SEATING - ATTENDANT - USSC VALOR R - BACK INTEGRAL CHILD, SWIVEL SEAT CN8 COMPLIANT A USSC Valor rear facing, R-back attendant seat with an integrated child seat installed at the head of the patient cot: a (2) position swivel seat mounted on a pedestal base with a heavy-duty seat frame / ABTS (All Belts To Seat) application with (4) point / (4) retractors single click internal mount belt system. The seat shall be padded and covered with sewn matching vinyl upholstery. -----	1.00	3,020.00
50-50-0121	----- SEATING - ATTENDANT - CENTERED WITH COT Attendant seat to be centered with cot per dwg #9 -----	1.00	369.00
50-50-0333	----- CPR SEAT STORAGE AREA, BELOW SEAT - W/HINGED SEAT BOTTOM The bottom seat cushion shall be hinged with a storage area located below. The interior of the storage area shall be sprayed with sound absorbing polyurethane material. An automatic latching fastener shall be installed to secure the CPR seat lid in the closed position. -----	1.00	878.00
CPROP4	----- SEATING - CPR - EVS WITH BACKPACK HARNESS A CPR seat shall be installed on the street side of the patient compartment aft of the primary action area counter. The CPR seat shall be KKK-A-1822F Change Notice 8 compliant with the Backpack style shoulder / seat belt system and conform to all applicable FMVSS and SAE J3026 requirements. -----	1.00	1,350.00
SQSTOP7	----- SEATING - CN8 COMPLIANT TWO (2) EVS BACKPACK A Squad bench seat: (2) EVS individual seating positions will be installed on the curb side of the patient compartment. Seats shall have the EVS Backpack Belting system and be covered with color coordinated, cut and sewn vinyl. -----	1.00	2,407.00
50-41-0408	----- HEAT/AIR CONDITIONING, PROAIR IW-3856 CD CENTER DUCTED - 700 CFM (56,000 BTU HEAT / 38,000 BTU COOL) BRUSHLESS BLOWER -----	1.00	2,370.00
COND_HSL_01	----- HVAC - SINGLE COIL CONDENSER - 24,000 BTU A single coil condenser, 24,000 BTU Low Profile, shall be installed on the front of the module. The condenser shall be top center mounted with mounting brackets. Condenser and brackets are to be painted to match the module. -----	1.00	2,021.00
COND_BRK_01	----- CONDENSER BRACKET TO BE FLAT DESIGN AND COLOR -----	1.00	Included



	MATCH TO THE CONDENSER The condenser bracket shall be a flat designed, painted to match the condenser, mounted to the bulkhead of the module.		
50-60-0730	DOOR PANELS - MODULE PASSAGE DOORS - FULL LENGTH ALUMINUM - W/ACCESS PANELS Interior rear and curbside passage door panels to be full length aluminum, Multi-Spec sprayed to match interior color and contain removable latch access panel per dwg. # 6 & # 8. (Total 3).	1.00	Included
50-60-0256	EXHAUST VENTILATOR, 3-SPEED - MULTIPLEX ELECTRIC SYSTEM Install: three-speed, 250 CFM (minimum) exhaust fan in the street side cabinet in the patient compartment, fan pulse width modulated from a switch on the attendant control panel vista screen, exhaust system to have a louvered grille inside and a chrome vent outside, system vent through the side of the vehicle, not through the roof.	1.00	Included
50-60-0325	NO - GLOVE, DISPENSER - CURBSIDE ABOVE DOOR Delete the glove box (3) dispenser above the curbside door.	1.00	Included
50-60-0332	GLOVE DISPENSER - (1) BOX - EACH REAR DOOR - TOTAL TWO (2) A single box glove dispenser unit, with a clear acrylic hinged access panel with cut-out, shall be recessed on the rear passage doors, one each door per dwg #8.	1.00	600.00
50-60-0351	GRAB RAILS, 1-1/4" DIAMETER, (96") OVER COT & (64") SQ BENCH Install 64" stainless steel grab rail over the squad bench area.	1.00	Included
50-60-0431	IV HANGERS - CEILING RECESSED - CAST PRODUCTS #IV2008-1 (2) Two (2) Cast Products #IV2008-1 recessed; dual ceiling I.V. hangers shall be provided per Dwg #9 locations.	2.00	Included
50-60-1640	OXYGEN OUTLET (1) RIGHT WALL - OHIO MED - HEAD END OF SEATING AREA One (1) Ohio Medical flush mounted; quick release wall outlet shall be installed in the right wall above the head end of the curbside seating area. Per dwg #6	1.00	Included
50-60-0629	FLOW METER, OXYGEN - THORPE STYLE One (1) Thorpe style oxygen flow meter (15LPM) shipped loose with the completed vehicle.	1.00	Included



50-60-0286	OXYGEN - ZICO QR-D-2 PORTABLE OXYGEN STORAGE BRACKETS TWO (2) RECESSED INTO HEAD OF SQUAD BENCH Two (2) Zico #QR-D-2 storage brackets for "D" oxygen cylinders, shall be recessed and installed into the forward end of the squad bench and accessible from the curbside stepwell.	1.00	1,521.00
------------	---	------	----------

Braun - Optional Patient Compartment Items

Item Number	Name	Quantity	Price
SR00137438	OTE 19507A CLIMATE CONTROLLED CABINET-TEMPERATURE CONTROL MODULE Install: 12-volt OTE key locking climate controlled cabinet at the action area counter, with an exterior vent.	1.00	3,619.00
SR00137450	STAINLESS STEEL WALL PROTECTION - INTERIOR CURBSIDE: A brushed stainless steel panel shall be provided on the street side wall 6" from the Floor.	1.00	Included
SR00137452	AISLE LIGHTING Install Ridgeback strip lights in a aluminum channel under the stainless steel wall protectors on the street side and the curb side.	1.00	1,340.00
SR00137461	CODE 3 VITAL VIO DECONTAMINATION SYSTEM PCL-LED-VV PATIENT LIGHT VV, 48LED, 12-24VDC (BARE LEADS) Install (3) Code 3 Vital Vio Antimicrobial Light Disinfection units in module headliner.	1.00	2,184.00
DECON-EVER-01	EVERGREEN LUMALIER UV ADU-136-PB DECONTAMINATION SYSTEM Install an Evergreen Lumalier Decontamination UV-C system per drawings.	1.00	3,583.00
50-62-0446	COT FASTENER - STRYKER FLOOR PLATE AND 12v PRE-WIRE FOR CUSTOMER FUTURE INSTALL OF A POWER OR PERFORMANCE COT LOAD SYSTEM Install Stryker Floor plate kit and 12v pre-wire for Customer supplied / Customer installed Stryker Performance or Power Load Cot	1.00	Included
30-10-0502	LIGHTS, INTERIOR - WHELEN MINI LED BRAKE/TURN REAR HEADPAD Install: Whelen Mini-LED turn signal and brake light on rear headpad above the rear doors (amber / red / amber).	1.00	240.00

Braun - Paint / Graphics



<i>Item Number</i>	<i>Name</i>	<i>Quantity</i>	<i>Price</i>
60-01-0001	PAINT PROCEDURE All non-anodized aluminum module body surfaces: completely chemically steam cleaned, filled with premium body filler as needed, sanded smooth and primed with an epoxy primer and then primed again with a high solid primer, cured primer surfacer shall be DA sanded with 320 grit and cleaned. A high solid primer shall then be applied, where needed, as a sealer. -----	1.00	Included
60-01-0005	STANDARDS AND SPECIFICATIONS FOR VEHICLE PAINT APPEARANCE Adhere to Standards and Specifications for Vehicle Paint Appearance. -----	1.00	Included
60-10-0108	CAB - OEM PAINT FORD OEM RACE RED -----	1.00	Included
60-01-0004	BUFFING, PAINT - MODULE The paint on the module sides shall be buffed to a high shine using a recommended paint buff system. -----	1.00	Included
60-09-0101	PAINT MOD ALL ONE SOLID COLOR, PLUS CLEAR COAT FORD OEM RACE RED The entire module shall be sprayed one-color and then clear coated. -----	1.00	Included
60-30-0200	REFLECTIVE - DOOR REFLECTIVITY Install reflective material (25" x 2.5" red/silver chevron style), on the lower interior stainless steel panel of each rear door and hinged side door. NOTE: If a sliding side door is provided, install a 1.50" x 40.00" white reflective stripe on the rear facing edge. -----	1.00	Included
60-25-0101	REFLECTIVE - BLACK MATERIAL IN RUB RAILS Install black reflective material in rub rails. -----	1.00	Included

Braun - Vehicle Manuals

<i>Item Number</i>	<i>Name</i>	<i>Quantity</i>	<i>Price</i>
80-20-0001	VEHICLE MANUALS (1) PACKAGE SET One (1) Delivery Manual Package shall be supplied with the vehicle, and shall include the following items: Ambulance manufacturer parts, service, and operation manuals, OEM chassis owner's guide, complete 12 VDC and 125 VAC wiring schematics for all included standard and optional systems, Multiplex Electrical system programming - electronic media -----	1.00	Included
90-10-0007	STATEMENT OF LIMITED WARRANTY NEW AMBULANCES	1.00	Included



DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE

OVERALL HEIGHT = 114"

OVERALL WIDTH WITH RUB

RAILS & FENDERETTES = 98"

WHELEN 700 CLEAR LED LIGHT WITH A PIONEER
PCH1 COMBINATION SPOT/FLOODLIGHT IN A PBH103
RECESSED HOUSING POINTING STRAIGHT OUT

(5) TECNIQ S330 AMBER
MINI-LED MARKER LIGHTS

(2) WHELEN 600 RED
ROTA-BEAM LED LIGHTS

NOTE: MODULE TO HAVE
74" HEADROOM AND BE
173" IN LENGTH.

LOCKING, SLIDING
WINDOW IN CAB

OEM POWER
ADJUSTABLE
MIRRORS

FLASHING HEADLIGHTS W/
DAYTIME RUNNING LIGHTS

BUCKSTOP OUTBACK
BUMPER/GRILLE GUARD

2" LED RUNNING
BOARD LIGHTS

BUELL AIR HORNS

(4) WHELEN 900 RED
LED LIGHTS WITH
CLEAR LENSES

HOSELINE TMC2007 CONDENSER
WITH (4) WHELEN 700
LED SCENE LIGHTS

(2) CODE 3 VITAL
VIO UV LIGHTS IN
THE CAB HEADLINER
(LOCATION MAY VARY)

(4) WHELEN 500 SERIES
SUPER LED GRILLE
LIGHTS WITH CLEAR LENSES:
LEFT - RED/RIGHT - WHITE

HIDDEN UNLOCK SWITCH
IN GRILLE AREA

CAST PRODUCTS RECESSED
100-WATT SIREN SPEAKERS.
CONNECTED TO PRIMARY
SIREN CONTROL.

-CHASSIS TO BE 4x4-

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.

PERRYSBURG F.D.



FRONT EXTERIOR VIEW
CHIEF XL-I/F550 CHASSIS


DATE:
1-16-23
DWG. TKD
REV. A

DRAWING NO.
CPQ# 6907
PFD-1

APPROVAL SIGNATURE:

DATE:

DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE
 OVERALL HEIGHT = 114"
 OVERALL WIDTH WITH RUB
 RAILS & FENDERETTES = 98"



THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



REAR EXTERIOR VIEW
 CHIEF XL-1/F550 CHASSIS

DATE: 8-25-22	DRAWING NO. CPQ# 6907
DWG. BT	REV. NR PFD-2

DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE
 OVERALL HEIGHT = 114"
 OVERALL LENGTH = 311"
 MODULE LENGTH = 173"



COMPARTMENT
O.S.S #1

CLEAR OPENING: 77.00h x 18.25w
 INSIDE DIM'S.: 86.75h x 24.50w x 20.75d
 'EZ-02 LIFT' SYSTEM ON THE DOOR
 (1) FIXED SHELF ABOVE EZ O2 LIFT THAT SEALS
 TO INSIDE OF DOOR.
 INVERTER, AIR HORN COMPRESSOR AND MISC LOCATED ABOVE SHELF
 AREA ABOVE SHELF TO BE VENTED THROUGH DOOR
 AREA ABOVE TO HAVE SOUND DEADENING MATERIAL

O.S.S #2

CLEAR OPENING: 44.25h x 43.00w
 INSIDE DIM'S.: 47.75h x 49.00w x 20.75d
 (2) ADJUSTABLE SHELF

O.S.S #3

CLEAR OPENING: 63.375h x 33.00w
 INSIDE DIM'S.: 65.25h x 38.50w x 20.75d
 UPPER AREA SHALLOW DEPTH; LOWER 36" FULL DEPTH
 (2) SCBA BRACKETS ON SHALLOW DEPTH WALL
 MOUNTED ON 6" WIDE TAPPING PLATE
 (1) ADJUSTABLE SHELF-FULL DEPTH LOWER
 DOORS TO OPEN AS WIDE AS POSSIBLE USING GAS SHOCK

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.

PERRYSBURG F.D.



STREETSIDE EXTERIOR VIEW
 CHIEF XL-I/F550 CHASSIS

DATE:
1-16-23
DWG.
TKD

REV.
A


DRAWING NO.
CPQ# 6907
PFD-3

DIMENSIONS FOR OVERALL HEIGHT AND LENGTH ARE APPROXIMATE

OVERALL HEIGHT = 114"

OVERALL LENGTH = 311"

MODULE LENGTH = 173"



COMPARTMENT

O.S.S #4

CLEAR OPENING: 73.00h x 13.25w
 INSIDE DIM'S: 82.75h x 17.00w x 20.75d
 FIXED DIVIDER 10" FROM FORWARD WALL
 (2) BACKBOARDS REAR OF DIVIDER
 (2) ADJ. SHELVES FORWARD OF DIVIDER

O.S.S #4A

CLEAR OPENING: 26.00h x 16.50w
 INSIDE DIMS: 29.00h x 23.00w x 20.75d
 MISC. STORAGE COMPARTMENT

O.S.S #5

CLEAR OPENING: 69.50h x 17.50w
 INSIDE DIM'S. 5A: SEE PARTITION INTERIOR VIEW
 INSIDE/OUTSIDE STORAGE WITH (3) ADJUSTABLE SHELVES

INSIDE DIM'S. 5B: 19.00h x 20.75w x 18.00d

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



CURBSIDE EXTERIOR VIEW
 CHIEF XL-I/F550 CHASSIS

DATE: 1-17-23
 DWG. TGD
 REV. A

DRAWING NO. CPQ# 6907
 PFD-4



COMPARTMENT

#1 DOOR OPENING: 16.25h x 20.75w
 INSIDE DIMS: 17.00h x 22.50w x 17.25d
 FIXED SHELF WITH TOP/BOTTOM DIVIDERS
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#2 DOOR OPENING: 16.25h x 30.25w
 INSIDE DIMS: 17.00h x 32.00w x 17.25d
 FIXED SHELF WITH TOP/BOTTOM DIVIDERS
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#2A DOOR OPENING: 16.25h x 30.25w
 INSIDE DIMS: 17.00h x 32.00w x 17.25d
 FIXED SHELF WITH TOP/BOTTOM DIVIDERS
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#3 DOOR OPENING: 26.68h x 32.87w
 INSIDE DIMS: 28.43h x 34.62w x 7.50d
 FIXED SHELF (6) ADJ. DIVIDERS TOP/BOTTOM
 SLIDING POLYCARBONATE DOORS
 TOTAL CABINET WEIGHT RATING = 25 lbs.

#5 - (2) PULL-OUT DRAWERS
 INSIDE DIMS: 3.50h x 14.00w x 11.50d
 FRONT-TO-BACK DIVIDERS IN EACH DRAWER
 LOCKING STAINLESS STEEL FLUSH PULL LATCHES
 TOTAL DRAWER WEIGHT RATING = 10 lbs. EACH

#6 DOOR OPENING: 4.75h x 30.25w
 INSIDE DIMS: 4.75h x 30.25w x 17.25d
 POLY DOOR WITH FRICTION HINGES
 CENTER SQUEEZE LATCH
 TOTAL CABINET WEIGHT RATING = 10 lbs.

VALOR SWIVEL SEAT WITH INTEGRAL CHILD SAFETY SEAT
 AND ADULT 4pt HARNESS, MOUNTED ON PEDESTAL BASE.
 SEAT MOVED 1.5" FORWARD FROM STANDARD POSITION
 AND CENTERED WITH THE COT.

#7 PULL-OUT SHARPS/WASTE DRAWER
 5-QUART TRASH / 1.5 QUART SHARPS
 DISPOSAL THROUGH COUNTERTOP
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 TOTAL DRAWER WEIGHT RATING = 10 lbs.

CABINETS #1, #2, AND #2A TO HAVE LIFT-UP
 RESTOCKING FRAMES
 CABINETS WITH INVENTORY CONTROL SYSTEM
 SOLID ACRYLIC COUNTERTOPS
 CABINETS TO BE ALUMINUM

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



STREETSIDE INTERIOR VIEW
 CHIEF XL-I

DATE:
 1-17-23
 DWG. REV.
 TKD A

DRAWING NO.
 CPQ# 6907
 PFD-5



COMPARTMENT

#1/#2 DOOR OPENING: 8.25h x 37.75w
 INSIDE DIMS: 6.75h x 37.75w x 10.25d
 ADJUSTABLE DIVIDERS IN EACH CABINET
 HINGED POLY DOORS WITH HOLD-OPENS
 CENTER SQUEEZE LATCHES
 43" MINIMUM HEADROOM BELOW THE CABINET
 TOTAL CABINET WEIGHT RATING = 10 lbs. EACH

#3 INSIDE DIM'S: 14.25h x 45.00w x 21.00d

#4 CABINET WITH SOLID ACRYLIC COUNTERTOP
 PULL-OUT DRAWER TOWARDS THE BENCH
 FRONT-TO-BACK DIVIDERS WITHIN
 INSIDE DIMS: 4.00h x 10.00w x 13.00d
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 TOTAL DRAWER WEIGHT RATING = 10 lbs.
 NOTCH BELOW DRAWER FOR SHARPS/WASTE DISPOSAL

#5 CABINET WITH SOLID ACRYLIC COUNTERTOP
 PULL-OUT DRAWER TOWARDS THE BENCH
 FRONT-TO-BACK DIVIDERS WITHIN
 INSIDE DIMS: 4.00h x 10.00w x 10.00d
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 DRAWER DOES NOT COMPLY WITH CN10

#6 PULL-OUT SHARPS/WASTE DRAWER TOWARDS THE AISLE
 8-qt. WASTE / 3.3-qt. SHARPS
 SHARPS/WASTE DROP FROM TOP WITH HINGED ACRYLIC
 LID. DRAWER OPENS TO ACCESS CONTAINERS.
 LOCKING STAINLESS STEEL FLUSH PULL LATCH
 TOTAL DRAWER WEIGHT RATING = 10 lbs.

SOLID ACRYLIC COUNTERTOPS
 CABINETS WITH INVENTORY CONTROL SYSTEM
 CABINETS TO BE ALUMINUM

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
 DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



CURBSIDE INTERIOR VIEW
 CHIEF XL-1

DATE: 1-17-23
 DWG. TKD
 REV. A

DRAWING NO. CPQ# 6907
 PFD-6




PERRYSBURG F.D.



PARTITION INTERIOR VIEW
CHIEF XL-I

DATE:
1-17-23
DWG. TKD
REV. A

DRAWING NO.
CPQ# 6907
PFD-7



THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.


PERRYSBURG F.D.



REAR INTERIOR VIEW
CHIEF XL-I

DATE:
1-17-23
DWG.
TKD

DRAWING NO.
CPQ# 6907
REV.
A
PFD-8



= (2) RECESSED CEILING IV HANGER LOCATIONS



= (1) CEILING OXYGEN OUTLET

* (2) ANTENNA BASES LOCATED OUTBOARD OF DOME LIGHTS WITH COAX SERVICE LOOP

STRYKER FLOOR PLATE AND 12V PRE-WIRE

MODULE WIDTH = 96"
MODULE LENGTH = 173"
MODULE HEAD ROOM = 74"

THIS DRAWING IS FOR REPRESENTATIONAL PURPOSES ONLY. DETAILS ARE CONCEPTUAL AND ARE SUBJECT TO CHANGE DURING DESIGN AND CONSTRUCTION
DIMENSIONS ARE APPROXIMATE UNLESS NOTED OTHERWISE TO MEET A SPECIFIC CUSTOMER NEED.

PERRYSBURG F.D.



FLOOR INTERIOR VIEW
CHIEF XL-I

DATE:
1-17-23
DWG.
TKD

REV.
A

DRAWING NO.
CPQ# 6907
PFD-9

RESOLUTION 8-2023

ADOPTING THE ORLEANS PARK MASTER PLAN

WHEREAS, the City of Perrysburg, Ohio strives to provide quality of life amenities to its residents and visitors alike; and,

WHEREAS, the City's extensive park system is one of the major components of providing quality of life opportunities within the city limits; and

WHEREAS, the City of Perrysburg prioritizes the continuing improvement and maintenance of features within the city's parks; and

WHEREAS, the city engaged The Edge Group in June of 2021 to create a Master Plan for Orleans Park. The Edge Group conducted several professional stakeholder meetings to gather input in order to create a draft Master Plan; and

WHEREAS, the draft Master Plan has been presented at public meetings before the Planning & Zoning Committee, Recreation Committee, and the Service Committee to allow for review and discussion.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. That the Master Plan for Orleans Park as created by The Edge Group and dated November 8, 2022, is hereby adopted by the City.

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Ordinance were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Resolution shall be in full force and effect at the earliest time permitted by law.

Res# 8-2023

President of Council

Mayor

PASSED: _____

ATTEST: _____

APPROVED: _____



Schematic Master Plan





PHASE 2 - Open Space & Playground



PHASE 3 - River Access Improvements



PHASE 4 - Connectivity Improvements



PHASE 5 - Pumptrack & Parking Lot



PHASE 6 - Multi-purpose Crew & Events Building



PHASE 7 - Multiuse Pavilion & Plaza

RESOLUTION 16-2023

A RESOLUTION DECLARING CERTAIN WOODLANDS PARK PLAYGROUND EQUIPMENT NO LONGER NEEDED FOR PUBLIC USE OR UNFIT FOR PUBLIC SERVICE

WHEREAS, Article III, Section III – 10.0 of the Perrysburg City Charter provides the City Council with the power to determine the method, manner, consideration and procedure for the purchase of property on behalf of the Municipality and the sale or disposal thereof; and,

WHEREAS, the city is no longer in need of certain playground equipment located at Woodlands Park; and,

WHEREAS, these items will be donated to Missions International of America; and,

WHEREAS, this legislation went before the Recreation Committee on February 28, 2023 and was approved 3-0 for advancement to City Council.

NOW, THEREFORE, BE IT RESOLVED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. The Council hereby authorizes the Mayor and Director of Finance to arrange for the donation of the playground equipment no longer deemed necessary for public use.

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Resolution were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Resolution shall be in full force and effect at the earliest time permitted by law.

Res 16-2023

President of Council

Mayor

PASSED _____

ATTEST: _____

APPROVED: _____

RESOLUTION 15-2023

**AUTHORIZING AN AGREEMENT WITH JONES AND HENRY ENGINEERS, LTD. IN AN AMOUNT NOT TO EXCEED SIXTY-THREE THOUSAND DOLLARS AND NO CENTS (\$63,000.00) FOR ENGINEERING AND DESIGN SERVICES FOR THE GRASSY CREEK INTERCEPTOR REHABILITATION PROJECT;
AND DECLARING AN EMERGENCY**

WHEREAS, the Department of Public Utilities has determined that the City of Perrysburg's Grassy Creek Interceptor is in need rehabilitation in order to address structural and I/I issues; and,

WHEREAS, the City of Perrysburg, Ohio, solicited proposals from engineering firms to complete task orders related to reducing flow to the manhole structure at Maple Street north of the Grassy Creek; and,

WHEREAS, Jones and Henry Engineers, LTD. was determined to be the best qualified firm to provide the services and, upon request, has provided a price proposal for the design services; and,

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. The Mayor and Director of Finance are authorized to enter into an agreement with Jones & Henry Engineers, LTD. in an amount not to exceed Sixty-Three Thousand Dollars and No Cents (\$63,000.00) for preliminary and detailed design for rehabilitating the Grassy Creek Interceptor, as defined in Exhibit A.

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Ordinance were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Resolution is hereby declared to be an emergency measure necessary for the immediate preservation of the public peace, health, and safety of the citizens of the City of Perrysburg, Wood County, Ohio, in order to address the structural issues in a timely manner and maintain timelines with the OEPA for the health of the City of Perrysburg, and shall be in full force and effect from and immediately after its passage and approval by the Mayor.

Res 15-2023

President of Council

Mayor

PASSED: _____

ATTEST: _____

APPROVED: _____

Task Order

In accordance with Paragraph 1.01 of the Agreement Between Owner and Engineer for Professional Services – Task Order Edition, dated September 2022 ("Agreement"), Owner and Engineer agree as follows:

1. Background Data

- a. Effective Date of Task Order: _____
- b. Owner: City of Perrysburg, Ohio
- c. Engineer: Jones & Henry Engineers, Ltd.
- d. Specific Project (title): Grassy Creek Interceptor Rehabilitation
- e. Specific Project (description): Proposal Attached

2. Services of Engineer

- A. The specific services to be provided or furnished by Engineer under this Task Order are:
 - ☒ as follows: Proposal for Grassy Creek Interceptor Rehabilitation dated January 11, 2023.
- B. Resident Project Representative (RPR) Services – Not used.
- C. Other Services – Not used.
- D. All of the services included above comprise Basic Services for purposes of Engineer's compensation under this Task Order.

3. Additional Services – Not used.

4. Owner's Responsibilities

- A. Owner shall have those responsibilities set forth in Article 2 of the Agreement and in Exhibit B, subject to the following: No modifications.

5. Task Order Schedule

- A. In addition to any schedule provisions provided in Exhibit A or elsewhere, the parties shall meet the following schedule: Scheduling will be coordinated with the Owner as described in Section 2.A.

6. Payments to Engineer

- A. Owner shall pay Engineer for services rendered under this Task Order as follows: Owner will be billed on a time and expense not to exceed bases as described in Section 2.A.

7. Consultants retained as of the Effective Date of the Task Order – None.

8. Other Modifications to Agreement and Exhibits – None.

9. Attachments: Proposal for Grassy Creek Interceptor Rehabilitation dated January 11, 2023.

10. Other Documents Incorporated by Reference – None.

11. Terms and Conditions

- A. Execution of this Task Order by Owner and Engineer shall make it subject to the terms and conditions of the Agreement (as modified above), which Agreement is incorporated by this reference. Engineer is authorized to begin performance upon its receipt of a copy of this Task Order signed by Owner.

The Effective Date of this Task Order is _____.

OWNER: City of Perrysburg, Ohio

By: _____

Print Name: _____


Title: _____

ENGINEER: Jones & Henry Engineers, Ltd.

By:  _____

Print Name: Bradley F. Lowery, P.E.

Title: President

By:  _____

Print Name: Ted Bennett, P.E.

Title: Principal / Treasurer

Engineer License or Firm's
Certificate No. (if required): _____

State of: Ohio

DESIGNATED REPRESENTATIVE FOR TASK ORDER:

Name: _____

Title: _____

Address: _____

E-Mail Address: _____

Phone: _____

DESIGNATED REPRESENTATIVE FOR TASK ORDER:

Name: Bradley F. Lowery, PE

Title: President

Address: 3103 Executive Parkway, Suite 300
Toledo, OH 43606

E-Mail Address: BLowery@JHEng.com

Phone: 567-661-0253

Task Order Form

EJCDC® E-505, Agreement Between Owner and Engineer for Professional Services – Task Order Edition.
Copyright © 2014 National Society of Professional Engineers, American Council of Engineering Companies,
and American Society of Civil Engineers. All rights reserved.



January 11, 2023

AJ Coleman, P.E.
Deputy-Director of Public Utilities
211 East Boundary Street
Perrysburg, OH 43551

Subject: City of Perrysburg, Ohio
Grassy Creek Interceptor Rehabilitation
Task Order #2

Mr. Coleman,

We are pleased to provide you with this proposal for engineering services associated with improvements to the Grassy Creek Interceptor. The improvements identified below were developed from our investigation of the subject sanitary sewers performed in 2021 and 2022. This proposal outlines the preliminary engineering and design engineering work to evaluate the sanitary sewer system along the limits described herein for rehabilitation to address structural and I/I Issues.

The original investigation and evaluation included sewers from Cherry St. to Sandusky Street. As part of the proposal process, the City has asked to include sewers along Grassy Creek Interceptor outside the limits of our original investigation area; Sandusky St. to E. Boundary and Cherry St. to Mulberry St.

The anticipated scope of improvements for the identified sewer main segments includes the following:

- a. Evaluation of approximately 1,345 feet of 12-inch sanitary sewer running along Grassy Creek from Sandusky St to East Boundary.
- b. Evaluation of approximately 2,375 feet of 12-inch sanitary sewer running along Grassy Creek from Cherry Street to Mulberry St.
- c. Rehabilitation of approximately 3,720 feet of 12-inch, 411 feet of 15-inch, 1,180 feet of 18-inch sewer and approximately 3,414 feet of 21-inch sewer running along Grassy Creek¹ from Cherry Street to Sandusky Street.
 1. Sewer mains will be rehabilitated using methods of joint grouting, sectional lining and / or cured-in-place pipe (CIPP) lining.
 2. Piping and pipe connections believed to be for bypassing the sewers will be eliminated and removed as part of the work.

¹ 4,100-feet of sewer main between Maple Street and Cherry Street was proposed to be rehabilitated in the AECOM Alternate 5. The scope of work proposed here includes additional pipe footage for inspection and rehabilitation.

3. All manholes with active leaks shall be rehabilitated with grouting.
4. All manholes within the project limits shall be rehabilitated with a spray applied coating.
- d. The rehabilitation method for the section of sewer from Cherry Street to Mulberry Street and Sandusky Street to E. Boundary Street shall be determined as part of the evaluation work described in Items a and b, above.

Scope of Preliminary Engineering Services²

1. Obtain and review the City's existing background information for the subject sewer mains. Helpful background information may include design or record plans, sewer tap records, construction reports, soils investigations, GIS data and any previous studies³.
2. Review CCTV inspection reports for approximately 2,375 feet of 12-inch sanitary sewer running along Grassy Creek from Cherry to W. Boundary Street and approximately 1,345 feet of 12-inch running from Sandusky Street to E. Boundary Street.

We anticipate the City will use Camtech for CCTV work to maintain file structure and video formatting from the previous inspection work to help streamline the bid document preparation³.

3. Locate manholes and conduct manhole inspections for the manholes located along the sewer from Cherry Street to Mulberry Street and Sandusky Street to E. Boundary Street.
4. Review CCTV inspection videos and reports for the subject sewer mains to ascertain existing conditions and note challenges for construction work.
5. Visit the site to review existing conditions visible on the surface or depicted on the topographic mapping supplied by the City relative to the contemplated sewer improvements.
6. Develop recommendations for rehabilitation or repairs to the subject sanitary sewers running along Grassy Creek from Cherry Street to Mulberry Street and Sandusky Street to E. Boundary Street.
7. Recommendations will be provided to the City in the form of a Memorandum with mapping to show the proposed locations and type of rehabilitation work proposed.

² Preliminary Engineering Services are proposed for the inspection and sewer condition assessment work required along the sections of sewer between Pine Street and Cherry Street & between Sandusky St. and E Boundary.

³ This section of sewer was not included in the CCTV work performed in 2022 on the Grassy Creek Sewer Interceptor.

Scope of Detail Design Engineering Services

1. Attend a project kick-off meeting to establish construction budget, scope of work, expected deliverables, and project schedule.
2. Prepared a project memorandum to summarize the construction budget, scope of work, deliverables, and design schedule.
3. Obtain background information for the work area in the form of record plans for roadway and utilities and information provided by utilities in response to an OUPS design ticket.
4. Design plans and contract documents will be submitted to the City via Dropbox at the 30%, 60% and 90% completion stage for review and discussion of the design development.
5. Develop recommendations for construction related coordination and sequencing. It is understood the work will require bypass pumping to convey wastewater flows around the sewer segments during the improvements. This step will include discussion of the project with sewer rehabilitation contractor(s) to examine constructability issues identified during this work⁴.
6. Prepare contract documents including design plans⁵ and specifications necessary for the public bidding of the improvements using the City's standards supplemented with Jones & Henry standard technical specifications and details modified to meet the specific requirements for this proposed work.
7. Prepare an Engineer's Opinion of Construction Cost for the proposed improvements. Unit pricing will be developed from our previous bid history information for similar work and from discussions with sewer rehabilitation contractors or vendors.
8. Assist the City with the bid process by aiding the City in answering bidder questions when requested to by the City. J&H will supply the City with Technical Specifications in PDF format along with an online georeferenced mapping database showing the proposed work scope. J&H will supply the City with a list of bid items and quantities in MS Excel format to assist the City with the preparation of the Bid Form. The City will handle the distribution of the bid package to bidders, receipt of bidder's questions and the review of bids. J&H will supply assistance to the City with answering questions of bidders. The City will issue any addendums required.

⁴ Flow monitoring data obtained by the City will be helpful for developing a bypass pumping strategy

⁵ Design plans will include only typical details to be inserted into the technical specifications. Large format plan and or profile sheets are not anticipated in the proposal.

Fee Schedule Breakdown

The following is a breakdown of the proposed engineering fee⁶ by tasks as described herein:

Preliminary Design Engineering Sanitary Sewer Evaluation – Cherry Street to Mulberry Street and Sandusky Street to E. Boundary Street	\$28,000.00
<u>Detailed Design Engineering - Sanitary Sewer Rehabilitation</u>	<u>\$35,000.00</u>
Total Fee	\$63,000.00

Contractual Reference

The project will be invoiced based on the schedule listed in Article 2, C2.01 of the Engineering Services Agreement. The budget for this work will not be exceeded without the prior authorization of an amendment by the City.

Exceptions and Clarifications

1. If during the performance of the services, additional services are determined to be needed or included scope items are not to be performed or are changed, we will provide amendment(s) for that additional work not included herein or work described in this scope of not performed or changed. Many of the excluded services described below can be added to the scope of services with an amendment to the agreement.
2. Work not specifically outlined in this proposal shall be considered work outside the scope of the proposal and the Engineer will be entitled to submit a request to amend the engineering fee subject to the approval of the Owner.
3. At this time, we have not included a topographic survey or a geotechnical engineering investigation of the project limits in our proposal.
4. Easement preparation has been excluded from this proposal as this service will be completed by the City.
5. The City will provide CCTV inspection videos of the sewer main to J&H for review. Any sewer main or lateral sewer cleaning and CCTV inspection will be performed inside of the scope of this proposal by a Contractor hired by J&H. We have based our proposal on the date when CCTV reports are received from the City.
6. We have not included the services of an environmental or historical / cultural consultant at this time given the plan to construct these improvements within a confined and previously disturbed site.
7. We have not included costs for preparing permit applications for Ohio EPA in the project fee. At the time this proposal is being prepared, we do not believe that a permit-to-install is required for sewer rehabilitation work.

⁶ The scope of work as defined in this document is offered for a lump sum price for each task identified.

8. Permit fees costs are excluded from this proposal as there are no anticipated needs for permits at this time. If later determined as required, permits will be prepared and submitted by the City.
9. Ensuring compliance with prevailing wage requirements shall be the responsibility of the City. For example, the review of certified payroll and onsite interviews for the Construction Contractor shall be performed by the City.

The engineering work only involves inspection, evaluation, and the design of improvements for sewer segments described herein.

Delivery Schedule

Currently, we anticipate the following delivery schedule for the proposed work:

Preliminary Design Commencement – At CCTV receipt from City
Preliminary and Detail Design – 60 days⁷
Advertise Project for Bids – 30 to 60 days from Design Completion
Open Bids/ Award Project – 30 days from Advertisement
Construction Commencement – Summer 2023⁸

Closing

We propose to do this work under our existing Task Order 2. If you find this Task Order acceptable, please return one signed copy of the Task Order agreement to my attention.

We appreciate the opportunity to present this proposal for your consideration. Please contact us if you need clarifications or additional information.

Sincerely,

JONES & HENRY ENGINEERS, LTD.



Theodore A. Bennett, P.E.
Director of Infrastructure

⁷ We have assumed CCTV documents are of sufficient quality and do not require reinspection.

⁸ Initial discussions with contractors indicate a preference to do this work in the dry months over the summer.

ORDINANCE 3-2023

AMENDING CODIFIED ORDINANCE 1050.10 OF THE CITY OF PERRYSBURG STREETS, UTILITIES AND PUBLIC SERVICE CODE LAST AMENDED BY ORDINANCE 125-2012 ON JULY 10, 2012

WHEREAS, City of Perrysburg, Ohio, Codified Ordinance 1050.10 explains the City's Wastewater/Septage Hauling Regulations; and,

WHEREAS, it is appropriate to amend and revise that Ordinance to update the associated fees with waste activated sludge disposal; and,

WHEREAS, the City's consultant, Fishbeck, completed a Wastewater Treatment Plant Capital Project Planning Report on May 27, 2021; and,

WHEREAS, said report recommended charging a fee per gallon of \$0.08 to \$0.12 per gallon for disposal; and,

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. Codified Ordinance 266.09-1, which currently reads as follows:

1050.10 WASTEWATER/SEPTAGE HAULING REGULATIONS.

All wastewater/septage haulers who engage in the business of picking up, transporting or disposing of wastewater or septage at the Perrysburg Wastewater Treatment Facility must comply with the following provisions:

(a) Definition of Terms.

(1) "Domestic waste or septage" means the liquid-borne waste resulting from normal domestic activities, including but not limited to cooking, washing, cleaning, bathing and disposal of sanitary waste.

(2) "Wastewater Treatment Facility" means the City of Perrysburg Water Pollution Control Division located at Number 1 West Boundary, Perrysburg, Ohio, 43551.

(3) "Domestic wastewater hauler" means any person or group of people who engage in the business of owning or operating vehicles for the purpose of transporting and disposing of domestic wastewater or septage from a sewage disposal system to another location for disposal.

(4) "Sewage disposal system" includes septic tanks, holding tanks, cesspools, privies or other equipment used to store, hold or treat waste of a domestic nature.

(b) Discharge Conditions.

(1) Any domestic wastewater hauler as defined in Section [1050.10\(a\)\(3\)](#) must register and receive a license from the Wastewater Treatment Facility. This license must be renewed annually and will expire December 31st of each year

(2) The City of Perrysburg Wastewater Treatment Facility will accept domestic wastewater or septage only as defined in Section [1050.10\(a\)\(1\)](#). Wastes from industrial processes, agricultural operations or wastes containing hazardous or toxic substances are specifically prohibited.

(3) Each domestic wastewater hauler shall comply with all applicable Water Pollution Control Division rules and regulations

(4) Violation of any or part of these conditions may result in the loss of discharge privileges. (Ord. 46-94. Passed 5-17-94.)

(c) Domestic waste haulers discharge rate per 1000 gallons shall be based on the percentage of plant operations versus total operations (Collection and Plant), multiplied by the minimum charge per billing quarter specified in Section [1050.02](#). This rate shall be approved by City Council by motion. (Ord. 125-2012. Passed 7-10-12.)

is hereby amended and revised to read:

1050.10 WASTEWATER/SEPTAGE WASTE ACTIVATED SLUDGE HAULING REGULATIONS.

All ~~wastewater/septage~~ **Community waste activated** haulers who engage in the business of picking up, transporting or disposing of ~~wastewater or septage~~ **waste activated sludge** at the Perrysburg Wastewater Treatment Facility must comply with the following provisions:

(a) Definition of Terms.

~~(1) "Domestic waste or septage" means the liquid-borne waste resulting from normal domestic activities, including but not limited to cooking, washing, cleaning, bathing and disposal of sanitary waste.~~

~~(2)~~ "Wastewater Treatment Facility" means the City of Perrysburg Water Pollution Control Division located at Number 1 West Boundary, Perrysburg, Ohio, 43551.

~~(3)~~ ~~"Domestic wastewater hauler"~~ **"Community waste activated sludge hauler"** means any person or group of people who engage in the business of owning or operating vehicles for the purpose of transporting and disposing of ~~domestic wastewater or septage~~ **waste activated sludge** from a sewage disposal system to another location for disposal **small communities**.

~~(4) "Sewage disposal system" includes septic tanks, holding tanks, cesspools, privies or other equipment used to store, hold or treat waste of a domestic nature.~~

(3) "Waste activated sludge" means biosolids generated through a Public Owned Treatment (POTW) facility.

(b) Discharge Conditions.

(1) Any ~~domestic wastewater~~ **Community waste activated sludge** hauler as defined in Section 1050.10(a)(~~3~~2) must register and receive a license from the Wastewater Treatment Facility. This license must be renewed annually and will expire December 31st of each year

(2) The City of Perrysburg Wastewater Treatment Facility will accept ~~domestic wastewater or septage~~ **waste activated sludge** only as defined in Section 1050.10(a)(~~1~~3). Wastes from industrial processes, agricultural operations or wastes containing hazardous or toxic substances are specifically prohibited. **The City of Perrysburg has the right to refuse waste activated sludge from a Community waste activated sludge hauler for any reason.**

(3) Each ~~domestic wastewater~~ **Community waste activated sludge** hauler shall comply with all applicable Water Pollution Control Division rules and regulations

(4) Violation of any or part of these conditions may result in the loss of discharge privileges. (Ord. 46-94. Passed 5-17-94.)

(c) ~~Domestic waste~~ **Community waste activated sludge** haulers ~~discharge rate per 1000 gallons shall be based on the percentage of plant operations versus total operations (Collection and Plant), multiplied by the minimum charge per billing quarter specified in Section 1050.02.~~ **shall be charged fees at the following rate per gallon discharged; \$0.08/gallon beginning April 1, 2023 and increasing by \$0.01 on April 1st of following years, up to a maximum of \$0.12/gallon. This rate shall be approved by City Council by motion. (Ord. 125-2012. Passed 7-10-12.)**

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Ordinance were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Ordinance shall be in full force and effect at the earliest time permitted by law.

President of Council

Mayor

PASSED: _____

ATTEST: _____

APPROVED: _____

TO: Mayor Mackin
President Smith
Members of City Council

FROM: Brian Thomas, City Engineer

RE: Resolution 28-2023

DATE: February 17, 2023



Subject Matter/Background

A Resolution authorizing awarding a bid and agreement with M&M FoamWorks LLC for the 2023 Sidewalk Program.

This project consists of repairing City sidewalks by lifting, leveling or grinding of any City sidewalk section that has been identified in need of repair or fully replacing sections that are beyond the repair specifications.

The Budget for this project is \$200,000.00 the engineering estimate from M&M Foam Works is \$200,000.00.

Financial Review

This purchase will come out of the 2023 budget, Account 4403-71541-55999.

Legal Review

Recommendation

If City Council is in agreement, a motion to waive the rules, waive the three readings, and pass this resolution as an emergency is appropriate. An emergency measure is requested because the bid opening for Sidewalks was February 17, 2023. Sixty days from February 17th is April 18, 2023 and the City needs the appropriate amount of time within that window to assign the bid and issue the agreement.

RESOLUTION 28-2023

A RESOLUTION AWARDING A BID AND AGREEMENT WITH M&M FOAMWORKS LLC IN AN AMOUNT NOT TO EXCEED TWO HUNDRED THOUSAND DOLLARS (\$200,000.00) FOR THE 2023 SIDEWALK PROGRAM AND DECLARING AN EMERGENCY

WHEREAS, the City of Perrysburg, Ohio solicited general contractor bids for its 2023 Sidewalk program, and the City issued a bid package which contained all relevant specifications and requirements for the program, which acknowledged that the City was authorized to waive minor irregularities in bidding which did not affect the fairness of the process, and pursuant to which the City would accept the lowest and best bid for the required work; and,

WHEREAS, M&M FoamWorks LLC provided the only bid for the sidewalk program, and it has the equipment, expertise, personnel, and knowledge to perform the required work; and,

WHEREAS, M&M FoamWorks LLC provided similar work to the City for its 2022, 2021 and 2020 Sidewalk Program; and,

NOW, THEREFORE, BE IT RESOLVED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. The City Council authorizes the award of the Bid for the 2023 Sidewalk Program to M&M FoamWorks LLC; and, the Mayor and Director of Finance are authorized to execute an Agreement with M&M FoamWorks LLC for the 2023 Sidewalk Program in an amount not to exceed Two Hundred Thousand Dollars (\$200,000) as outlined in the quote attached hereto and incorporated herein as Exhibit A.

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Resolution were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Resolution is hereby declared to be an emergency measure necessary for the immediate preservation of the public peace, health and safety of the citizens of the City of Perrysburg, Wood County, Ohio, to allow the City of Perrysburg to issue the bid and agreement within 60 days of the bid opening, and shall be in full force and effect from and immediately after its passage and approval by the Mayor.

President of Council

Mayor

PASSED: _____

ATTEST: _____

APPROVED: _____

General Info

Total:

\$35.00

Number	Description
2023 Sidewalk Repair Program	Perrysburg 2023 Sidewalk Program
Deadline	This project consists of repairing City sidewalks by lifting, leveling or grinding of any City sidewalk section that has been identified in need of repair or fully replacing sections that are beyond the repair specifications.
02/17/2023 02:00 PM EST	
Vendor	The project will be awarded to the lowest and most responsive bidder based on the Grand Total Price of the Base Bid.
FoamWork Solutions	
Submitted	As part of the 2022 Sidewalk Program approximately 39,000 sf of sidewalk was lifted (1,941 slabs), 2,600 sf of sidewalk was replaced (130 slabs) and 290 lf of sidewalk was ground down (70 slabs).
02/17/2023 09:04 AM EST	
Signed by	Engineering Estimate for the entire project: \$ 200,000
Jesse Miller Account Holder	
Jesse Miller	Allows zero unit prices and labor
Opened	Yes
02/17/2023 02:00 PM EST	Allows negative unit prices and labor
By	Yes
bthomas@ci.perrysburg.oh.us	

Attachment List

03_LegalNotice.pdf (121 KB)
Legal Advertisement

Scope.pdf (29.8 KB)
Proposed Scope

Sidewalk Criteria.pdf (50.4 KB)
Sidewalk Criteria

04_Insurance Requirements.pdf (115 KB)
Insurance Requirements

05_Specs_FY23.pdf (98.3 KB)
Specs FY23

07_InstructionstoBid-FY23.pdf (99.1 KB)
Instructions to Bid FY23

08_General Conditions.pdf (230 KB)
General Conditions

10_ContractForm_FY23.pdf (467 KB)
Contract Form FY23

18_Contractor Prevailing Wage Affidavit.pdf (94.8 KB)

19_wage rates and attachments.pdf (143 KB)

Proposal

BID

Proposal of: *

M&M FoamWorks LLC

(hereinafter called "Bidder"), organized and existing under the laws of the State of *

Ohio

doing business as *

"a corporation"

submitted to The City of Perrysburg (hereinafter called "Owner").

In compliance with the Advertisement for Bids, the Bidder hereby proposes to perform all Work for the construction of: *

Perrysburg 2023 Sidewalk Program

in strict accordance with the Contract Documents, within the time set forth therein, and accept as compensation therefore the sum of (in words): *

two hundred thousand

\$ (in currency): *

\$200,000.00

;however, the final amount will be controlled by the following unit prices and no payments shall exceed the total unit prices for said work. The Bidder agrees to accept the following unit prices for any addition or deductions caused by any change or alterations in the plans or specifications of the work.

By submission of this Bid, each Bidder certifies, and in the case of a joint Bid each party thereto certifies as to his own organization, that: 1) this Bid has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this Bid with any other Bidder or with any competitor; 2) they do not have an unresolved finding for recovery issued by the Auditor of State, in accordance with Section 9.24 of the Ohio Revised Code; and 3) they do not have an active exclusion shown in the Federal System of Award Management (SAM).

The Bidder hereby agrees to commence work under this contract on or before a date to be specified in the Notice to Proceed and to complete the project on/before the date specified. The Bidder further agrees to pay as liquidated damages, the sum of \$400 for each consecutive calendar day thereafter as provided in the General Conditions.

The Bidder acknowledges receipt of the following Addendum (Type N/A if not applicable):

Addenda #: *

NA

Addenda Date: *

NA

The Bidder acknowledges that 1) they have not received nor relied upon any representations or warranties of any nature whatsoever from the Owner, its officers, employees, or agents; 2) they are responsible for verifying the current prevailing wage rates and requirements according to Chapter 4114 of the Ohio Revised Code; 3) upon contract award, they will be required to sign an affidavit indicating whether or not they have delinquent personal property taxes on the General Tax List of Personal Property of Wood County, Ohio, in accordance with Section 5719.042 of the Ohio Revised Code.

In submitting this Bid, it is understood it may be withdrawn prior to the scheduled closing time for the receipt of bids, but that the Bidder may not withdraw its Bid after the actual opening thereof.

On acceptance of this Bid, the Bidder does hereby bind itself to enter into a written contract with the Owner within ten (10) days of the Notice of Award and give a Surety Bond amounting to 100% of the Contract.

Signature: *

Jesse Miller

Address: *

28848 E River Rd

Title: *

Owner

City, State, Zip: *

Perrysburg, Ohio 43551

Legal Name of Bidder: *

Jesse A Miller

Phone Number: *

(352) 279-7566

Fax Number: *

NA

E-mail Address *

jesse@fwslift.com

Base Bid

\$35.00

Item Code	Description	Quantity	Units	Unit Price	Extension
Alternates are not included in bid total.					
SP	Lift Sidewalk Section	1.00	Square Foot	\$5.00	\$5.00
SP	Grind Sidewalk Section	1.00	Linear Foot	\$15.00	\$15.00
SP	Remove and Replace Sidewalk Section	1.00	Square Foot	\$15.00	\$15.00
					Total: \$35.00

BID GUARANTEE AND PERFORMANCE BOND

KNOW ALL MEN BY THESE PRESENTS, That we, the undersigned *

NA

as Principal and *

NA

as Surety, are hereby held and firmly bound unto the City of Perrysburg as Obligee in the penal sum of the dollar amount of the bid submitted by the Principal to the Obligee on *

NA

to undertake the project known as: *

2023 Sidewalk Program

The penal sum referred to herein shall be the dollar amount of the Principal's bid to the Obligee, incorporating any additive or deductive alternate proposals made by the Principal on the date referred to above to the Obligee, which are accepted by the Obligee. In no case shall the penal sum exceed the amount of (in words):

twenty thousand dollars

\$ (in currency):

\$20,000.00

(If the above line is left blank, the penal sum shall be the full amount of Principal's bid, including alternates. Alternatively, if completed, the amount stated must not be less than the full amount of the Principal's bid including alternates, in dollars and cents. A percentage is not acceptable)

Bond Percentage

10.00%

Guarantee Method *

Certified Check or Paper Bid
Bond

Certified Check or Paper Bid Bond

Confirmation *

I have provided a Cashier's Check for 10.00% of the bid total amount and have uploaded the Consent of Surety to the Required Documents List at the bottom of the solicitation forms.

For the payment of the penal sum well and truly to be made, we hereby jointly and severally bind ourselves, our heirs, executors, administrators, successor, and assigns.

THE CONDITION OF THE ABOVE OBLIGATION IS SUCH, that whereas the above named Principal has submitted a bid on the above-referred project;

NOW, THEREFORE, if the Obligee accepts the bid of the Principal and the Principal fails to enter into a proper contract in accordance with the bid, plans, details, specifications, and bills of material; and in the event the Principal pays to the Obligee the difference not to exceed ten percent (10%) of the penalty hereof between the amount specified in the bid and such larger amount for which the Obligee may in good faith contract with the next lowest bidder to perform the work covered by the bid; or in the event that the Obligee does not award the contract to the next lowest bidder and resubmits the project for bidding, the Principal pays to the Obligee the difference not to exceed ten percent (10%) of the penalty hereof between the amount specified in the bid, or the costs, in connection with the resubmission, of printing new contract documents, required advertising, and printing and mailing notices to prospective bidders, whichever is less, that this obligation shall be null and void, otherwise to remain in full force and effect. If the Obligee accepts the bid of the Principal, and the Principal within ten days after the awarding of the contract, enters into a proper contract in accordance with the bid, plans, details, specifications, and bills of material, then said contract is made part of this bond the same as through set forth herein.

NOW ALSO, if the said Principal shall well and faithfully do and perform each and every condition of such contract; and shall pay all lawful claims of subcontractors, materialmen and laborers, for labor performed and materials furnished in the carrying forward, performing, or completing of said contract; we agreeing and assenting that this undertaking shall be for the benefit of any materialman or laborer having a just claim, as well as for the Obligee herein; then this obligation shall be void; otherwise the same shall in no event exceed the penal amount of this obligation as herein stated.

The said surety hereby stipulates and agrees that no modifications, omissions, or additions, in or to the terms of said contract or in or to the plans or specifications therefore shall in any wise affect the obligations of said Surety on this bond.

Principal: *

NA

By: *

NA

Title: *

NA

Surety: *

NA

By (Attorney-in-Fact): *

NA

Address: *

NA

Agent: *

NA

Address: *

NA

EXPERIENCE STATEMENT

Bidder shall provide information regarding similar work performed including, but not limited to, project name, description, location, and contact information, and any other details that will enable the City to assess the Contractor's capabilities, experience, skills, and financial standing with regard to this proposal. This statement shall also include information showing that the Bidder:

- maintains a permanent place of business.
- has adequate facilities and equipment available for the work under the proposed contract.
- has suitable financial means to meet obligations incidental to the proposed contract.
- has appropriate technical experience and possesses sufficient skills and experience.
- has the ability or resources available to make all repairs and adjustments that may be required on the equipment to be used under the proposed contract.

Response to the above: *

FoamWorks has a permanent place of business at 28848 E River Rd. Perrysburg OH. We have completed the City Sidewalk Programs for the City of Perrysburg in 2020, 2021 and 2022. We possess the skills and equipment to complete the 2023 Sidewalk program.

City of Perrysburg Sidewalk Programs (2022, 2021, 2020)
Rob Ross

Monarch Apartments
Nikki Moodt
15001 Brandt St.
Romulus MI 48174
(Completed sidewalk lifting, replacement and grinding an multiple apartment sites in Northwest Ohio)

If Bidder is Corporation, list Officers, type N/A if not applicable:

Name: *

Jesse Miller

Title: *

Owner

If Bidder is Partnership, list Members, type N/A if not applicable:

Name: *

Thomas McNamee

Title: *

Owner

LIST OF SUBCONTRACTORS

Bidder shall provide the names, addresses, and type of work (Item No. or Description, if applicable) which the Bidder proposes to subcontract under this Contract.

Name: *

Varga Custom Concrete, LLC

Address: *

259 S Manor Ct. Oak Harbor, OH 43449

Type of Work: *

Concrete removal and replacement

NONCOLLUSION AFFIDAVIT

STATE OF: *

Ohio

COUNTY OF: *

Wood

Bid Identification *

2023 Sidewalk Program

Bidder's Name *

Jesse Miller

, being first dually sworn, deposes and says that he is:

*

partner

Enter response if "other" was selected

of (company name): *

M&M FoamWorks LLC

the party making the foregoing bid; that such bid is not made in the interest of or on behalf of any undisclosed person, partnership, company, association, organization, or corporation; that such bid is genuine and not collusive or sham; that said bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid, and has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or that anyone shall refrain from bidding; that said bidder has not in any manner, directly or indirectly, sought by agreement, communication or conference with anyone to fix the bid price of said bidder or of any other bidder, or to fix any overhead, profit, or cost element of such bid price, or of that of any other bidder, or to secure any advantage against the public body awarding the contract or anyone interested in the proposed contract; that all statements contained in such bid are true; and further that said bidder has not, directly or indirectly submitted his bid price on any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, or paid and will not pay any fee in connection therewith, to any corporation, partnership, company, association, organization, bid depository, or to any member or agent thereof, or to any other individual except to such person or persons as have a partnership or other financial interest with said bidder in his general business.

Signed: *

Jesse Miller

Title: *

Owner

SUBSTITUTIONS/OPTIONS FORM

Optional: Vendor is not required to complete.

Any substitutions, deletions, additions, or deviations to the minimum specifications must be shown on this form and attached to the proposal forms in order to be considered as part of the bid. The City reserves the right to accept or reject any and all substitutions or optional bids. *

Will discount bid 3% if a performance bond is not required.

PREVAILING WAGE RESPONSIBILITIES

Keep full and accurate payroll records available for inspection for up to one (1) year following the completion of the project. Owners/partners must be shown on payrolls for any physical work they perform on the job.

- A. time records
- B. payroll records including canceled checks
- C. fringe benefit records including canceled check

Prevailing Wage Determination must be posted on the project site.

Supply Perrysburg Prevailing Wage Coordinator with dates of the life of the contract and a listing of all subcontractors to include the name, address, and telephone number of each.

Supply each employee with written notification of his assigned job classification, hourly prevailing wage rate and fringe payments, and identity of the Prevailing Wage Coordinator for the project.

Supply all subcontractors with any changes in the Prevailing Wage rates issued during the life of the project.

Out-of-State contractors must submit to the Ohio Secretary of State, the full name and address of their Statutory Agent in Ohio.

Submit certified payrolls starting no later two (2) weeks after the initial pay period. Insure all payrolls include the following:

- A. Employees full name, address, and social security number
- B. Work classification
 - (1) Be specific when listing laborers and operators
 - (2) Show level/year for all apprentices
- C. Hours worked on the project
 - (1) As of May 1, 1984, overtime is to be paid at not less than time and one-half for all hours worked in excess of forty (40) hours per week.
- D. Hourly rate of pay

Actual hourly rate paid employee for the time worked. Overtime hourly rate of not less than time and one-half the basic or regular rate paid is required under Chapter 4115. In addition to paying not less than the predetermined rate for the classification in which the employee works, the amounts predetermined as fringe benefits in the wage determination issued for the project, shall also be paid.

(Sample calculation: \$12.82 (base rate) x 1 1/2 = \$19.25 + \$1.70 (fringe payments) = \$20.93). Fringe payments must be entered in appropriate blocks on payroll forms when such fringes are paid to approved plans, funds, etc.

E. List all fringe benefits (if any) and amount per hour for each

(1) Hourly amount is to be based on 2080 hours per year.

F. Total deductions

G. Net pay for the pay period

Send a copy of Apprenticeship Agreement for each apprentice and a Final Affidavit to:

Perrysburg Prevailing Wage Coordinator

201 West Indiana Avenue

Perrysburg, OH 43551

(419) 872-7880

dbombrys@ci.perrysburg.oh.us

STATE OF OHIO PREVAILING WAGE RATES ARE AVAILABLE ON-LINE AT THE FOLLOWING WEBSITE:

Ohio Department of Commerce (<http://www.com.ohio.gov/laws/>)

Required Document List

Name	Omission Terms	Submitted File
Consent of Surety If providing a certified check or paper bid bond in lieu of Electronic Bid Bond	Electronically verifying Bid Bond	Bid Bond Check.pdf
Miscellaneous Attachment as Needed Miscellaneous Attachment	Omit if Not Needed	I am not enclosing this document because the omission terms have been met.
2 Required Documents		

AGREEMENT

This Agreement made this ____ day of _____, 2023 by and between the City of Perrysburg, by the Mayor in that behalf, duly authorized by Resolution 28-2023 of the Council of the City of Perrysburg adopted on March 7, 2023, and M&M Foamworks, LLC, of Perrysburg, OH, Contractor.

WITNESSETH: That the City of Perrysburg and the Contractor for the consideration state herein agree as follows:

SECTION 1: Scope of Work - The Contractor shall perform within the time stipulated, the Contract as herein defined of which this Agreement is a component part and everything required to be performed, and shall provide and furnish any and all of the labor, all materials together with all tools, expendable equipment and all utility and transportation services necessary to perform the Contract and complete in a workmanlike manner all the work covered by the Contract in connection with the Project identified as:

2023 SIDEWALK REPAIR PROGRAM

In strict conformity with the Plans and Specifications including any and all Addenda on file in the office of the City Engineering Department.

It is agreed that said labor, materials, tools, equipment and services shall be furnished and the Contract performed and completed under the direction and supervision and subject to the approval of the City Engineering Department.

SECTION 2: Performance Bond - The Contractor will furnish a performance bond of even date with these presents in the amount of 100% of the Contract price as determined by sum of items in the Bid Proposal.

SECTION 3: Unit Price - The City of Perrysburg shall pay to the Contractor as full consideration for

performance of the Contract an amount computed upon the basis of the quantity of work actually performed according to the specifications at the unit price and lump sum bids in the Bid.

It is understood that the quantities stated for the unit price bids are approximate only and are subject to either increase or decrease; and should the quantities of any of the items of the unit price work be increased, the Contractor shall perform the additional work at the unit prices as specified elsewhere herein, and should the quantities be decreased, payment will be made on actual quantities completed at the unit price as specified elsewhere herein, and the Contractor will make no claim for anticipated profits for any decrease in the quantities. Actual quantities will be determined upon completion of work.

SECTION 4: Guaranty - The Contractor shall guarantee all materials, equipment, and workmanship for a period of one (1) year from the date of Substantial Completion. Should faulty materials or workmanship occur during this period, the Contractor agrees to make the necessary corrections to the satisfaction of the City Engineering Department. The Performance Bond shall remain in full force and effect through the guarantee period.

SECTION 5: Component Parts of this Contract - The Contract entered into by the acceptance of the Contractor's bid and the signing of this Agreement consists of hereto attached documents and relative detailed plans and specifications, all of which are component parts of said Contract and fully a part thereof.

IN WITNESS WHEREOF, (THREE) identical counterparts of this Agreement, each of which shall, for all purposes, be deemed an original thereof, have been duly executed by the parties herein above named, on this day and year first above written.

MAYOR

IN WITNESS WHEREOF, The City of Perrysburg has caused to be affixed hereto its corporate name and seal by its Mayor thereunto duly authorized and the Contractor has hereunto subscribed its name at Perrysburg Ohio, on the day and year, first above mentioned.

CITY OF PERRYSBURG
STATE OF OHIO

MAYOR

CONTRACTOR

BY: _____

TITLE: _____

AFFIDAVIT
(Ohio Revised Code Section 5719.042)

STATE OF _____)
) ss:
_____ COUNTY)

The undersigned, _____, whether one or more than one; and if a corporation or partnership, its official who is authorized to bind the corporation with a signature, being first duly cautioned and sworn according to law, deposes and states that the undersigned is entering an Agreement with the City of Perrysburg, Ohio, an Ohio municipal corporation, pursuant to a competitive bid heretofore proposed and awarded.

MARK THE APPLICABLE STATEMENT BELOW

_____ It is further stated that the undersigned has no delinquent personal property taxes on the General Tax List of Personal Property of Wood County, Ohio.

_____ It is further stated that the undersigned has delinquent personal property taxes on the General Tax List of Personal Property of Wood County, Ohio; and the amount of such due and unpaid delinquent taxes and unpaid penalties and interest thereon are as follow:

Affiant says nothing further.

Signature

Sworn to before me and subscribed in my presence this _____ day of _____, 20____.

Notary Public

Commission Expires: _____

PERFORMANCE BOND

(To be completed if Bid Guaranty was a Certified Check, Cashier's Check, or Letter of Credit)

KNOW ALL MEN BY THESE PRESENTS, that we, the undersigned _____ as
Principal and _____ as Surety, are
hereby held and firmly bound unto the City of Perrysburg and the Ohio Department of Transportation
in the sum of _____ (\$_____) Dollars, for
the payment of which well and truly to be made, we hereby jointly and severally bind ourselves, our
heirs, executors, administrators, successors, and assigns.

THE CONDITION OF THE ABOVE OBLIGATION IS SUCH, that whereas the above named
Principal did on the _____ day of _____, 20____, enter into a Contract with
_____ which
said Contract is made a part of this bond the same as though set forth herein.

NOW, if the said Principal shall well and faithfully do and perform each and every condition of such
Contract and shall pay all lawful claims of sub-contractors, materialmen, and laborers, for labor
performed and materials furnished in the carrying forward, performing, or completing of said
Contract; we agreeing and asserting that this undertaking shall be for the benefit of any materialman
or laborer having a just claim, as well as for the Obliges herein; then this obligation shall be void,
otherwise the same shall remain in full force and effect; it being expressly understood and agreed that
the liability of the Surety for any and all claims hereunder shall in no event exceed the amount of this
obligation as herein stated.

PERFORMANCE BOND (CONTINUED)

The said Surety hereby stipulates and agrees that no modifications, omissions, or additions, in or to the items of said Contract or in or to the plans or specifications therefore shall in any wise affect the obligations of said Surety on this bond.

Signed and sealed this ____ day of _____, 20__.

PRINCIPAL: _____

BY: _____

TITLE: _____

SURETY: _____

BY: _____

ADDRESS: _____

AGENT: _____

AGENTS ADDRESS: _____

APPROVAL

The foregoing Bond and Contract is hereby approved this _____ day of _____ 20____.

MAYOR

APPROVAL OF OWNER'S LEGAL OFFICE

I hereby approve the form and execution of the foregoing Contract and Bond, this _____ day of _____ 20____.

CITY LAW DIRECTOR

RESOLUTION PASSED: _____

BID OPENING: _____ February 17, 2023 _____

CONTRACT AWARDED: _____

CORRECT, _____
MAYOR

The Contract Documents are hereby approved.

DATE

MAYOR

CERTIFICATE OF FISCAL OFFICER

I, Amber Rathburn, Finance Director of the City of Perrysburg, Wood County, Ohio hereby certify that the sum of Two Hundred Thousand Dollars and Zero Cents (\$200,000) is in the Treasury of the City of Perrysburg, or in process of collection and has been properly appropriated and credited to an appropriate Fund, for the purpose of this Contract.

DATE

FINANCE DIRECTOR

APPROPRIATION
RESOLUTION: _____

APPROPRIATION
RESOLUTION PASSED: _____

NOTICE TO PROCEED

TO: _____

DATE: _____

PROJECT: 2023 SIDEWALK REPAIR
PROGRAM

You are hereby notified to commence work in accordance with the Agreement dated
_____, 20__.

The Final Completion Date of all work is on or before November 1, 2023 as stated in the Bid documents.

CITY OF PERRYSBURG, OHIO
OWNER

BY: _____
MAYOR

ACCEPTANCE OF NOTICE:

Receipt of above NOTICE TO PROCEED is hereby acknowledged by:

_____, this _____ day of _____, 20__.

BY: _____ TITLE: _____

CONTRACTOR'S AFFIDAVIT

STATE OF _____)
)

COUNTY OF _____)

The undersigned, _____, hereby represents that on _____, _____ (Contractor) was awarded a Contract by the City of Perrysburg, in accordance with the terms and conditions of the Contract titled:

2023 SIDEWALK REPAIR PROGRAM

The undersigned further represents that the subject work has now been accomplished and the said Contract has now been completed.

The undersigned hereby warrants and certifies that all Contractor indebtedness arising by reason of the said Contract has been fully paid or satisfactorily secured; that all claims from sub-contractors and others for labor and material used in accomplishing the said Project, as well as all claims arising from the performance of the said Contract have been fully paid or satisfactorily settled; and that the undersigned has complied with Chapter 4115 of the Ohio Revised Code. The undersigned further agrees that, if any such claim should hereafter arise, Contractor shall assume responsibility for the same immediately upon request to do so by the City of Perrysburg.

The undersigned, for a valuable consideration, the receipt of which is hereby acknowledged, does further hereby waive, release and relinquish any and all claims or right of lien which the undersigned now has or may hereafter acquire upon the subject premises for labor and material used in accomplishing said Project owned by the City of Perrysburg.

This affidavit is freely and voluntarily given with full knowledge of the facts, on this _____ day of _____, 20____.

CONTRACTOR

BY: _____

TITLE: _____

Subscribed and sworn to before me this _____ day of _____, 20____.

(S E A L)

NOTARY PUBLIC

MY COMMISSION EXPIRES: _____

CITY OF PERRYSBURG
NOTICE OF COMMENCEMENT
(PURSUANT TO OHIO REVISED CODE SECTION NO. 1311.252)

STATE OF OHIO)
) ss:
COUNTY OF WOOD)

The City Administrator, being first duly sworn, hereby represents the following:

1. The Public Authority will be commencing a public improvement identified as follows: 2023 Sidewalk Repair Program
2. Tom Mackin is the Mayor of the City of Perrysburg, 201 West Indiana Ave., Perrysburg, OH 43551 (the "Public Authority").
3. The following lists the name, address and trade of each of the principal contractors working on this public improvement:

<u>NAME</u>	<u>GENERAL CONTRACTOR</u> <u>ADDRESS</u>	<u>TRADE</u>
FoamWorks Solutions	28848 E. River Rd., Perrysburg, OH 43551	Contractor

4. The Contract with the Principal Contractor was executed on the _____ day of _____, 2023.
5. The following lists the names and addresses of the sureties for all of those Principal Contractors:

<u>NAME OF SURETY</u>	<u>ADDRESS OF SURETY</u>
-----------------------	--------------------------

6. For the purpose of serving an Affidavit pursuant to Revised Code, Section 1311.26, service may be made upon the following representative of the Public Authority:

Mayor
201 West Indiana Ave.
Perrysburg, OH 43551

Sworn to before me and subscribed in my presence this _____ day of _____ 20____.

NOTARY PUBLIC
MY COMMISSION EXPIRES: _____

Perrysburg Income Tax Department
201 West Indiana Ave., Perrysburg, OH 43551
PH: 419-872-8035 FX: 419-872-8037

City Contractor Registration

1. Individual's or business' legal name _____

2. Trade name or doing business as _____

3. Mailing address _____
Street/PO Box City ST Zip

4. Fed. ID # _____ - _____ Soc. Sec. # _____ - _____ - _____
The Federal identification number under which W-2s would be reported

5. Phone _____ Contact person _____

6. Business type: Corporation _____ S Corporation _____ Partnership _____

Limited Partnership _____ LLC/LLP _____ Sole Proprietor or Single-member LLC _____

7. If not a calendar year, the fiscal period is: _____

8. Name of City Contract/Project: _____

What product or service will you provide for the City? _____

9. Will employees be working within the Perrysburg city limits? Yes ____ No ____

If yes, date you will begin withholding _____ / _____ date you will stop withholding _____ / _____ (if known)
Month Year Month Year

10. On the lines below, please provide the names, residence addresses, and titles of any other owners, partners, shareholders, or officers of the business.

_____ Name of owner, partner, shareholder, or officer	_____ Residence address
_____ Title	_____ City, State, Zip
_____ Name of owner, partner, shareholder, or officer	_____ Residence address
_____ Title	_____ City, State, Zip
_____ Name of owner, partner, shareholder, or officer	_____ Residence address
_____ Title	_____ City, State, Zip

_____ Signature of person who furnished this information	_____ Date
---	---------------

The Income Tax Department may request additional information including, but not limited to the Social Security numbers of the owners, partners, shareholders, or officers

ORDINANCE 8-2023

AMENDING THE CITY OF PERRYSBURG ADMINISTRATIVE CODE, CHAPTER 252, DEPARTMENT OF FINANCE

WHEREAS, City of Perrysburg, Ohio, Chapter 252 of the Administrative Code explains the duties of the Department of Finance; and,

WHEREAS, This ordinance, which applies to all construction projects in excess of \$50,000.00, will clarify the City's policy of awarding bids to the lowest, responsible, and responsive bidder. This will ensure that City projects that are funded by taxpayer dollars are completed by highly skilled workers who receive fair and competitive compensation for the work they perform. This includes the requirement that bidders provide healthcare and retirement benefits as a standard part of their compensation package and that workers are trained through a registered apprenticeship program. The bidders for construction projects will also be required to provide certain disclosures that will evidence that they are a responsible contractor. This ordinance will improve standards for working families and help ensure that publicly-funded projects are completed on time, under budget, and without delay.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF PERRYSBURG, WOOD COUNTY, OHIO:

SECTION 1. Chapter 252 of the Perrysburg Administrative Code, Department of Finance is amended by adding section 252.052 Determination of lowest and best bid for public improvement projects, which reads as follows:

252.052 DETERMINATION OF LOWEST AND BEST BID FOR PUBLIC IMPROVEMENT PROJECTS

Section 1. Determination of Lowest and Best Bid

- A. Council hereby requires that the Mayor, or designee, shall require all bidders of construction projects that exceed \$50,000 and require Council approval to submit to the designated city contracting official or a construction management or design build firm hired by the city, prior to submitting its bid, on a form required by the Department of Finance, proof, in accordance with the wage and fringe benefit requirements set forth in O.R.C § 4115.03 (E), that it meets the following standards:
 1. The bidder provides healthcare benefits or cash equivalent to its employees as a standard part of its compensation package and not only on projects subject to a state or federal prevailing wage requirement.

2. The bidder provides retirement benefits to its employees as a standard part of its compensation package and not only on projects subject to a state or federal prevailing wage requirement.
 3. The bidder participates in, sponsors, or exclusively hires graduates of a construction apprenticeship program certified and regulated by the State of Ohio or the U.S. Department of Labor.
- B. The failure of a bidder to comply with § 252.052 due to a lack of submission to the designated city contracting official, or construction management or design-build firm hired by the city, or the bidder's failure to affirmatively meet these standards, shall result in the bidder being considered non-responsive.
- C. A bidder that is awarded a contract under this section shall require its direct subcontractors to meet the requirements of § 252.052. Failure to ensure a subcontractor meets these requirements shall result in debarment from city contracts for a period of three (3) years.
- D. A subcontractor of contracts subject to § 252.052 shall require its direct subcontractors to meet the requirements of § 252.052. Failure to ensure a subcontractor meets this requirement shall result in debarment from city contracts for a period of three (3) years.
- E. Council hereby requires that the Mayor, or designee, shall require all bidders of construction projects subject to § 252.052 to provide evidence of the following to the designated city contracting official prior to the submission of its bid:
 1. Disclosure of any safety violations or settlement agreements between the bidder and the Occupational Safety & Health Administration or a state-based agency of similar jurisdiction during the ten (10) years prior to the submission of the bid.
 2. Disclosure of any violation of, or settlement agreement related to, any wage and hour laws at the local, state, or federal level during the ten (10) years prior the submission of the bid.
 3. Disclosure of an active and compliant Ohio Bureau of Workers Compensation insurance policy.
 4. Disclosure of any license issued by the Ohio Construction Industry Licensing Board that has been assigned to the bidder.
 5. Disclosure of any legal judgments against the bidder during the ten (10) years prior to the submission of the bid.

6. Disclosure of the relevant experience of the bidder, including the number of years in business under its present and any former business names.
 7. A complete listing of all the bidder's ongoing and completed public and private construction projects within the last three (3) years, including the nature and value of each contract and the name, address, and phone number or email address for a representative of the owner of each project.
 8. Disclosure of any state or federal Environmental Protection Agency complaints issued against the bidder during the ten (10) years prior to the submission of the bid.
 9. Description of the management experience of the bidder's project manager(s) and superintendent(s) who will be assigned to the project.
 10. If the bidder is a foreign corporation not incorporated under the laws of Ohio, a Certificate of Good Standing from the Ohio Secretary of State demonstrating its right to conduct business in the state of Ohio.
 11. Disclosure of any debarments of the bidder by any public authority in the United States during the ten (10) years prior to the submission of the bid.
 12. Description of the bidder's Occupational Safety and Health Administration compliant safety program.
 13. Disclosure of an active and compliant Ohio Drug Free Workplace policy issued by the State of Ohio.
 14. An estimate of the percentage of the bidder's workforce that resides in Wood, Hancock, Putnam, Henry, Lucas, Sandusky, and Ottawa Ohio counties.
 15. Disclosure of the percentage of the bidder's workforce that has five (5) or more years of experience within their trade.
- F. Any construction management or design-build firm hired by the city shall only contract with bidders that comply with the requirements of § 252.052.
- G. Any construction management or design-build firm hired by the city shall include § 252.052 as part of its prequalification requirements for prospective bidders.
- H. Contractors and subcontractors awarded a contract by a construction management or design-build firm on a city project shall comply with §

252.052.

- I. The City or a construction management or design-build firm hired by the City shall require a bidder to provide evidence of its compliance or the compliance of its subcontractors with § 252.052.

Section 2. Conflicting Ordinances. Any ordinance, provision of any ordinance, or resolution of the Perrysburg Municipal Code in conflict with the provisions of this ordinance is hereby repealed.

Section 3. Severability. The invalidity of any section, clause, sentence, or provision of this ordinance shall not affect the validity of any other part of this ordinance which can be given effect without such invalid part or parts.

Section 4. Effective Date. This ordinance shall be in full force and effect from and after its passage and approval by the Mayor of Perrysburg and publication as required by law.

SECTION 2. It is found and determined that all formal actions of Council concerning or relating to the passage of this Ordinance were adopted in an open meeting of the Council, and that all deliberations of this Council and any of its committees, that resulted in such formal actions, were in meetings open to the public in compliance with all legal requirements of the City of Perrysburg and the State of Ohio.

SECTION 3. This Ordinance shall be in full force and effect at the earliest time permitted by law.

Ord 8-2023

President of Council

Mayor

PASSED: _____

ATTEST: _____

APPROVED: _____